



**BOEING REALTY CORPORATION
FORMER C-6 FACILITY
LOS ANGELES, CALIFORNIA**

**TECHNICAL MEMORANDUM
QUARTERLY REPORT NO. 10
FIRST QUARTER 2004
INTERIM ACTION FULL-SCALE SVE SYSTEM**

To: Mr. Brian Mossman
Boeing Realty Corporation
3855 Lakewood Blvd.
Building 1A MC D001-0097
Long Beach, CA 90846

From: Haley & Aldrich, Inc.

Date: 26 April 2004

Subject: Quarterly Report No. 10, First Quarter 2004 Interim Action Full-Scale SVE System, Boeing Realty Corporation, Former C-6 Facility - Parcel A, Los Angeles, California

Haley & Aldrich, Inc. has prepared this technical memorandum to summarize soil vapor extraction (SVE) activities conducted at the former Boeing C-6 Facility (Site), in Los Angeles, California. One SVE system is currently present on the Site; an interim action full-scale SVE system in the former Building 1/36 area (Figure 1).

This technical memorandum summarizes system operations, field measurements, vapor sampling and analysis, mass removal, extraction well optimization, and planned future SVE activities for the Building 1/36 SVE system.

BACKGROUND

Laboratory results for soil samples collected in the former Building 1/36 area at the Site indicated the presence of VOCs at depth, requiring remediation to prevent possible impact to groundwater. Based on the results of the investigations, shallow occurrences of impacted soil (less than 12 feet below ground surface) were excavated and disposed of at an approved facility. SVE was recommended for the remediation of deep impacted soil. Haley & Aldrich was contracted by Boeing Realty Corporation (BRC) to install and operate first an SVE pilot test system, and later a full-scale SVE system. Appropriate workplans for the SVE systems were submitted and approved by the LARWQCB in June 2001, and December 2001, respectively.

FORMER BUILDING 1/36 OVERVIEW/CHRONOLOGY

Initial pilot testing commenced in the Building 1/36 area in July 2001 and continued until October 2001, when site grading began. Due to site grading conflicts, the SVE pilot test system was removed and the SVE wells were abandoned. At the end of November 2001, one dual-completion well (1-VEW-24A/B) was re-installed and the pilot test system was re-started on 13 December 2001. An additional forty-one dual and single completion wells (1-VEW-1 through 1-VEW-26) were installed during the month of January 2002 as part of the interim action SVE system implementation. The location of the Building 1/36 SVE system is shown in Figure 1. The well field layout, including well screen depths, is shown on Figure 2.

During the second quarter of 2002, the pilot test system was shut down and replaced with a 1,000 standard cubic feet per minute (scfm) SVE system. The Building 1/36 interim action SVE system currently consists of forty-three 3-inch diameter, single and dual-completion, SVE wells, a trailer-mounted 1,000 scfm blower system, three 8,000-lb granular activated carbon (GAC) vapor control vessels (primary, secondary, and stand-by), and associated piping. Haley & Aldrich began system operation on 15 May 2002.

On June 7, 2002, the system shut down due to apparent vandalism. The remediation progress prior to system shut down is shown in Figure 3 (3 June 2002). Exothermic reactions on the GAC beds continued until June 12, when upon discovery, the beds were quenched with water. Due to the GAC bed overheating, system damage occurred that required repair prior to re-start. GAC was removed from all three vessels on 13 June 2002.

In December 2002, twenty-five static vapor samples were collected from fourteen wells and the samples were submitted for laboratory analysis. These samples were collected in an effort to identify high concentrations of methyl ethyl ketone (MEK) prior to restarting the SVE system. MEK was reported above the method detection limit in 16 of the 25 samples collected in concentrations ranging from 0.0023 to 620 parts per million by volume (ppmv).

In March 2003 the installation of a GAC water quench system to control MEK heat generation was completed and the system was restarted on 11 March 2003. The procedures for restarting the SVE system included bringing the well field on-line in a phased approach. Wells that were not likely to yield MEK, (Category 3 wells), were brought on-line first, followed by wells that may yield MEK (Category 2 wells), brought on-line second, and wells that were likely to yield MEK (Category 1 wells), brought on-line last. Throughout this process, flow rates and VOC and MEK concentrations/mass loading rates were closely monitored.

These start-up procedures were completed on 15 April 2003, and the system was fully operational until it was temporarily deactivated on 22 May 2003, so that modifications could be made to the South Coast Air Quality Management District (SCAQMD) permit to facilitate greater flexibility in GAC changeout procedures. Once modifications were complete and approved by the SCAQMD, the system was reactivated on 27 June 2003. During the three remaining days in the quarter, similar staged well activation steps were taken to manage MEK loading on the carbon vessels to control heat generation and system shut-down.

During the third quarter of 2003, the system operated uninterrupted, as wells were added slowly to the influent stream, to limit carbon changeout frequency to a seven-day schedule. By 25 September 2003, vapors were being extracted from all 43 SVE wells.

In the fourth quarter of 2003, the system operated at a regular, controlled efficiency, by decreasing flow from wells exhibiting lower VOC concentrations and increasing flow from wells exhibiting higher VOC concentrations. At this time, the system carbon exchange frequency was still the limiting factor in the mass removal rate of VOCs at the site (ie, blower capacity below 100%).

At the end of the fourth quarter of 2003, the system was shut down for annual maintenance. Before system restart, early in the first quarter of 2004, diagnostic tests were performed to confirm system operational logic and evaluate the status of alarms, alarm responses, and the calibration of system instrumentation.

Diagnostic tests were completed and the system was restarted on 7 January 2004. On 21 January 2004, the system was deactivated due to adjacent excavation activities near the SVE system water supply line. The SVE well field remained inactive until nearby excavation activities were completed, when the system was restarted on 2 February 2004. In the first quarter of 2004, the system operated with 43 out of 43 wells actively under vacuum. The regular weekly carbon exchange frequency was maintained by increasing flow from wells exhibiting higher VOC concentrations while decreasing flow from periphery wells exhibiting lower VOC concentrations.

FIRST QUARTER 2004 BUILDING 1/36 SVE OPERATION SUMMARY

Days of Operations	71
Available Days of Operation	91
Operational Time (%) (1 January to 31 March)	78%
Mass Removed during Period (lbs)	4,043
Cumulative Mass Removed (lbs) (July '01-Mar '04)	27,445

OPERATIONS INFORMATION

Operational data and VOC mass removal for the SVE unit are tabulated and shown graphically in Attachment 1. During the first quarter, 43 out of 43 SVE wells were actively under vacuum. Total days of SVE system operation for this period were 71 of 91.

Three shut-down events occurred during the quarter. The first event occurred in conjunction with a year-end shut down and system diagnostic that began on 23 December 2003. This shut down period continued until 5 January 2004, during which system components, alarms, alarm responses, and equipment were tested. After the successful completion of diagnostic testing, the blower was restarted on 7 January 2004 and the well field was brought back online on 8 January 2004.

The second system shut-down occurred during the excavation of arsenic-impacted soils on the adjacent property in late January 2004. This adjacent excavation was located near the SVE system compound and

associated water supply line. Although the blower remained operational with full atmospheric air dilution, the entire well field was deactivated on 21 January 2004. Following the completion of the nearby excavation activities, the well field was reactivated on 2 February 2004.

The third system shut down occurred on 29 March 2004, due to a momentary loss of signal from a vessel thermocouple. The blower was automatically turned off by the system programmable logic controller and remained off through the end of March 2004.

The result of these three down time events equates to an up-time of approximately 78 percent for the quarter, which is shown in Attachment 1, Graph 1. A system maintenance log is also provided in Attachment 1.

The monthly and cumulative mass of VOCs removed by the Building 1/36 SVE system is shown in Attachment 1, Graph 3. Since 2 July 2001 (initial small-scale pilot test start-up) approximately 27,445 lbs. of VOCs have been extracted during approximately 11,207 hours of SVE unit operation. Operation of the SVE system is currently in compliance with the site-specific permit from the SCAQMD.

FIELD MEASUREMENTS

VOC concentrations were measured with a photoionization detector (PID) calibrated to 100 parts per million by volume (ppmv) hexane, as per the SCAQMD permit requirements, at the undiluted inlet, diluted inlet, between the GAC vessels, and at the exhaust stack. Flowrates were measured with a direct flow meter or by hand-held Veloci-Cal™ meter. Additional measurements were collected during operation including vacuum readings at each extraction well, temperatures at the GAC vessels, and blower exhaust temperature. The combined well field influent VOC measurements are provided in Attachment 1, Table I and plotted in Attachment 1, Graph 2. Field measurements of flow, VOC concentration, and vacuum measured at each well head are provided in Attachment 1, Table III.

VAPOR SAMPLING AND ANALYSIS

For this period, a total of 9 vapor samples were collected from the inlet, mid-point, and exhaust of the process air stream and were delivered to a state-certified laboratory for analysis. These samples were collected for SCAQMD permit compliance as well as system performance evaluation. The vapor samples were collected using a Tedlar bag in a vacuum case. Laboratory analyses were conducted on these vapor grab samples using EPA Method 8260B/TO-14A. The laboratory results of the influent vapor sampling are summarized in Attachment 1, Table II.

Based on the results of the laboratory analysis of vapor grab samples, maximum undiluted inlet VOC concentrations in parts per billion by volume (ppbv) for the period are as follows:

■ 1,1,1-Trichloroethane	210,000 ppbv
■ Toluene	72,000 ppbv
■ 2-Butanone (MEK)	50,000 ppbv
■ Trichloroethene (TCE)	4,800 ppbv

■ 1,1-Dichloroethene (1,1-DCE)	4,500 ppbv
■ Xylene	3,100 ppbv
■ Acetone	1,500 ppbv
■ Ethyl-benzene	160 ppbv
■ 1,1,2-Trichloroethane	94 ppbv
■ 1,1-Dichloroethane	72 ppbv

In addition to regular compliance samples at the treatment system, selected wells and the system undiluted influent were sampled and analyzed for EPA Method 8260B/TO-14A on 26 February 2004. These samples were gathered to update the extent and concentrations of MEK in the VOC plume.

Figure 3 depicts past well field VOC concentrations, as well as more recent field screening results and contours. Well field MEK concentration contours, from December 2002, April 2003, and February 2004 are depicted on Figure 4 and the data are included in Attachment 1, Table IV.

EXTRACTION WELL OPTIMIZATION

Due to carbon exchange restraints (targeting scheduled breakthroughs at seven-day intervals), total system influent concentrations have generally been kept below 1,000 ppmv. At this time, non-VOC producing wells near the perimeter of the plume have been reduced in flow to approximately 5 scfm. Conversely, high VOC producing wells, such as 1-VEW-23B and 1-VEW-21B have been opened fully. These adjustments were made to keep influent concentrations at or near 1,000 ppmv. These adjustments maximized VOC mass removal while maintaining a weekly carbon breakthrough schedule. This optimization process continued to successfully reduce the peripheral soil vapor concentrations surrounding the core wells (1-VEW-23B and 1-VEW-21B).

ACTIVITIES FOR NEXT QUARTER

During the second quarter of 2004, well optimization adjustments will continue in order to maximize mass removal while maintaining a weekly breakthrough schedule. While optimizing the system, consideration will be given to GAC vessel temperature, safe MEK loading rates, and carbon breakthrough schedule.

A 2004 Second Quarter Report summarizing activities during the period April 2004 through June 2004 will be prepared and submitted to BRC in July 2004.

We appreciate the opportunity to provide environmental consulting services on this project. Please do not hesitate to call if you have any questions or comments.

Sincerely yours,
HALEY & ALDRICH, INC.

Richard M. Farson, PE
Senior Engineer

Scott P. Zachary
Project Manager

c: John Scott, Boeing
Scott Zachary, Haley & Aldrich
Richard Farson, Haley & Aldrich
File




Attachments:

- Figure 1 – SVE System Locations Building 1/36 and Building 2
- Figure 2 – Building 1/36 SVE Well Field Layout
- Figure 3 – Building 1/36 Wellhead VOC Concentration Contours
- Figure 4 – Building 1/36 Wellhead MEK Concentration Contours
- Appendix A – Building 1/36 SVE Operational Data


G:\Projects\ENVIRONMENTAL\28997_Boeing C-6 2002 SVE\Quarterly Performance Presentations-2004\1st quarter 2004\FINAL Tech Memo Qrt Rpt No_10.doc

FIGURES



NOTE:

ALL BUILDINGS SHOWN IN THIS
FIGURE WERE PREVIOUSLY REMOVED
DURING DEMOLITION ACTIVITIES.



ALL DIMENSIONS AND LOCATIONS APPROXIMATE

SOURCE OF BASEMAP: KENNEDY JENKS CONSULTANTS, 2000, SAMPLING AND ANALYSIS PLAN,
BOEING REALTY CORPORATION'S C-6 FACILITY, PARCEL C, LOS ANGELES, CA, AUGUST 18, 2000.



BOEING REALTY CORPORATION
FORMER C-6 FACILITY
LOS ANGELES, CALIFORNIA

**SVE SYSTEM LOCATIONS
BUILDING 1/36**


UNDERGROUND
ENGINEERING &
ENVIRONMENTAL
SOLUTIONS

SCALE: AS SHOWN


FIGURE 1

APRIL 2004

BOE-C6-0009351



LEGEND





BOEING REALTY CORPORATION
FORMER C-6 FACILITY
LOS ANGELES, CALIFORNIA

BUILDING 1/36 WELL FIELD LAYOUT


UNDERGROUND
ENGINEERING &
ENVIRONMENTAL
SOLUTIONS

SCALE: AS SHOWN

FIGURE 2



Legend



21A-15
21B-4801



Note:
VOC concentrations based on field measurements
using a Flame Ionization Detector (FID) calibrated to
100 ppm Hexane for the year 2002 data, and a Photo
Ionization Detector (PID) calibrated to 100 ppm Hexane
for the years 2003 and 2004 data.

0 75 150 300
Feet



UNDERGROUND
ENGINEERING &
ENVIRONMENTAL
SOLUTIONS



BOEING REALTY COMPANY
FORMER C-6 FACILITY
LOS ANGELES, CALIFORNIA

BUILDING 1/36
WELLHEAD VOC
CONCENTRATION CONTOURS

SCALE AS SHOWN

FIGURE 3

APRIL 2004



BOEING REALTY COMPANY
FORMER C-6 FACILITY
LOS ANGELES, CALIFORNIA

UNDERGROUND
ENGINEERING &
ENVIRONMENTAL
SOLUTIONS

FIGURE 4
BUILDING 1/36 WELLHEAD MEK CONCENTRATION CONTOURS
SCALE AS SHOWN
APRIL 2004

Appendix A
Building 1/36 SVE Operational Data

TABLE I - TREATMENT SYSTEM FIELD DATA

Site Name: BRC Former C-6 Facility
Location: Los Angeles, California
System: Building 1/36 Interim Action SVE System

DATE	HOUR METER	TIME	INLET	PRIMARY VESSEL TEMP (deg F)	SECONDARY VESSEL MAX TEMP (deg F)	UNDILUTED INLET FLOW RATE (scfm)	DILUTED INLET FLOW RATE (1) (scfm)	VACUUM (inches of H2O)	DILUTED INFLUENT FID (2,3) (ppmv)	MID POINT CARBON FID (2,3) (ppmv)	EFFLUENT CARBON FID (ppmv)	COMMENTS
Pilot system removed. 1000 scfm unit installed.												
05/15/02	5	16:50	NA	NA	NA	985	995	96	375 *	0.1 *	0.7 *	
05/16/02	31	17:45	NA	NA	NA	1040	1060	91	320 *	14.2 *	0.2 *	
05/17/02	55	17:20	NA	NA	NA	915	985	69	310 *	0.0 *	0.1 *	
05/18/02	76	14:40	NA	NA	NA	840	870	90	845	45.0	0.0	
05/19/02	97	11:40	NA	NA	NA	875	905	88	780	18.0	10.0	
05/20/02	119	10:00	NA	NA	NA	900	905	88	725	14.0	12.0	
05/21/02	143	14:50	NA	NA	NA	935	975	72	160	34.0	7.5	GAC Changeout
05/22/02	169	17:10	NA	NA	NA	925	950	77	330	9.8	7.0	
05/23/02	190	14:35	NA	NA	NA	925	815	62	355	9.8	9.0	
05/24/02	208	8:41	NA	NA	NA	403	400	61	1,250	13.0	12.0	
05/25/02	236	12:40	NA	NA	NA	383	377	60	850	10.5	9.0	
05/26/02	259	11:20	NA	NA	NA	392	364	61	1,000	13.0	11.8	
05/27/02	283	11:24	NA	NA	NA	402	368	60	1,000	25.0	12.0	GAC Changeout
05/29/02	286	17:30	NA	NA	NA	830	795	95	245 *	0.0 *	0.0 *	
06/03/02	400	10:00	NA	NA	NA	780	760	109	350	60.0	7.5	Primary vessel switched
Carbon bed overheating. System shutdown 6/7/02.												
Start up procedures from 3/12/03 through 3/31/03.												
03/12/03	NM	16:50	NM	92.1	91.5	500	500	55	670	3.0	0.0 *	
03/13/03	NM	11:00	NM	NM	NM	700	700	NM	666	10.0	NM	
03/15/03	NM	NM	NM	NM	NM	645	645	NM	911	4.0	0.0	
03/16/03	NM	NM	NM	NM	NM	720	720	NM	1,325	11.0	0.0	
03/17/03	NM	NM	NM	89.8	9034	710	710	60	1,342	8.0	0.0	
03/24/03	NM	9:00	NM	NM	NM	720	720	65	395	140.0	0.0	Primary vessel switched
03/24/03	NM	9:00	NM	NM	NM	720	720	65	395	140.0	0.0	
Breakthrough on carbon vessel on 3/31/03. System shut down for carbon regeneration.												
4/1/2003	584	14:50	.99	87.5	91.7	755	755	60	342	1.7	.0	
4/3/2003	630.8	15:10**	104	.83	.85	775	775	60	273	0.6	0.0	
4/4/2003	654.8	NM**	100	.82	.84	770	770	55	293	0.9	0.0	
4/7/2003	725.7	15:02	106	.90	.93	760	760	55	297	1.5	0.0	
4/8/2003	749.3	14:40	.94	.95	100	770	770	50	297	2.5	0.0	
4/9/2003	760.4	.940	102	.86	.91	780	780	50	358	3	0.0	
4/10/2003	780.7	8:55**	.96	.86	.91	860	860	57	404	3.2	0.0	
4/11/2003	821.3	16:30	.98	.82	.87	860	860	50	1,950	28.9	0.0	Primary vessel switched
4/15/2003	909	.751	.92	.78	.86	875	835	63	1,476	11	0.0	Primary vessel switched
4/16/2003	941.5	16:20**	106	.88	.89	860	800	59	1,350	5	0.0	
4/18/2003	988.7	15:30**	NM	NM	NM	850	850	NM	1,256	8.3	0.0	
4/21/2003	1053.7	8:30	.88	.76	.80	855	845	60	1,230	60	0.0	
4/24/2003	1127.3	10:00	104	.79	.82	860	850	60	1,100	6	0.0	
4/29/2003	1245.8	8:30**	102	.87	.87	870	850	60	1,190	51	0.0	Primary vessel switched
5/5/2003	1398.2	8:00	.75	.76	.83	800	780	50	1,423	105	11.0	
5/8/2003	1464	15:30	.81	.89	.89	NM	NM	57	1,422	8.3	5.4	Primary vessel switched
5/12/2003	1553	14:00	.84	.87	.88	910	860	49	912	35	10.0	Primary vessel switched
5/19/2003	1728	15:00	.92	.84	.945	992	47	870	870	56	2.0	Primary vessel switched
System shut down for SCACMD permit modifications on 5/22/03. System restarted on 6/27/03.												
6/27/2003	1797	16:00	.87	.90	.95	760	991	NM	294	6	0.0	No change in Primary
6/30/2003	1863	10:00	.94	.93	.98	845	835	85	150	32	2.5	Primary vessel switched
7/1/2003	1885	8:00	.86	.87	.89	785	665	85	1,031	15	3.0	No change in Primary
7/2/2003	1894	13:30	.99	.101	.106	725	715	80	260	15	3.0	Primary vessel switched
7/3/2003	1913	8:00	.98	.98	.100	732	720	85	318	4.5	2.0	No change in Primary
7/7/2003	2010	9:00	.83	.86	.89	755	710	87	310	3.6	2.7	No change in Primary

TABLE I - TREATMENT SYSTEM FIELD DATA

Site Name: BRC Former C-6 Facility
Location: Los Angeles, California
System: Building 1/36 Interim Action SVE System

DATE	HOUR METER	TIME	INLET	PRIMARY VESSEL TEMP (deg F)	SECONDARY VESSEL MAX TEMP (deg F)	UNDILUTED INLET FLOW RATE (scfm)	DILUTED INLET FLOW RATE (1) (scfm)	VACUUM (inches of H2O)	DILUTED INFLUENT FID (2,3) (ppmv)	MID POINT CARBON FID (2,3) (ppmv)	EFFLUENT CARBON FID (ppmv)	COMMENTS
7/10/2003	2082	9:00	90	88	91	760	750	90	372	4.9	3.1	No change in Primary
7/14/2003	2179	9:20	94	88	91	780	695	90	371	12.9	3.2	No change in Primary
7/18/2003	2274	8:42	86	88	89	675	670	89	424	28.5	3.3	Primary vessel switched
7/24/2003	2418	9:00	87	87	89	810	775	84	446	3.7	0.0	No change in Primary
7/31/2003	2585	8:00	97	89	90	810	770	72	441	35	2.4	Primary vessel switched
8/7/2003	2754	9:30	89	86	87	885	770	75	415	20.9	2.7	Primary vessel switched
8/14/2003	2921	8:00	85	87	87	840	770	75	323	11.4	2.4	No change in Primary
8/14/2003	2921	8:00	NM	NM	NM	NM	NM	NM	NM	NM	NM	Lowered influent to 223
8/21/2003	3090	8:30	90	89	93	800	735	78	446	29.1	4.1	Primary vessel switched
8/21/2003	3097	15:30	NM	NM	NM	835	NM	NM	NM	NM	NM	No change in Primary
8/28/2003	3255	6:45	79	82	83	885	775	73	583	20.5	1.3	Primary vessel switched
9/4/2003	3423	6:50	NA	81	87	870	815	65	430	1.6	0.0	No change in Primary
9/4/2003	3429	13:45	NM	NM	NM	865	780	60	1031	12	4.0	After Well Changes
9/5/2003	3451	11:30	NM	NM	NM	815	800	63	159	10.4	3.2	No change in Primary
9/6/2003	3476	11:00	109	96	94	800	770	68	148	16.3	3.3	No change in Primary
9/11/2003	3591	6:30	95	91	101	855	790	73	290	17.3	0.4	Primary vessel switched
System shut down on 12/23/03 due to OAL Vessel breach. System restarted on 1/1/2004.												
9/18/2003	3759	7:00	103	96	103	895	840	70	487	13.8	2.2	Primary vessel switched
9/25/2003	3927	7:00	82	83	85	925	895	71	975	15.9	0.0	Primary vessel switched
10/2/2003	4095	6:30	81	82	84	930	875	65	786	10.9	0.0	No change in Primary
10/9/2003	4267	9:00	84	81	80	865	865	65	655	144	3.5	Primary vessel switched
10/16/2003	4431	6:00	79	79	81	1000	910	64	975	26.5	0.4	Primary vessel switched
10/23/2003	4599	6:00	76	76	76	915	890	63	902	8.1	0.0	No change in Primary
10/30/2003	4608	6:00	74	103	90	830	830	74	1,157	8.6	1.5	No change in Primary
11/5/2003	4706	10:00	72	71	74	850	845	79	620	6	1.0	Primary vessel switched
11/6/2003	4777	9:00	77	83	80	900	885	76	903	8.8	2.3	No change in Primary
11/10/2003	4873	9:00	81	81	73	NM	NM	NM	NM	NM	NM	No change in Primary
11/13/2003	4879	9:00	NM	NM	NM	NM	NM	NM	NM	NM	NM	No change in Primary
11/20/2003	4902	10:00	77	75	73	885	810	80	1,568	22.2	4.9	Primary vessel switched
11/26/2003	5043	7:00	64	63	63	960	835	84	371	12.5	2.8	No change in Primary
12/1/2003	5165	9:30	71	68	61	910	850	74	374	4.8	1.8	No change in Primary
12/4/2003	5237	9:30	72	70	67	830	825	80	1,038	25.1	5.7	Primary vessel switched
12/11/2003	5404	8:30	75	72	69	940	850	83	1,076	32	3.8	Primary vessel switched
12/18/2003	5571	8:00	69	66	70	930	840	81	1,067	28.6	0.0	Primary vessel switched
12/23/2003	5690	6:00	71	70	77	905	830	80	763	7.9	1.7	No change in Primary
System shut down on 12/23/03 for annual maintenance & testing												
1/5/2004	5694	9:00	49	58	60	NM	NM	NM	NM	6.4	2.50	System Restarted
1/7/2004	5758	8:00	84	80	75	NM	NM	NM	NM	NM	NM	Annual system check
1/8/2004	5763	9:00	87	94	88	905	850	78	926	0.70	No change in Primary	
1/12/2004	5860	9:30	74	74	75	NM	NM	NM	NM	NM	NM	No change in Primary
1/15/2004	5931	9:00	81	80	75	860	800	83	692	23.4	0.70	Primary vessel switched
1/22/2004	6059	9:00	86	68	63	NM	NM	NM	NM	1.9	1.10	No change in Primary
1/29/2004	6271	13:00	85	78	73	920	850	73	1,220	12.7	1.70	No change in Primary
2/2/2004	6363	9:00	77	72	66	890	860	76	1,227	10.3	0.00	No change in Primary
2/3/2004	6388	10:00	NM	NM	NM	NM	NM	NM	NM	NM	NM	No change in Primary
2/5/2004	6435	9:00	76	72	68	875	845	82	838	20.3	1.20	Primary vessel switched
2/12/2004	6603	9:00	83	81	79	865	825	77	866	37	10.10	Primary vessel switched
2/19/2004	6771	9:00	71	70	72	890	735	76	656	5.5	0.20	No change in Primary
2/26/2004	6939	9:30	76	76	73	815	770	86	833	35	0.30	Primary vessel switched
3/4/2004	7105	7:00	72	70	72	880	865	83	1,006	43	7.60	Primary vessel switched
3/11/2004	7272	6:30	71	72	76	785	775	95	1,045	25.9	5.60	Primary vessel switched
3/18/2004	7442	8:30	79	78	82	765	735	91	770	4.6	0.00	No change in Primary
3/25/2004	7608	6:00	73	73	74	810	770	90	1,223	58	0.00	Primary vessel switched
3/29/2004	7703	9:00	103	90	89	NM	NM	NM	NM	NM	NM	No change in Primary

TABLE I - TREATMENT SYSTEM FIELD DATA

Site Name: BRC Former C-6 Facility
Location: Los Angeles, California
System: Building 1/36 Interim Action SVE System

DATE	HOUR METER	TIME	INLET	PRIMARY VESSEL TEMP. (deg F)	SECONDARY VESSEL MAX TEMP (deg F)	UNDILUTED INLET FLOW RATE (scfm)	DILUTED INLET FLOW RATE (1) (scfm)	VACUUM (inches of H ₂ O)	DILUTED INFLUENT FID (2,3) (ppmv)	MID POINT CARBON FID (2,3) (ppmv)	EFFLUENT CARBON FID (ppmv)	COMMENTS
------	------------	------	-------	---------------------------------	--------------------------------------	-------------------------------------	---------------------------------------	--	--------------------------------------	--------------------------------------	-------------------------------	----------

Notes:

ppmv: parts per million by volume

scfm: standard cubic foot per minute (acf m corrected for vacuum and temperature)

NA: Data not available or applicable

NM : Data not measured

GAC: granular activated carbon

* PID Adjusted to FID equivalents as Hexane by multiplying PID Reading by 0.35 (Hexane Equiv = PID Reading x PID CF X FID RF)

** Associated hour meter readings are extrapolated from nearest date and time readings with hour reading measurements

(1) Direct flow readings taken by hand-held TSI Veloci-calc Plus, unless otherwise denoted

(2) Measurements taken with a Foxboro OVA-108 PID calibrated to 100 ppmv Hexane until August 2003 when changed to MiniRea-2000.

(3) As of 3/12/03, Field measurements were conducted using a 10.6 eV PID. No correction has been applied.

TABLE II - INFLUENT VAPOR CONCENTRATIONS, C-6 SVE SYSTEM, BUILDING 1/36

Site Name: BRC Former C-6 Facility

Location: Los Angeles, California

System: Building 1/36 Interim Action SVE System

SAMPLE DATE	LAB ID	SAMPLE LOCATION	COMPOUND																				
			PCE (ppbv)	TCE (ppbv)	1,1,1 TCA (ppbv)	1,1,2 TCA (ppbv)	1,1 DCE (ppbv)	cis-1,2 DCE (ppbv)	1,1 DCA (ppbv)	1,2 DCA (ppbv)	2-Butanone (ppbv)	Chloroform (ppbv)	Acetone (ppbv)	Methylene chloride (ppbv)	Trichlorofluoro-methane (ppbv)	1,2,4 Trimethylbenzene (ppbv)	1,3,5 Trimethylbenzene (ppbv)	4-Ethyltoluene (ppbv)	Toluene (ppbv)	Benzene (ppbv)	Ethylbenzene (ppbv)	Xylene (ppbv)	TNmoc (ppbv)
7/2/2001	EXHAUST 7/2/01	Exhaust	ND	18,000	140,000	810	110,000	ND	ND	ND	20,000	ND	ND	1,200	ND	ND	ND	ND	110,000	ND	ND	ND	NA
7/2/2001	VEW 1-2 DILUTED	Influent	ND	82,000	210,000	6,500	91,000	ND	5,000	ND	47,000	ND	10	1	ND	ND	ND	ND	1,100,000	ND	ND	ND	7,200
7/13/2001	VEW 1-4 DILUTED	Influent	ND	12,000	48,000	760	21,000	ND	1,100	ND	6,900	ND	ND	540	ND	ND	ND	ND	150,000	ND	ND	ND	2,000
7/20/2001	VEW 4-2 DILUTED	Influent	ND	6,300	31,000	360	12,000	ND	660	ND	3,500	ND	ND	690	ND	ND	ND	ND	80,000	ND	ND	ND	770
7/27/2001	VEW 1- DILUTED	Influent	ND	7,300	37,000	460	15,000	ND	880	ND	5,400	ND	ND	1,200	ND	ND	ND	ND	98,000	ND	ND	ND	1,400
8/1/2001	VEW 1- DILUTED	Influent	ND	7,000	47,000	400	16,000	ND	810	ND	4,800	ND	5	1,400	ND	ND	ND	ND	86,000	ND	190	ND	1,300
8/3/2001	EXHAUST 8/3/01	Exhaust	ND	15	330	ND	26	ND	ND	ND	10	ND	24	6	ND	ND	ND	ND	220	ND	2	8	NA
8/3/2001	VEW 1B DILUTED	Influent	ND	120,000	9,500,000	ND	660,000	ND	35,000	ND	98,000	ND	ND	ND	ND	ND	ND	ND	350,000	ND	ND	ND	NA
8/10/2001	EXHAUST 7/2/01	Exhaust	ND	14	32	2	15	ND	ND	ND	13	ND	20	2	ND	ND	ND	ND	290	ND	1	6	NA
8/10/2001	VEW 1B DILUTED	Influent	ND	28,000	1,000,000	ND	110,000	ND	8,200	ND	37,000	ND	ND	ND	ND	ND	ND	ND	140,000	ND	ND	ND	NA
9/11/2001	EXHAUST 9/11/01	Exhaust	ND	11	480	ND	41	3	2	ND	35	ND	49	6	ND	1	ND	ND	97	1	ND	4	NA
9/11/2001	VEW 3A DILUTED	Influent	ND	46,000	3,500	ND	180,000	3,800	1,900	ND	ND	ND	ND	ND	ND	ND	ND	ND	670	ND	ND	ND	NA
9/17/2001	EXHAUST 9/17/01	Exhaust	28	ND	ND	ND	ND	ND	ND	ND	2	ND	13	ND	ND	1	ND	ND	6	ND	ND	ND	NA
9/17/2001	VEW 3B DILUTED	Influent	ND	34,000	140,000	ND	200,000	3,000	7,600	ND	ND	ND	6,900	ND	ND	ND	ND	ND	19,000	ND	390	1,600	NA
9/24/2001	EXHAUST 9/24/01	Exhaust	9	ND	2	ND	1	ND	ND	ND	ND	ND	10	1	ND	ND	ND	ND	5	ND	ND	ND	NA
9/24/2001	VEW 3B DILUTED	Influent	ND	56,000	180,000	ND	210,000	5,300	11,000	ND	ND	ND	18,000	ND	ND	ND	ND	ND	82,000	ND	780	6,700	NA
9/27/2001	VEW 5A DILUTED	Influent	ND	100,000	52,000	ND	260,000	1,500	6,400	ND	ND	ND	890	ND	ND	ND	ND	ND	ND	ND	ND	ND	NA
9/28/2001	VEW 6A DILUTED	Influent	ND	30,000	15,000	ND	150,000	ND	1,200	ND	ND	ND	ND	ND	ND	ND	ND	ND	730	ND	ND	ND	NA
1/3/2002	EXHAUST 1/3/02	Exhaust	74	4,400	1,700	ND	810	26	49	ND	ND	12	ND	11	ND	ND	ND	ND	270	ND	ND	ND	14,000
1/3/2002	DILUTED INLET BLDG 1 01/03/02	Influent	ND	12,000	34,000	ND	32,000	380	1,400	ND	ND	ND	ND	ND	ND	ND	ND	ND	1,800	ND	ND	ND	120,000
2/7/2002	EXHAUST 2/7/02	Exhaust	ND	1	2	ND	3	ND	ND	ND	ND	ND	6	2	ND	ND	ND	ND	3	ND	ND	ND	ND
2/7/2002	DILUTED INLET BLDG 1 02/07/02	Influent	190	45,000	170,000	120	140,000	1,600	3,700	250	ND	330	ND	300	ND	ND	ND	ND	81,000	190	250	1,700	630,000
3/6/2002	EXHAUST 3/6/02	Exhaust	ND	1	ND	ND	2	ND	ND	ND	ND	ND	4	1	ND	ND	ND	ND	2	ND	ND	ND	ND
3/6/2002	DILUTED INLET 3/6/02	Influent	1,600	61,000	220,000	ND	140,000	2,800	5,700	560	ND	490	ND	2,500	130	ND	ND	ND	210,000	530	750	5,000	1,200,000
Pilot system removed. Installed 1000 scfm unit.																							
5/21/2002	GAC0001D_AV052102_0001	Influent	260	48,000	15,000	ND	83,000	1,400	2,200	ND	62,000	240	ND	6,200	150	ND	ND	ND	22,000	260	ND	910	240,000
5/21/2002	GAC0001E_AV052102_0002	Exhaust	ND	1	1	ND	ND	ND	ND	ND	ND	3	1	ND	ND	ND	ND	ND	1	ND	ND	ND	ND
6/3/2002	GAC0001D_AV060302_0001	Influent	ND	29,000	220,000	ND	43,000	1,700	2,700	ND	150,000	ND	ND	8,400	ND	ND	ND	ND	170,000	ND	ND	2,500	860,000
6/3/2002	GAC0001E_AV060302_0002	Exhaust	ND	ND	1	ND	39	ND	ND	ND	ND	4	170	ND	1	ND	1	4	1	ND	4	240	
Carbon bed over-heating. System shutdown 6/7/02.																							
3/12/2003	GAC001U_AV031203_0001	Influent	140	25,000	6,900	ND	57,000	280	530	ND	ND	ND	ND	ND	ND	ND	ND	ND	810	ND	ND	ND	110,000
3/13/2003	GAC001U_AV031303_0001	Influent	110	24,000	37,000	ND	63,000	290	530	ND	ND	ND	ND	ND	ND	ND	ND	ND	25,000	180	ND	ND	190,000
3/14/2003	GAC001U_AV031403_0001	Influent	ND	29,000	66,000	ND	64,000	470	970	ND	ND	ND	ND	ND	ND	ND	ND	ND	70,000	ND	ND	ND	350,000
3/17/2003	GAC001U_AV031703_0001	Influent	ND	21,000	63,000	ND	54,000	3															

TABLE II - INFLUENT VAPOR CONCENTRATIONS, C-6 SVE SYSTEM, BUILDING 1/36

Site Name: BRC Former C-6 Facility

Location: Los Angeles, California

System: Building 1/36 Interim Action SVE System

SAMPLE DATE	LAB ID	SAMPLE LOCATION	COMPOUND																				
			PCE (ppbv)	TCE (ppbv)	1,1,1 TCA (ppbv)	1,1,2 TCA (ppbv)	1,1 DCE (ppbv)	cis- 1,2 DCE (ppbv)	1,1 DCA (ppbv)	1,2 DCA (ppbv)	2- Butanone (ppbv)	Chloroform (ppbv)	Acetone (ppbv)	Methylene chloride (ppbv)	Trichlorofluoro-methane (ppbv)	1,2,4 Trimethylbenzene (ppbv)	1,3,5 Trimethylbenzene (ppbv)	4-Ethyl toluene (ppbv)	Toluene (ppbv)	Benzene (ppbv)	Ethyl benzene (ppbv)	Xylene (ppbv)	TNMOC (ppbv)
4/4/2003	GAC001U_AV040403_001	Influent	36	9,600	43,000	ND	16,000	290	500	73	290	63	ND	330	35	ND	ND	10,000	68	ND	ND	99,000	
4/4/2003	GAC001C_AV040403_001	Breakthrough	ND	760	350	ND	130	2	4	ND	2	ND	6	9	1	2	2	91	1	1	7	960	
4/7/2003	GAC001U_AV040703_001	Influent	ND	11,000	38,000	ND	16,000	370	690	ND	ND	ND	ND	530	ND	ND	ND	ND	11,000	ND	ND	ND	110,000
4/7/2003	GAC001C_AV040703_001	Breakthrough	ND	120	400	ND	320	4	8	ND	ND	ND	9	51	4	2	ND	3	130	4	2	11	1,500
4/8/2003	GAC001U_AV040803_0001	Influent	ND	9,000	47,000	ND	14,000	310	630	ND	1,300	ND	ND	520	ND	ND	ND	ND	14,000	ND	ND	ND	130,000
4/8/2003	GAC001C_AV040803_0001	Breakthrough	ND	110	700	1	640	5	11	1	54	1	17	120	8	2	ND	2	ND	4	2	10	2,600
4/9/2003	GAC001U_AV040903_001	Influent	ND	9,900	90,000	ND	17,000	340	620	ND	2,400	ND	ND	610	ND	ND	ND	ND	22,000	ND	ND	ND	180,000
4/9/2003	GAC001C_AV040903_001	Breakthrough	ND	180	1,400	ND	1,300	ND	16	ND	32	ND	ND	230	11	ND	ND	ND	570	ND	ND	ND	4,100
4/9/2003	GAC001E_AV040903_001	Exhaust	ND	28	580	ND	24	ND	ND	ND	15	ND	15	4	ND	ND	ND	ND	260	4	2	11	1,300
4/10/2003	GAC001U_AV041003_001	Influent	ND	17,000	480,000	ND	26,000	ND	2,300	ND	24,000	ND	ND	5,400	ND	ND	ND	ND	180,000	ND	ND	ND	910,000
4/10/2003	GAC001C_AV041003_001	Breakthrough	ND	95	4,400	ND	2,700	ND	43	ND	130	ND	ND	420	18	ND	ND	ND	1,000	ND	ND	ND	9,500
4/15/2003	GAC001U_AC041503_001	Influent	ND	10,000	130,000	ND	10,000	ND	1,100	ND	42,000	ND	ND	3,600	ND	ND	ND	ND	77,000	ND	ND	ND	390,000
4/15/2003	GAC001C_AV041503_001	Breakthrough	ND	ND	31,000	ND	5,000	ND	400	ND	590	ND	ND	2,900	ND	ND	ND	ND	190	ND	ND	ND	58,000
4/16/2003	GAC001U_AV041603_001	Influent	ND	8,400	150,000	ND	10,000	ND	790	ND	33,000	ND	ND	2,600	ND	ND	ND	ND	65,000	ND	ND	ND	330,000
4/16/2003	GAC001C_AV041603_001	Breakthrough	ND	150	1,600	3	89	5	7	ND	440	ND	13	18	ND	ND	ND	ND	940	ND	2	13	4,000
4/24/2003	GAC001U_AV042403_0001	Influent	ND	7,900	89,000	250	7,500	460	780	230	54,000	ND	930	2,700	ND	ND	ND	ND	56,000	ND	140	960	320,000
4/24/2003	GAC001C_AV042403_0001	Breakthrough	ND	43	3,300	ND	260	ND	26	ND	260	ND	ND	740	ND	ND	ND	ND	350	ND	ND	ND	7,000
4/29/2003	GAC0001U_AV042903_0001	Influent	ND	6,400	120,000	ND	6,300	ND	540	ND	45,000	ND	ND	2,000	ND	ND	ND	ND	52,000	ND	ND	ND	260,000
4/29/2003	GAC001C_AV042903_0001	Breakthrough	ND	47	1,100	2	100	2	7	ND	460	ND	18	660	5	ND	ND	2	390	ND	2	11	2,700
5/6/2003	GAC0001X_AV050603_0001	Exhaust	ND	1.2J	41	ND	3	ND	ND	ND	9.0J	ND	10	14	ND	10	3	7	42	1.0J	3	19	NA
6/30/2003	GAC0001U_AV063003_0001	Influent	74	3,800	21,000	ND	4,400	120	170	ND	1,200	ND	280	200	ND	ND	ND	ND	5,500	ND	ND	ND	77,000
6/30/2003	GAC0001X_AV063003_0001	Exhaust	0.00097J	0	0	ND	0	ND	ND	0	ND	0	0.0024J	ND	0	0.0066	0.013	0.24	0.0017J	0.0056	0.037	1	
7/1/2003	GAC001U_AV070103_0001	Influent	ND	9,000	230,000	340J	7,100	510J	1,000	ND	33,000	ND	ND	2,600	ND	ND	ND	ND	110,000	ND	270J	1,600	850,000
7/31/2003	GAC0001U_AV073103_0001	Influent	ND	2,900	23,000	ND	2,000	92J	170J	ND	3,100	ND	230J	240	ND	ND	ND	ND	22,000	ND	110J	820	110,000
7/31/2003	GAC0001B_AV073103_0001	Breakthrough	ND	41	260	ND	69	1.2J	2.1	ND	31	ND	15	320	10	1.5J	ND	1.6J	230	1.2J	2	16	1,800
7/31/2003	GAC0001X_AV073103_0001	Exhaust	ND	ND	2	ND	ND	ND	ND	4.5J	ND	8.6J	2.7	ND	3.3	1.1J	3.6	20	2	3	18	230J	
8/28/2003	GAC0001X_AV082603_0001	Exhaust	ND	ND	1.2J	ND	ND	ND	ND	ND	ND	ND	ND	1.3J	ND	1.0J	2.9J	ND	0.65J	3	43J		
8/28/2003	GAC0001B_AV082603_0001	Breakthrough	ND	ND	1.6J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	0.79J	ND	ND	ND	57J		
8/28/2003	GAC0001U_AV082603_0001	Influent	ND	2,300	14,000	ND	1,400	98J	160J	ND	2,400	ND	350J	330	ND	ND	ND	ND	25,000	ND	130J	950	90,000
9/25/2003	GAC0001X_AV092503_0001	Exhaust	0.66J	ND	6.7	ND	ND	ND	ND	5.5J	ND	5.6J	2.8	ND	2.9	ND	2.1	10	ND	1.1J	7	100J	
9/25/2003	GAC0001B_AV092503_0001	Breakthrough	ND	31	550	1.9J	14	2.0J	2.6J	ND	280	ND	14J	280	3.9J	ND	ND	ND	490	ND	1.9J	12	2,500
9/25/2003	GAC0001U_AV092503_0001	Influent	ND	3,000	44,000	180J	1,500	190J	260	120J	27,000	ND	710J	800	ND	ND	ND	ND	44,000	ND	97J	730	220,000
10/30/03	GAC0001X_AV103003_0001	Exhaust	ND	ND	2,100	ND	21	ND	5.9	ND	ND	ND	5.8J	460	4.4	ND	ND</td						

TABLE II - INFLUENT VAPOR CONCENTRATIONS, C-6 SVE SYSTEM, BUILDING 1/36

Site Name: BRC Former C-6 Facility

Location: Los Angeles, California

System: Building 1/36 Interim Action SVE System

SAMPLE DATE	LAB ID	SAMPLE LOCATION	COMPOUND																					
			PCE (ppbv)	TCE (ppbv)	1,1,1 TCA (ppbv)	1,1,2 TCA (ppbv)	1,1 DCE (ppbv)	cis- 1,2 DCE (ppbv)	1,1 DCA (ppbv)	1,2 DCA (ppbv)	2- Butanone (ppbv)	Chloroform (ppbv)	Acetone (ppbv)	Methylene chloride (ppbv)	Trichlorofluoro-methane (ppbv)	1,2,4 Trimethylbenzene (ppbv)	1,3,5 Trimethylbenzene (ppbv)	4-Ethyl toluene (ppbv)	Toluene (ppbv)	Benzene (ppbv)	Ethyl benzene (ppbv)	Xylene (ppbv)	TNMOC (ppbv)	
12/23/03	GAC0001U_AV122303_0001	Influent	ND	2,000	40,000	ND	1,100	ND	ND	ND	43,000	ND	1,300J	ND	ND	ND	ND	ND	29,000	ND	ND	760J	160,000	
01/29/04	GAC0001X_AV012904_0001	Exhaust	ND	ND	110	ND	1.4J	ND	ND	ND	4.2J	ND	6.6J	71	1.7J	3	2.1	2	7.7	ND	0.68J	4	340J	
01/29/04	GAC0001B_AV012904_0001	Breakthrough	ND	28J	11,000	ND	150	ND	18J	ND	280	ND	ND	31J	ND	ND	ND	ND	ND	430	ND	ND	ND	20,000
01/29/04	GAC0001U_AV012904_0001	Influent	ND	4,800	210,000	ND	4,500	ND	ND	ND	50,000	ND	ND	ND	ND	ND	ND	ND	ND	72,000	ND	ND	3,100	530,000J
02/26/04	GAC0001X_AV022604_0001	Exhaust	ND	ND	80	ND	ND	ND	ND	ND	ND	ND	4.1J	1.7J	ND	ND	ND	ND	4.8J	0.91J	ND	2	140J	
02/26/04	GAC0001B_AV022604_0001	Breakthrough	ND	7	9,700	ND	66	ND	1.9J	ND	33	ND	13	96	13	ND	ND	ND	ND	47	ND	ND	1.3J	16,000
02/26/04	GAC0001U_AV022604_0001	Influent	ND	2,100	34,000	94J	770	ND	72J	ND	46,000	ND	1,200	ND	ND	ND	ND	ND	ND	35,000	ND	160J	1,000	130,000
03/25/04	GAC0001X_AV032504_0001	Exhaust	ND	ND	26	ND	ND	ND	ND	ND	2.3J	ND	21	1.0J	ND	ND	ND	ND	ND	3.5J	0.84J	ND	1.2J	100J
03/25/04	GAC0001B_AV032504_0001	Breakthrough	ND	6.8J	2,700	ND	13J	ND	ND	ND	87J	ND	26J	54	6.5J	ND	ND	ND	ND	74	ND	ND	ND	4,900J
03/25/04	GAC0001V_AV032504_0001	Influent	ND	1,400	20,000	ND	610	ND	ND	ND	47,000	ND	1,500J	ND	ND	ND	ND	ND	ND	27,000	ND	140J	1,100	100,000J

Notes:

ppbv = parts per million by volume

ND = not detected

NA = not analyzed

TNMOC = Total Non Methane Organic Carbons

J = Estimated result. Result is less than Reporting Limit.

TABLE III - WELLFIELD DATA

Site Name: BRC Former C-6 Facility
Location: Los Angeles, California
System: Building 1/36 Interim Action SVE System

WELL ID	DATE	TIME	FLOW RATE (1) (scfm)	VACUUM (inches of H ₂ O)	WELLHEAD FID (2) (ppmv)	COMMENTS
1-VEW-1	3/6/2002	13:40	NA	0.0	NA	Well Closed
	3/29/2002	8:15	NA	0.5	NA	"
	5/23/2002	11:21	4.41	9	115	Well Opened
	5/23/2002	12:38	18.9	40	125	"
	5/23/2002	14:19	37.6	96	155	"
	6/3/2002	10:00	39	90	51	"
	6/7/02 through 3/11/03		SVE shut down for retrofit			
	3/12/2003		Begin start-up procedures			
	3/24/2003		26	65	210	Well Opened**
	4/1/2003		21	60	210	
	4/16/2003		19	55	155	
	4/29/2003	8:30	22	56	46	
	5/5/2003	8:00	52	64	47	
	5/8/2003	15:30	NM	NM	NM	
	5/12/2003	8:00	32	55	128	
	5/19/2003	15:00	45.8	74	91	
	6/27/2003	16:00	40	92	242	
	6/30/2003	10:00	40	40	101	
	7/1/2003	8:00	25.2	43	93	
	7/2/2003	13:30	40	55	112	
	7/3/2003	8:00	40	50	120	
	7/7/2003	9:00	40	75	121	
	7/18/2003	8:42	40	77	80	
	7/24/2003	9:00	40	86	85	
	7/31/2003	8:00	40	85	92	
	8/7/2003	9:30	40	78	51	
	8/14/2003	8:00	31	79	52	
	8/14/2003	8:00	NM	NM	NM	
	8/21/2003	8:30	30	82	67	
	8/21/2003	15:30	NM	NM	NM	
	8/28/2003	6:45	25	78	49	
	9/4/2003	6:50	40	75	30	
	9/4/2003	13:45	NM	NM	NM	
	9/5/2003	11:30	NM	NM	NM	
	9/11/2003	6:30	27	78	33	
	9/11/2003	13:30	NM	NM	NM	
	9/18/2003	7:00	40	77	24	
	9/25/2003	7:00	24	76	28	
	10/2/2003	6:30	20	75	17	
	10/9/2003	9:00	20	70	15	
	10/16/2003	6:00	20	70	14	
	10/23/2003	6:00	20	68	15	
	10/30/2003	6:00	20	65	22	
	11/6/2003	9:00	20	67	13	
	11/26/2003	7:00	20	74	17	
	12/1/2003	9:30	NM	NM	NM	
	12/4/2003	9:30	20	71	11	
	12/11/2003	8:30	20	72	16	
	12/18/2003	8:00	20	70	16	
	12/23/2003	6:00	20	71	18	
	1/5/2004	9:00	NM	NM	NM	
	1/7/2004	8:00	NM	NM	NM	
	1/8/2004	9:00	20	68	43	
	1/15/2004	9:00	20	50	13	
	2/2/2004	9:00	20	45	41	
	2/5/2004	9:00	20	53	13	
	2/12/2004	9:00	20	50	11	
	2/19/2004	9:00	20	50	14	
	2/26/2004	9:30	20	55	11	Well 15% Open
	3/4/2004	7:00	20	54	9	Well 15% Open
	3/11/2004	6:30	20	74	8	Well 15% Open
	3/18/2004	8:30	20	74	9	Well 15% Open
	3/25/2004	6:00	20	70	6	Well 15% Open

TABLE III - WELLFIELD DATA

Site Name: BRC Former C-6 Facility
Location: Los Angeles, California
System: Building 1/36 Interim Action SVE System

WELL ID	DATE	TIME	FLOW RATE (1) (scfm)	VACUUM (inches of H ₂ O)	WELLHEAD FID (2) (ppmv)	COMMENTS
1-VEW-2	3/6/2002	13:40	NA	0.5	NA	Well Closed
	3/29/2002	8:15	NA	1	NA	"
	5/23/2002	11:24	5.45	9	49	Well Opened
	5/23/2002	12:35	21.2	35.5	51	"
	5/23/2002	14:23	47.2	96	58	"
	6/3/2002	10:00	45	90	30	"
	6/7/02 through 3/11/03		SVE shut down for retrofit			
	3/12/2003		Begin start-up procedures			
	3/24/2003		32	83	106	Well Opened**
	4/1/2003		23	80	75	
	4/16/2003		20	74	66	
	4/29/2003	8:30	26	75	23	
	5/5/2003	8:00	39.6	60	65	
	5/8/2003	15:30	NM	NM	NM	
	5/12/2003	8:00	32	55	4	
	5/19/2003	15:00	61.5	53	35	
	6/27/2003	16:00	38	98	98	
	6/30/2003	10:00	40	28	32	
	7/1/2003	8:00	22.8	33	39	
	7/2/2003	13:30	40	55	110	
	7/3/2003	8:00	40	52	100	
	7/7/2003	9:00	40	60	41	
	7/18/2003	8:42	40	61	23	
	7/24/2003	9:00	40	72	27	
	7/31/2003	8:00	40	70	18	
	8/7/2003	9:30	40	68	22	
	8/14/2003	8:00	34	74	32	
	8/14/2003	8:00	NM	NM	NM	
	8/21/2003	8:30	30	78	39	
	8/21/2003	15:30	NM	NM	NM	
	8/28/2003	6:45	30	74	29	
	9/4/2003	6:50	28	70	20	
	9/4/2003	13:45	NM	NM	NM	
	9/5/2003	11:30	NM	NM	NM	
	9/11/2003	6:30	30	73	24	
	9/11/2003	13:30	NM	NM	NM	
	9/18/2003	7:00	28	73	24	
	9/25/2003	7:00	30	72	19	
	10/2/2003	6:30	30	73	14	
	10/9/2003	9:00	30	65	15	
	10/16/2003	6:00	30	65	15	
	10/23/2003	6:00	30	62	17	
	10/30/2003	6:00	30	75	32	
	11/6/2003	9:00	30	78	30	
	11/26/2003	7:00	30	83	19	
	12/1/2003	9:30	NM	NM	NM	
	12/4/2003	9:30	30	83	21	
	12/11/2003	8:30	30	84	21	
	12/18/2003	8:00	30	85	23	
	12/23/2003	6:00	30	83	53	
	1/5/2004	9:00	NM	NM	NM	
	1/7/2004	8:00	NM	NM	NM	
	1/8/2004	9:00	30	68	38	
	1/15/2004	9:00	30	58	18	
	2/2/2004	9:00	30	50	51	
	2/5/2004	9:00	30	62	22	
	2/12/2004	9:00	30	60	15	
	2/19/2004	9:00	30	60	20	
	2/26/2004	9:30	30	65	14	Well 20% Open
	3/4/2004	7:00	30	65	12	Well 20% Open
	3/11/2004	6:30	30	85	11	Well 20% Open
	3/18/2004	8:30	30	82	10	Well 20% Open
	3/25/2004	6:00	30	80	10	Well 20% Open

TABLE III - WELLFIELD DATA

Site Name: BRC Former C-6 Facility
Location: Los Angeles, California
System: Building 1/36 Interim Action SVE System

WELL ID	DATE	TIME	FLOW RATE (1) (scfm)	VACUUM (inches of H2O)	WELLHEAD FID (2) (ppmv)	COMMENTS
1-VEW-3	3/6/2002	13:40	NA	0.1	NA	Well Closed
	3/29/2002	8:15	NA	0.6	NA	"
	5/23/2002	11:17	3.37	8.5	32	Well Opened
	5/23/2002	12:43	15.6	42	87	"
	5/23/2002	14:13	30.2	96	82	"
	6/3/2002	10:00	24	69	40	"
	6/7/02 through 3/11/03		SVE shut down for retrofit			
	3/12/2003		Begin start-up procedures			
	3/24/2003		32	70	190	Well Opened**
	4/1/2003		25	65	210	
	4/16/2003		20	65	155	
	4/29/2003	8:30	33	61	79	
	5/5/2003	8:00	31.5	65	14	
	5/8/2003	15:30	NM	NM	NM	
	5/12/2003	8:00	63	60	139	
	5/19/2003	15:00	64.5	58	109	
	6/27/2003	16:00	30	41	197	
	6/30/2003	10:00	30	42	117	
	7/1/2003	8:00	12.3	40	157	
	7/2/2003	13:30	30	43	237	
	7/3/2003	8:00	30	40	250	
	7/7/2003	9:00	30	55	196	
	7/18/2003	8:42	30	44	148	
	7/24/2003	9:00	30	80	237	
	7/31/2003	8:00	30	68	192	
	8/7/2003	9:30	30	81	117	
	8/14/2003	8:00	30	81	140	
	8/14/2003	8:00	NM	NM	NM	
	8/21/2003	8:30	25	96	182	
	8/21/2003	15:30	NM	NM	NM	
	8/28/2003	6:45	25	93	142	
	9/4/2003	6:50	25	90	96	
	9/4/2003	13:45	NM	NM	NM	
	9/5/2003	11:30	NM	NM	NM	
	9/11/2003	6:30	28	93	112	
	9/11/2003	13:30	NM	NM	NM	
	9/18/2003	7:00	30	58	79	
	9/25/2003	7:00	25	92	120	
	10/2/2003	6:30	26	91	77	
	10/9/2003	9:00	30	85	73	
	10/16/2003	6:00	30	85	75	
	10/23/2003	6:00	30	84	68	
	10/30/2003	6:00	15	95	79	
	11/6/2003	9:00	15	96	75	
	11/26/2003	7:00	15	100	74	
	12/1/2003	9:30	NM	NM	NM	
	12/4/2003	9:30	15	100	72	
	12/11/2003	8:30	15	97	70	
	12/18/2003	8:00	15	95	80	
	12/23/2003	6:00	15	96	90	
	1/5/2004	9:00	NM	NM	NM	
	1/7/2004	8:00	NM	NM	NM	
	1/8/2004	9:00	20	95	67	
	1/15/2004	9:00	20	93	49	
	2/2/2004	9:00	20	93	80	
	2/5/2004	9:00	20	98	59	
	2/12/2004	9:00	20	94	58	
	2/19/2004	9:00	20	94	63	
	2/26/2004	9:30	20	98	45	Well 20% Open
	3/4/2004	7:00	20	98	33	Well 20% Open
	3/11/2004	6:03	20	90	33	Well 20% Open
	3/18/2004	8:30	20	88	45	Well 20% Open
	3/25/2004	6:00	20	85	54	Well 20% Open

TABLE III - WELLFIELD DATA

Site Name: BRC Former C-6 Facility
Location: Los Angeles, California
System: Building 1/36 Interim Action SVE System

WELL ID	DATE	TIME	FLOW RATE (1) (scfm)	VACUUM (inches of H2O)	WELLHEAD FID (2) (ppmv)	COMMENTS
1-VEW-4	3/6/2002	13:40	NA	1.4	NA	Well Closed
	3/29/2002	8:15	NA	1.4	NA	"
	5/23/2002	10:45	2.61	13	8	Well Opened
	5/23/2002	NA	7.05	34.5	360	"
	5/23/2002	14:08	18.1	96	230	"
	6/3/2002	10:00	9	51	120	"
	6/7/02 through 3/11/03		SVE shut down for retrofit			
	3/12/2003		Begin start-up procedures			
	3/24/2003		11	20	1,600	Well Opened**
	4/1/2003		9	20	1,120	
	4/16/2003		11	15	220	
	4/29/2003	8:30	14	15	130	
	5/5/2003	8:00	74	50	425	
	5/8/2003	15:30	NM	NM	NM	
	5/12/2003	8:00	11	50	294	
	5/19/2003	15:00	4.71	41	120	Well at 50%
	6/27/2003	16:00	10	74	620	
	6/30/2003	10:00	10	50	534	
	7/1/2003	8:00	10	40	1,037	
	7/2/2003	13:30	10	35	1,610	
	7/3/2003	8:00	10	30	1,635	
	7/7/2003	9:00	10	30	1,174	
	7/18/2003	8:42	10	30	291	
	7/24/2003	9:00	10	40	428	
	7/31/2003	8:00	10	40	351	
	8/7/2003	9:30	10	45	303	
	8/14/2003	8:00	10	45	319	
	8/14/2003	8:00	NM	NM	NM	
	8/21/2003	8:30	10	50	385	
	8/21/2003	15:30	NM	NM	NM	
	8/28/2003	6:45	10	45	363	
	9/4/2003	6:50	10	40	306	
	9/4/2003	13:45	NM	NM	NM	
	9/5/2003	11:30	NM	NM	NM	
	9/11/2003	6:30	10	45	300	
	9/11/2003	13:30	NM	NM	NM	
	9/18/2003	7:00	10	45	325	
	9/25/2003	7:00	10	53	326	
	10/2/2003	6:30	10	53	218	
	10/9/2003	9:00	10	52	195	
	10/16/2003	6:00	10	50	187	
	10/23/2003	6:00	10	50	180	
	10/30/2003	6:00	10	55	215	
	11/6/2003	9:00	10	63	158	
	11/26/2003	7:00	10	65	142	
	12/1/2003	9:30	NM	NM	NM	
	12/4/2003	9:30	10	50	272	
	12/11/2003	8:30	10	50	223	
	12/18/2003	8:00	10	40	245	
	12/23/2003	6:00	10	50	136	
	1/5/2004	9:00	NM	NM	NM	
	1/7/2004	8:00	NM	NM	NM	
	1/8/2004	9:00	10	45	141	
	1/15/2004	9:00	10	15	116	
	2/2/2004	9:00	10	15	72	
	2/5/2004	9:00	10	15	131	
	2/12/2004	9:00	10	15	95	
	2/19/2004	9:00	10	10	5	
	2/26/2004	9:30	10	11	3	Well 5% Open
	3/4/2004	7:00	10	10	2	Well 5% Open
	3/11/2004	6:30	10	10	0	Well 5% Open
	3/18/2004	8:30	10	10	5	Well 5% Open
	3/25/2004	6:00	10	10	2	Well 5% Open

TABLE III - WELLFIELD DATA

Site Name: BRC Former C-6 Facility
Location: Los Angeles, California
System: Building 1/36 Interim Action SVE System

WELL ID	DATE	TIME	FLOW RATE (1) (scfm)	VACUUM (inches of H ₂ O)	WELLHEAD FID (2) (ppmv)	COMMENTS
1-VEW-5	3/6/2002	13:40	NA	1.4	NA	Well Closed
	3/29/2002	8:15	NA	1.5	NA	"
	5/21/2002	11:38	6.9	12	59	Well Opened
	5/21/2002	13:02	15.6	19	16	"
	5/21/2002	12:45	32.1	34	29	"
	6/3/2002	10:00	NA	10	NA	Well Closed
	6/7/02 through 3/11/03		SVE shut down for retrofit			
	3/12/2003		Begin start-up procedures			
	3/24/2003		52	30	12	Well Opened**
	4/1/2003		30	40	5.8	
	4/16/2003		29	40	12.5	
	4/29/2003	8:30	31	40	12	
	5/5/2003	8:00	40.5	40	47	
	5/8/2003	15:30	NM	NM	NM	
	5/12/2003	8:00	41	40	3	Well at 50%
	5/19/2003	15:00	40.4	38	233	"
	6/27/2003	16:00	30	25	10	
	6/30/2003	10:00	30	25	4	
	7/1/2003	8:00	30	25	16	
	7/2/2003	13:30	30	20	9	
	7/3/2003	8:00	30	22	5	
	7/7/2003	9:00	30	20	6	
	7/18/2003	8:42	30	20	4	
	7/24/2003	9:00	30	25	5	
	7/31/2003	8:00	30	25	8	
	8/7/2003	9:30	30	23	7	
	8/14/2003	8:00	30	24	7	
	8/14/2003	8:00	NM	NM	NM	
	8/21/2003	8:30	30	24	13	
	8/21/2003	15:30	NM	NM	NM	
	8/28/2003	6:45	30	22	41	
	9/4/2003	6:50	30	22	8	
	9/4/2003	13:45	NM	NM	NM	
	9/5/2003	11:30	NM	NM	NM	
	9/11/2003	6:30	30	22	4	
	9/11/2003	13:30	NM	NM	NM	
	9/18/2003	7:00	30	21	13	
	9/25/2003	7:00	30	22	3	
	10/2/2003	6:30	30	22	3	
	10/9/2003	9:00	30	22	2	
	10/16/2003	6:00	30	22	1	
	10/23/2003	6:00	30	20	0	Well Closed
	10/30/2003	6:00	NM	NM	NM	Well Closed
	11/6/2003	9:00	NM	NM	NM	Well Closed
	11/26/2003	7:00	NM	NM	NM	Well Closed
	12/1/2003	9:30	NM	NM	NM	Well Closed
	12/4/2003	9:30	NM	NM	NM	Well Closed
	12/11/2003	8:30	NM	NM	NM	Well Closed
	12/18/2003	8:00	NM	NM	NM	Well Closed
	12/23/2003	6:00	NM	NM	NM	Well Closed
	1/5/2004	9:00	NM	NM	NM	
	1/7/2004	8:00	NM	NM	NM	
	1/8/2004	9:00	NM	NM	NM	Well Closed
	1/15/2004	9:00	NM	NM	NM	Well Closed
	2/2/2004	9:00	NM	NM	NM	Well Closed
	2/5/2004	9:00	5	10	135	
	2/12/2004	9:00	5	10	0	
	2/19/2004	9:00	5	10	18	
	2/26/2004	9:30	5	15	2	Well 10% Open
	3/4/2004	7:00	5	15	1	Well 10% Open
	3/11/2004	6:30	5	15	0	Well 10% Open
	3/18/2004	8:30	5	14	1	Well 10% Open
	3/25/2004	6:00	5	14	2	Well 10% Open

TABLE III - WELLFIELD DATA

Site Name: BRC Former C-6 Facility
Location: Los Angeles, California
System: Building 1/36 Interim Action SVE System

WELL ID	DATE	TIME	FLOW RATE (1) (scfm)	VACUUM (inches of H ₂ O)	WELLHEAD FID (2) (ppmv)	COMMENTS
1-VEW-6	3/6/2002	13:40	NA	2.2	NA	Well Closed
	3/29/2002	8:15	NA	1.6	NA	"
	5/21/2002	11:25	6.3	8	52	Well Opened
	5/21/2002	13:05	16.5	15	16	"
	5/21/2002	12:50	33.3	30	30	"
	6/3/2002	10:00	NA	7	NA	Well Closed
6/7/02 through 3/11/03		SVE shut down for retrofit				
	3/12/2003	Begin start-up procedures				
	3/24/2003		30	30	6	Well Opened**
	4/29/2003	8:30	22	30	5	
	5/5/2003	8:00	32	30	61	
	5/8/2003	15:30	NM	NM	NM	
	5/12/2003	8:00	34	29	2	Well at 50%
	5/19/2003	15:00	19	30	216	"
	6/27/2003	16:00	30	21	15	
	6/30/2003	10:00	30	23	4	
	7/1/2003	8:00	30	28	17	
	7/2/2003	13:30	30	25	5	
	7/3/2003	8:00	30	21	10	
	7/7/2003	9:00	30	25	7	
	7/18/2003	8:42	20	27	5	
	7/24/2003	9:00	30	27	4	
	7/31/2003	8:00	30	25	3	
	8/7/2003	9:30	30	25	7	
	8/14/2003	8:00	30	25	7	
	8/14/2003	8:00	NM	NM	NM	
	8/21/2003	8:30	30	25	12	
	8/21/2003	15:30	NM	NM	NM	
	8/28/2003	6:45	30	25	17	
	9/4/2003	6:50	30	25	7	
	9/4/2003	13:45	NM	NM	NM	
	9/5/2003	11:30	NM	NM	NM	
	9/11/2003	6:30	30	25	5	
	9/11/2003	13:30	NM	NM	NM	
	9/18/2003	7:00	30	25	15	
	9/25/2003	7:00	30	25	8	
	10/2/2003	6:30	30	25	7	
	10/9/2003	9:00	30	25	2	
	10/16/2003	6:00	30	25	1	
	10/23/2003	6:00	30	25	0	Well Closed
	10/30/2003	6:00	NM	NM	NM	Well Closed
	11/6/2003	9:00	NM	NM	NM	Well Closed
	11/26/2003	7:00	NM	NM	NM	Well Closed
	12/1/2003	9:30	NM	NM	NM	Well Closed
	12/4/2003	9:30	NM	NM	NM	Well Closed
	12/11/2003	8:30	NM	NM	NM	Well Closed
	12/18/2003	8:00	NM	NM	NM	Well Closed
	12/23/2003	6:00	NM	NM	NM	Well Closed
	1/5/2004	9:00	NM	NM	NM	
	1/7/2004	8:00	NM	NM	NM	
	1/8/2004	9:00	NM	NM	NM	Well Closed
	1/15/2004	9:00	NM	NM	NM	Well Closed
	2/2/2004	9:00	NM	NM	NM	Well Closed
	2/5/2004	9:00	5	10	86	
	2/12/2004	9:00	5	10	0	
	2/19/2004	9:00	5	10	12	
	2/26/2004	9:30	5	12	2	Well 15% Open
	3/4/2004	7:00	5	10	1	Well 15% Open
	3/11/2004	6:30	5	10	0	Well 15% Open
	3/18/2004	8:30	5	10	1	Well 15% Open
	3/25/2004	6:00	5	10	2	Well 15% Open

TABLE III - WELLFIELD DATA

Site Name: BRC Former C-6 Facility
Location: Los Angeles, California
System: Building 1/36 Interim Action SVE System

WELL ID	DATE	TIME	FLOW RATE (1) (scfm)	VACUUM (inches of H ₂ O)	WELLHEAD FID (2) (ppmv)	COMMENTS
1-VEW-7	3/6/2002	13:40	NA	1.9	NA	Well Closed
	3/29/2002	8:15	NA	0.1	NA	"
	5/23/2002	10:38	9.85	13	44	Well Opened
	5/23/2002	11:37	42.1	41	85	"
	5/23/2002	13:58	92	95	120	"
	6/3/2002	10:00	88	88	30	"
6/7/02 through 3/11/03		SVE shut down for retrofit				
	3/12/2003	Begin start-up procedures				
	3/24/2003	60	60	340		Well Opened**
	4/29/2003	8:30	39	50	90	
	5/5/2003	8:00	45	50	315	
	5/8/2003	15:30	NM	NM	NM	
	5/12/2003	8:00	47	45	117	
	5/19/2003	15:00	40.8	45	143	
	6/27/2003	16:00	30	9	2,728	
	6/30/2003	10:00	30	20	689	
	7/1/2003	8:00	30	20	516	
	7/2/2003	13:30	30	10	666	
	7/3/2003	8:00	30	12	710	
	7/7/2003	9:00	30	20	432	
	7/18/2003	8:42	30	20	346	
	7/24/2003	9:00	30	20	292	
	7/31/2003	8:00	30	20	214	
	8/7/2003	9:30	30	18	279	
	8/14/2003	8:00	30	20	325	
	8/14/2003	8:00	NM	NM	NM	
	8/21/2003	8:30	30	20	428	
	8/21/2003	15:30	NM	NM	NM	
	8/28/2003	6:45	30	20	360	
	9/4/2003	6:50	30	20	317	
	9/4/2003	13:45	NM	NM	NM	
	9/5/2003	11:30	NM	NM	NM	
	9/11/2003	6:30	30	28	318	
	9/11/2003	13:30	NM	NM	NM	
	9/18/2003	7:00	30	16	349	
	9/25/2003	7:00	30	18	309	
	10/2/2003	6:30	30	18	208	
	10/9/2003	9:00	30	20	180	
	10/16/2003	6:00	30	20	111	
	10/23/2003	6:00	30	16	99	
	10/30/2003	6:00	30	12	79	
	11/6/2003	9:00	30	17	89	
	11/26/2003	7:00	30	20	89	
	12/1/2003	9:30	NM	NM	NM	
	12/4/2003	9:30	30	20	121	
	12/11/2003	8:30	30	21	95	
	12/18/2003	8:00	30	20	98	
	12/23/2003	6:00	30	20	104	
	1/5/2004	9:00	NM	NM	NM	
	1/7/2004	8:00	NM	NM	NM	
	1/8/2004	9:00	30	10	73	
	1/15/2004	9:00	30	10	49	
	2/2/2004	9:00	30	5	57	
	2/5/2004	9:00	30	15	49	
	2/12/2004	9:00	30	15	36	
	2/19/2004	9:00	30	18	36	
	2/26/2004	9:30	30	22	43	Well 10% Open
	3/4/2004	7:00	30	21	40	Well 10% Open
	3/11/2004	6:30	30	21	33	Well 10% Open
	3/18/2004	8:30	30	22	37	Well 10% Open
	3/25/2004	6:00	30	22	33	Well 10% Open

TABLE III - WELLFIELD DATA

Site Name: BRC Former C-6 Facility
Location: Los Angeles, California
System: Building 1/36 Interim Action SVE System

WELL ID	DATE	TIME	FLOW RATE (1) (scfm)	VACUUM (inches of H ₂ O)	WELLHEAD FID (2) (ppmv)	COMMENTS
1-VIEW-8A	3/6/2002	13:40	NA	0.5	NA	Well Closed
	3/29/2002	8:15	NA	0.6	NA	"
	5/22/2002	11:25	10.75	11.5	175	Well Opened
	5/22/2002	14:23	63	41.5	150	"
	5/22/2002	15:32	112	82	142	"
	6/3/2002	10:00	33	22	40	"
	6/7/02 through 3/11/03		SVE shut down for retrofit			
	3/12/2003		Begin start-up procedures			
	3/24/2003		39	30	120	Well Opened**
	4/29/2003	8:30	27	25	75	
	5/5/2003	8:00	57.5	40	111	
	5/8/2003	15:30	NM	NM	NM	
	5/12/2003	8:00	55	60	65	
	5/19/2003	15:00	42	45	52	
	6/27/2003	16:00	20	10	45	
	6/30/2003	10:00	20	13	31	
	7/1/2003	8:00	20	15	46	
	7/2/2003	13:30	20	10	65	
	7/3/2003	8:00	20	12	59	
	7/7/2003	9:00	20	14	58	
	7/18/2003	8:42	20	13	31	
	7/24/2003	9:00	20	15	30	
	7/31/2003	8:00	20	15	29	
	8/7/2003	9:30	20	14	26	
	8/14/2003	8:00	20	14	31	
	8/14/2003	8:00	NM	NM	NM	
	8/21/2003	8:30	20	15	35	
	8/21/2003	15:30	NM	NM	NM	
	8/28/2003	6:45	20	14	26	
	9/4/2003	6:50	20	19	17	
	9/4/2003	13:45	NM	NM	NM	
	9/5/2003	11:30	NM	NM	NM	
	9/11/2003	6:30	20	19	19	
	9/11/2003	13:30	NM	NM	NM	
	9/18/2003	7:00	20	18	21	
	9/25/2003	7:00	20	19	17	
	10/2/2003	6:30	20	18	11	
	10/9/2003	9:00	20	18	10	
	10/16/2003	6:00	20	17	10	
	10/23/2003	6:00	20	16	11	
	10/30/2003	6:00	20	20	9	
	11/6/2003	9:00	20	17	14	
	11/26/2003	7:00	20	18	12	
	12/1/2003	9:30	NM	NM	NM	
	12/4/2003	9:30	20	17	2	
	12/11/2003	8:30	20	18	8	
	12/18/2003	8:00	20	18	65	
	12/23/2003	6:00	20	18	31	
	1/5/2004	9:00	NM	NM	NM	
	1/7/2004	8:00	NM	NM	NM	
	1/8/2004	9:00	20	18	7	
	1/15/2004	9:00	20	18	6	
	2/2/2004	9:00	20	18	7	
	2/5/2004	9:00	20	18	4	
	2/12/2004	9:00	20	18	2	
	2/19/2004	9:00	20	18	6	
	2/26/2004	9:30	20	21	9	Well 25% Open
	3/4/2004	7:00	20	20	9	Well 25% Open
	3/11/2004	6:30	20	20	10	Well 25% Open
	3/18/2004	8:30	20	20	8	Well 25% Open
	3/25/2004	6:00	20	20	7	Well 25% Open

TABLE III - WELLFIELD DATA

Site Name: BRC Former C-6 Facility
Location: Los Angeles, California
System: Building 1/36 Interim Action SVE System

WELL ID	DATE	TIME	FLOW RATE (1) (scfm)	VACUUM (inches of H2O)	WELLHEAD FID (2) (ppmv)	COMMENTS
1-VIEW-8B	3/6/2002	13:40	NA	0.3	NA	Well Closed
	3/29/2002	8:15	NA	0.6	NA	"
	5/17/2002	NA	3.7	14	565	Well Opened
	5/17/2002	NA	6.05	43	650	"
	5/17/2002	NA	11.3	72	510	"
	6/3/2002	10:00	10	90	60	"
	6/7/02 through 3/11/03		SVE shut down for retrofit			
	3/12/2003		Begin start-up procedures			
	3/24/2003		19	30	1,207	Well Opened**
	4/29/2003	8:30	19	18	370	
	5/5/2003	8:00	28.9	35	656	
	5/8/2003	15:30	NM	NM	NM	
	5/12/2003	8:00	21	60	389	
	5/19/2003	15:00	62	40	301	
	6/27/2003	16:00	20	42	355	
	6/30/2003	10:00	20	19	154	
	7/1/2003	8:00	20	25	94	
	7/2/2003	13:30	20	22	250	
	7/3/2003	8:00	20	20	248	
	7/7/2003	9:00	20	22	249	
	7/18/2003	8:42	20	25	140	
	7/24/2003	9:00	20	25	156	
	7/31/2003	8:00	20	25	181	
	8/7/2003	9:30	20	27	127	
	8/14/2003	8:00	20	24	150	
	8/14/2003	8:00	NM	NM	NM	
	8/21/2003	8:30	20	24	172	
	8/21/2003	15:30	NM	NM	NM	
	8/28/2003	6:45	20	24	147	
	9/4/2003	6:50	20	58	96	
	9/4/2003	13:45	NM	NM	NM	
	9/5/2003	11:30	NM	NM	NM	
	9/11/2003	6:30	20	60	102	
	9/11/2003	13:30	NM	NM	NM	
	9/18/2003	7:00	20	59	94	
	9/25/2003	7:00	20	59	86	
	10/2/2003	6:30	20	54	71	
	10/9/2003	9:00	20	52	62	
	10/16/2003	6:00	20	48	75	
	10/23/2003	6:00	20	46	66	
	10/30/2003	6:00	20	60	63	
	11/6/2003	9:00	20	60	72	
	11/26/2003	7:00	20	60	68	
	12/1/2003	9:30	NM	NM	NM	
	12/4/2003	9:30	20	70	54	
	12/11/2003	8:30	20	65	66	
	12/18/2003	8:00	20	60	82	
	12/23/2003	6:00	20	70	52	
	1/5/2004	9:00	NM	NM	NM	
	1/7/2004	8:00	NM	NM	NM	
	1/8/2004	9:00	20	73	40	
	1/15/2004	9:00	20	68	34	
	2/2/2004	9:00	20	73	39	
	2/5/2004	9:00	20	70	36	
	2/12/2004	9:00	20	70	41	
	2/19/2004	9:00	20	65	38	
	2/26/2004	9:30	20	70	45	Well 50% Open
	3/4/2004	7:00	20	65	54	Well 50% Open
	3/11/2004	6:30	20	70	48	Well 50% Open
	3/18/2004	8:30	20	68	31	Well 50% Open
	3/25/2004	6:00	20	64	33	Well 50% Open

TABLE III - WELLFIELD DATA

Site Name: BRC Former C-6 Facility
Location: Los Angeles, California
System: Building 1/36 Interim Action SVE System

WELL ID	DATE	TIME	FLOW RATE (1) (scfm)	VACUUM (inches of H ₂ O)	WELLHEAD FID (2) (ppmv)	COMMENTS
1-VEW-9	3/6/2002	13:40	NA	NA	NA	Well Closed
	3/29/2002	8:15	NA	NA	NA	"
	5/23/2002	10:30	4.33	13	63	"
	5/23/2002	13:05	27.7	45	410	Well Opened
	5/23/2002	13:56	46.4	95	305	"
	6/3/2002	10:00	49	88	120	"
	6/7/02 through 3/11/03		SVE shut down for retrofit			
	3/12/2003		Begin start-up procedures			
	4/29/2003	8:30	21	47	618	Well Opened***
	5/5/2003	8:00	40	45	4,100	
	5/8/2003	15:30	NM	NM	NM	
	5/12/2003	8:00	26	42	2,740	
	5/19/2003	15:00	20.6	40	2,680	
	6/27/2003	16:00	NA	NA	NA	Well Closed
	6/30/2003	10:00	20	35	1,120	
	7/1/2003	8:00	20	28	3,940	
	7/2/2003	13:30	20	25	322	
	7/3/2003	8:00	20	20	4,330	
	7/7/2003	9:00	20	32	3,635	
	7/18/2003	8:42	20	30	3,034	
	7/24/2003	9:00	20	27	2,920	
	7/31/2003	8:00	20	30	4,100	
	8/7/2003	9:30	20	25	2,510	
	8/14/2003	8:00	20	25	2,949	
	8/14/2003	8:00	NM	NM	NM	
	8/21/2003	8:30	20	26	4,212	
	8/21/2003	15:30	20	26	3,964	Rechecked Well per H&A
	8/28/2003	6:45	20	27	3,459	
	9/4/2003	6:50	20	30	2,799	
	9/4/2003	13:45	10	NM	3,045	Rechecked Well per H&A
	9/5/2003	11:30	5	14	NM	
	9/11/2003	6:30	10	15	2,140	
	9/11/2003	13:30	NM	NM	NM	
	9/18/2003	7:00	10	15	1,765	
	9/25/2003	7:00	10	20	3,668	Changed scfm from 10 to 20
	10/2/2003	6:30	20	20	1,662	
	10/9/2003	9:00	47	20	1,530	Well 100% Open
	10/16/2003	6:00	29	55	1,401	
	10/23/2003	6:00	35	54	1,157	
	10/30/2003	6:00	39	72	1,592	
	11/6/2003	9:00	39	73	851	
	11/26/2003	7:00	39	80	950	
	12/1/2003	9:30	NM	NM	NM	
	12/4/2003	9:30	39	80	1,050	Well 100% Open
	12/11/2003	8:30	39	80	938	
	12/18/2003	8:00	39	78	900	
	12/23/2003	6:00	39	80	552	
	1/5/2004	9:00	NM	NM	NM	
	1/7/2004	8:00	NM	NM	NM	
	1/8/2004	9:00	53	82	1,201	
	1/15/2004	9:00	53	72	550	
	2/2/2004	9:00	53	78	1,278	
	2/5/2004	9:00	53	80	956	Well 100% Open
	2/12/2004	9:00	53	72	725	Well 100% Open
	2/19/2004	9:00	53	73	634	Well 100% Open
	2/26/2004	9:30	53	84	473	Well 100% Open
	3/4/2004	7:00	53	81	436	Well 100% Open
	3/11/2004	6:30	53	95	316	Well 100% Open
	3/18/2004	8:30	53	94	274	Well 100% Open
	3/25/2004	6:00	53	95	258	Well 100% Open

TABLE III - WELLFIELD DATA

Site Name: BRC Former C-6 Facility
Location: Los Angeles, California
System: Building 1/36 Interim Action SVE System

WELL ID	DATE	TIME	FLOW RATE (1) (scfm)	VACUUM (inches of H ₂ O)	WELLHEAD FID (2) (ppmv)	COMMENTS
1-VIEW-10A	3/6/2002	13:40	NA	NA	NA	Well Closed
	3/29/2002	8:15	NA	NA	NA	"
	5/16/2002	NA	2.7	26	270	Well Opened
	5/16/2002	NA	11	54	195	"
	5/16/2002	NA	19.8	18	35	"
	6/3/2002	10:00	19	65	16	"
6/7/02 through 3/11/03			SVE shut down for retrofit			
	3/12/2003		Begin start-up procedures			
	4/16/2003		0:00	47	65	
	4/29/2003	8:30	29	45	23	Well Opened***
	5/5/2003	8:00	45	46	39	
	5/8/2003	15:30	NM	NM	NM	
	5/12/2003	8:00	10	43	47	
	5/19/2003	15:00	21.3	43	92	
	6/27/2003	16:00	NA	NA	NA	Well Closed
	6/30/2003	10:00	20	68	28	
	7/1/2003	8:00	20	67	452	
	7/2/2003	13:30	20	70	99	
	7/3/2003	8:00	20	62	201	
	7/7/2003	9:00	20	65	158	
	7/18/2003	8:42	20	60	4	
	7/24/2003	9:00	20	48	8	
	7/31/2003	8:00	20	50	7	
	8/7/2003	9:30	20	47	56	
	8/14/2003	8:00	20	45	31	
	8/14/2003	8:00	NM	NM	NM	
	8/21/2003	8:30	20	46	72	
	8/21/2003	15:30	NM	NM	NM	
	8/28/2003	6:45	20	43	20	
	9/4/2003	6:50	20	43	11	
	9/4/2003	13:45	NM	NM	NM	
	9/5/2003	11:30	NM	NM	NM	
	9/11/003	6:30	20	43	16	
	9/11/2003	13:30	NM	NM	NM	
	9/18/2003	7:00	20	43	12	
	9/25/2003	7:00	20	40	4	
	10/2/2003	6:30	20	36	5	
	10/9/2003	9:00	20	33	4	
	10/16/2003	6:00	20	28	2	
	10/23/2003	6:00	20	23	3	
	10/30/2003	6:00	20	31	5	
	11/6/2003	9:00	20	21	2	
	11/26/2003	7:00	20	51	0	
	12/1/2003	9:30	NM	NM	NM	
	12/4/2003	9:30	20	50	1	
	12/11/2003	8:30	20	50	5	
	12/18/2003	8:00	20	48	4	
	12/23/2003	6:00	20	49	44	
	1/5/2004	9:00	NM	NM	NM	
	1/7/2004	8:00	NM	NM	NM	
	1/8/2004	9:00	20	55	6	
	1/15/2004	9:00	20	45	4	
	2/2/2004	9:00	20	50	4	
	2/5/2004	9:00	20	50	24	
	2/12/2004	9:00	20	45	0	
	2/19/2004	9:00	20	25	3	
	2/26/2004	9:30	20	40	1	Well 10% Open
	3/4/2004	7:00	6	25	2	Well 5% Open
	3/11/2004	6:30	6	25	0	Well 5% Open
	3/18/2004	8:30	6	30	3	Well 5% Open
	3/25/2004	6:00	6	30	3	Well 5% Open

TABLE III - WELLFIELD DATA

Site Name: BRC Former C-6 Facility
Location: Los Angeles, California
System: Building 1/36 Interim Action SVE System

WELL ID	DATE	TIME	FLOW RATE (1) (scfm)	VACUUM (inches of H ₂ O)	WELLHEAD FID (2) (ppmv)	COMMENTS
1-VIEW-10B	3/6/2002	13:40	NA	NA	NA	Well Closed
	3/29/2002	8:15	NA	NA	NA	
	5/20/2002	13:05	2.74	20	290	Well Opened
	5/20/2002	15:45	12.7	25	750	
	5/20/2002	16:53	21	78	600	
	6/3/2002	10:00	29	60	290	
	6/7/02 through 3/11/03		SVE shut down for retrofit			
	3/12/2003		Begin start-up procedures			
	4/16/2003		0.00	55	1,030	
	4/29/2003	8:30	19	56	495	Well Opened***
	5/5/2003	8:00	48	55	3,130	
	5/8/2003	15:30	NM	NM	NM	
	5/12/2003	8:00	13	52	1,994	
	5/19/2003	15:00	30	51	1,958	
	6/27/2003	16:00	NA	NA	NA	Well Closed
	6/30/2003	10:00	10	34	1,164	
	7/1/2003	8:00	10	32	4,912	
	7/2/2003	13:30	10	35	1,691	
	7/3/2003	8:00	10	30	+10000	
	7/7/2003	9:00	10	38	9,620	
	7/18/2003	8:42	10	38	4,791	
	7/24/2003	9:00	10	36	4,573	
	7/31/2003	8:00	10	35	6,510	
	8/7/2003	9:30	10	38	3,901	
	8/14/2003	8:00	10	35	4,523	
	8/14/2003	8:00	NM	NM	NM	
	8/21/2003	8:30	10	35	+10000	
	8/21/2003	15:30	10	35	+10000	Well Rechecked per H&A
	8/28/2003	6:45	10	34	4,547	
	9/4/2003	6:50	10	35	2,801	
	9/4/2003	13:45	NM	NM	NM	
	9/5/2003	11:30	NM	NM	NM	
	9/11/2003	6:30	10	34	4,209	
	9/11/2003	13:30	NM	NM	NM	
	9/18/2003	7:00	10	35	3,204	
	9/25/2003	7:00	10	35	2,341	Changed scfm from 10 to 20
	10/2/2003	6:30	20	60	3,579	
	10/9/2003	9:00	15	59	2,015	Well 100% Open
	10/16/2003	6:00	15	59	1,706	
	10/23/2003	6:00	25	57	1,147	
	10/30/2003	6:00	25	71	1,452	
	11/6/2003	9:00	25	73	1,643	
	11/26/2003	7:00	25	78	2,632	
	12/1/2003	9:30	NM	NM	NM	
	12/4/2003	9:30	25	79	1,993	Well 100% Open
	12/11/2003	8:30	25	78	1,730	
	12/18/2003	8:00	25	75	1,327	
	12/23/2003	6:00	25	78	964	
	1/5/2004	9:00	NM	NM	NM	
	1/7/2004	8:00	NM	NM	NM	
	1/8/2004	9:00	20	20	1,205	
	1/15/2004	9:00	20	60	1,017	
	2/2/2004	9:00	20	55	1,110	
	2/5/2004	9:00	20	50	1,539	Well 100% Open
	2/12/2004	9:00	20	70	1,413	Well 100% Open
	2/19/2004	9:00	20	70	1,137	Well 100% Open
	2/26/2004	9:30	20	68	830	Well 100% Open
	3/4/2004	7:00	20	76	940	Well 100% Open
	3/11/2004	6:30	20	81	672	Well 100% Open
	3/18/2004	8:30	20	80	680	Well 100% Open
	3/25/2004	6:00	20	80	775	Well 100% Open

TABLE III - WELLFIELD DATA

Site Name: BRC Former C-6 Facility
Location: Los Angeles, California
System: Building 1/36 Interim Action SVE System

WELL ID	DATE	TIME	FLOW RATE (1) (scfm)	VACUUM (inches of H2O)	WELLHEAD FID (2) (ppmv)	COMMENTS
1-VIEW-11A	3/6/2002	13:40	NA	4.7	NA	Well Closed
	3/29/2002	8:15	NA	2.8	NA	"
	5/15/2002	18:08	5.3	40	400	Well Opened
	5/15/2002	19:22	5.6	>100	400	"
	5/15/2002	18:57	20.1	52	420	"
	6/3/2002	10:00	22	90	44	Well Closed
	6/7/02 through 3/11/03		SVE shut down for retrofit			
	3/12/2003		Begin start-up procedures			
	3/24/2003		34	35	48	Well Opened**
	4/1/2003		11	36	77	
	4/16/2003		18	35	13	
	4/29/2003	8:30	22.5	36	11	
	5/5/2003	8:00	40	62	23	
	5/8/2003	15:30	NM	NM	NM	
	5/12/2003	8:00	22	32	14	Well at 50%
	5/19/2003	15:00	49	32	13	
	6/27/2003	16:00	20	81	43	
	6/30/2003	10:00	20	80	19	
	7/1/2003	8:00	20	78	159	
	7/2/2003	13:30	20	65	32	
	7/3/2003	8:00	20	61	103	
	7/7/2003	9:00	20	60	31	
	7/18/2003	8:42	20	41	72	
	7/24/2003	9:00	20	48	107	
	7/31/2003	8:00	20	50	42	
	8/7/2003	9:30	20	49	101	
	8/14/2003	8:00	10	35	149	
	8/14/2003	8:00	NM	NM	NM	
	8/21/2003	8:30	20	50	1,332	
	8/21/2003	15:30	NM	NM	NM	
	8/28/2003	6:45	20	46	376	
	9/4/2003	6:50	20	46	97	
	9/4/2003	13:45	NM	NM	NM	
	9/5/2003	11:30	NM	NM	NM	
	9/11/2003	6:30	20	46	251	
	9/11/2003	13:30	NM	NM	NM	
	9/18/2003	7:00	20	47	261	
	9/25/2003	7:00	20	45	133	
	10/2/2003	6:30	20	43	138	
	10/9/2003	9:00	20	44	4	
	10/16/2003	6:00	20	43	3	
	10/23/2003	6:00	20	38	3	
	10/30/2003	6:00	20	55	15	
	11/6/2003	9:00	20	50	2	
	11/26/2003	7:00	20	55	0	
	12/1/2003	9:30	NM	NM	NM	
	12/4/2003	9:30	20	55	0	
	12/11/2003	8:30	20	53	2	
	12/18/2003	8:00	20	53	2	
	12/23/2003	6:00	20	53	50	
	1/5/2004	9:00	NM	NM	NM	
	1/7/2004	8:00	NM	NM	NM	
	1/8/2004	9:00	16	71	12	
	1/15/2004	9:00	16	65	22	
	2/2/2004	9:00	16	70	6	
	2/5/2004	9:00	16	70	12	Well 100% Open
	2/12/2004	9:00	16	65	0	Well 100% Open
	2/19/2004	9:00	16	65	13	Well 100% Open
	2/26/2004	9:30	16	68	2	Well 100% Open
	3/4/2004	7:00	7	26	1	Well 2% Open
	3/11/2004	6:30	7	26	0	Well 2% Open
	3/18/2004	8:30	7	32	2	Well 2% Open
	3/25/2004	6:00	7	25	2	Well 2% Open

TABLE III - WELLFIELD DATA

Site Name: BRC Former C-6 Facility
Location: Los Angeles, California
System: Building 1/36 Interim Action SVE System

WELL ID	DATE	TIME	FLOW RATE (1) (scfm)	VACUUM (inches of H ₂ O)	WELLHEAD FID (2) (ppmv)	COMMENTS
1-VIEW-11B	3/6/2002	13:40	NA	5.0	NA	Well Closed
	3/29/2002	8:15	NA	3.0	NA	"
	5/18/2002	9:40	2.16	23.5	270	Well Opened
	5/18/2002	11:50	7.7	38	340	"
	5/18/2002	13:35	15.5	60	280	"
	6/3/2002	10:00	29	50	75	"
	6/7/02 through 3/11/03		SVE shut down for retrofit			
	3/12/2003		Begin start-up procedures			
	3/24/2003		51	50	970	Well Opened**
	4/1/2003		18	49	569	
	4/16/2003		17	45	105	
	4/29/2003	8:30	21	45	92	
	5/5/2003	8:00	22.1	55	203	
	5/8/2003	15:30	NM	NM	NM	
	5/12/2003	8:00	13	45	97	
	5/19/2003	15:00	24.7	42	84	
	6/27/2003	16:00	20	58	209	
	6/30/2003	10:00	20	60	315	
	7/1/2003	8:00	20	60	506	
	7/2/2003	13:30	20	60	360	
	7/3/2003	8:00	20	60	477	
	7/7/2003	9:00	20	60	1,072	
	7/18/2003	8:42	20	38	1,371	
	7/24/2003	9:00	20	51	3,717	
	7/31/2003	8:00	20	55	1,112	
	8/7/2003	9:30	20	51	5,223	
	8/14/2003	8:00	20	50	9,530	
	8/14/2003	8:00	NM	NM	NM	
	8/21/2003	8:30	20	53	+10000	
	8/21/2003	15:30	20	53	+10000	Well Rechecked per H&A
	8/28/2003	6:45	20	50	+10000	
	9/4/2003	6:50	20	50	3,350	
	9/4/2003	13:45	10	NM	4,906	Well Rechecked per H&A
	9/5/2003	11:30	5	27	NM	
	9/11/2003	6:30	10	35	+10000	
	9/11/2003	13:30	NM	NM	NM	
	9/18/2003	7:00	10	35	+10000	
	9/25/2003	7:00	10	35	3,083	Changed scfm from 10 to 20
	10/2/2003	6:30	20	52	854	
	10/9/2003	9:00	20	52	259	
	10/16/2003	6:00	20	50	55	
	10/23/2003	6:00	20	48	34	
	10/30/2003	6:00	20	62	50	
	11/6/2003	9:00	20	64	36	
	11/26/2003	7:00	20	69	37	
	12/1/2003	9:30	NM	NM	NM	
	12/4/2003	9:30	20	68	30	
	12/11/2003	8:30	20	69	34	
	12/18/2003	8:00	20	65	25	
	12/23/2003	6:00	20	69	75	
	1/5/2004	9:00	NM	NM	NM	
	1/7/2004	8:00	NM	NM	NM	
	1/8/2004	9:00	18	68	56	
	1/15/2004	9:00	18	63	64	
	2/2/2004	9:00	18	65	51	
	2/5/2004	9:00	18	65	94	Well 100% Open
	2/12/2004	9:00	18	60	23	Well 100% Open
	2/19/2004	9:00	18	60	45	Well 100% Open
	2/26/2004	9:30	18	70	17	Well 100% Open
	3/4/2004	7:00	14	68	15	Well 100% Open
	3/11/2004	6:30	14	68	7	Well 100% Open
	3/18/2004	8:30	14	80	7	Well 100% Open
	3/25/2004	6:00	14	80	8	Well 100% Open

TABLE III - WELLFIELD DATA

Site Name: BRC Former C-6 Facility
Location: Los Angeles, California
System: Building 1/36 Interim Action SVE System

WELL ID	DATE	TIME	FLOW RATE (1) (scfm)	VACUUM (inches of H2O)	WELLHEAD FID (2) (ppmv)	COMMENTS
1-VEW-12	3/6/2002	13:40	NA	3.5	NA	Well Closed
	3/29/2002	8:15	NA	2.2	NA	"
	5/21/2002	11:45	6.2	18.5	80	Well Opened
	5/21/2002	13:44	17.3	43	65	"
	5/21/2002	12:40	32.3	90	63	"
	6/3/2002	10:00	17	55	14	Well Closed
	6/7/02 through 3/11/03		SVE shut down for retrofit			
	3/12/2003		Begin start-up procedures			
	3/24/2003		54	45	48	Well Opened**
	4/1/2003		19	45	21	
	4/16/2003		16	45	7	
	4/29/2003	8:30	17	45	3	
	5/5/2003	8:00	55	45	6	
	5/8/2003	15:30	NM	NM	NM	
	5/12/2003	8:00	19	45	4	
	5/19/2003	15:00	23	41	5	
	6/27/2003	16:00	10	29	14	
	6/30/2003	10:00	10	20	6	
	7/1/2003	8:00	10	25	34	
	7/2/2003	13:30	10	20	10	
	7/3/2003	8:00	10	22	13	
	7/7/2003	9:00	10	25	25	
	7/18/2003	8:42	10	25	5	
	7/24/2003	9:00	10	23	4	
	7/31/2003	8:00	10	25	8	
	8/7/2003	9:30	10	22	9	
	8/14/2003	8:00	10	23	7	
	8/14/2003	8:00	NM	NM	NM	
	8/21/2003	8:30	10	22	14	
	8/21/2003	15:30	NM	NM	NM	
	8/28/2003	6:45	10	22	13	
	9/4/2003	6:50	10	22	11	
	9/4/2003	13:45	NM	NM	NM	
	9/5/2003	11:30	NM	NM	NM	
	9/11/2003	6:30	10	20	22	
	9/11/2003	13:30	NM	NM	NM	
	9/18/2003	7:00	10	20	12	
	9/25/2003	7:00	10	20	3	
	10/2/2003	6:30	10	20	3	
	10/9/2003	9:00	10	20	3	
	10/16/2003	6:00	10	19	3	
	10/23/2003	6:00	10	18	3	
	10/30/2003	6:00	10	18	7	
	11/6/2003	9:00	10	20	7	
	11/26/2003	7:00	10	24	3	
	12/1/2003	9:30	NM	NM	NM	
	12/4/2003	9:30	10	23	0	
	12/11/2003	8:30	10	23	4	
	12/18/2003	8:00	10	23	4	
	12/23/2003	6:00	10	23	43	
	1/5/2004	9:00	NM	NM	NM	
	1/7/2004	8:00	NM	NM	NM	
	1/8/2004	9:00	10	29	9	
	1/15/2004	9:00	10	29	9	
	2/2/2004	9:00	10	28	6	
	2/5/2004	9:00	10	30	6	
	2/12/2004	9:00	10	30	0	
	2/19/2004	9:00	10	30	18	
	2/26/2004	9:30	10	35	1	Well 10% Open
	3/4/2004	7:00	7	18	3	Well 5% Open
	3/11/2004	6:30	7	18	2	Well 5% Open
	3/18/2004	8:30	7	16	4	Well 5% Open
	3/25/2004	6:00	7	15	5	Well 5% Open

TABLE III - WELLFIELD DATA

Site Name: BRC Former C-6 Facility
Location: Los Angeles, California
System: Building 1/36 Interim Action SVE System

WELL ID	DATE	TIME	FLOW RATE (1) (scfm)	VACUUM (inches of H ₂ O)	WELLHEAD FID (2) (ppmv)	COMMENTS
1-VIEW-13A	3/6/2002	13:40	NA	3.0	NA	Well Closed
	3/29/2002	8:15	NA	2.0	NA	"
	5/15/2002	18:23	5.4	20	84	Well Opened
	5/15/2002	19:05	11.2	56	95	"
	5/15/2002	19:29	28.1	>100	120	"
	6/3/2002	10:00	59	87	14	"
	6/7/02 through 3/11/03		SVE shut down for retrofit			
	3/12/2003		Begin start-up procedures			
	3/24/2003		48	55	18	Well Opened**
	4/1/2003		15.5	48	19.1	
	4/16/2003		30	50	14.3	
	4/29/2003	8:30	24	50	6	
	5/5/2003	8:00	31	50	18	
	5/8/2003	15:30	NM	NM	NM	
	5/12/2003	8:00	26	48	12	
	5/19/2003	15:00	33	45	14	
	6/27/2003	16:00	20	80	30	
	6/30/2003	10:00	30	82	10	
	7/1/2003	8:00	26	79	104	
	7/2/2003	13:30	30	80	115	
	7/3/2003	8:00	30	80	21	
	7/7/2003	9:00	30	80	26	
	7/18/2003	8:42	30	80	7	
	7/24/2003	9:00	30	62	16	
	7/31/2003	8:00	30	65	4	
	8/7/2003	9:30	30	62	15	
	8/14/2003	8:00	30	61	16	
	8/14/2003	8:00	NM	NM	NM	
	8/21/2003	8:30	30	63	26	
	8/21/2003	15:30	NM	NM	NM	
	8/28/2003	6:45	30	57	24	
	9/4/2003	6:50	30	60	17	
	9/4/2003	13:45	NM	NM	NM	
	9/5/2003	11:30	NM	NM	NM	
	9/11/2003	6:30	30	60	12	
	9/11/2003	13:30	NM	NM	NM	
	9/18/2003	7:00	30	60	25	
	9/25/2003	7:00	30	58	14	
	10/2/2003	6:30	30	45	6	
	10/9/2003	9:00	30	54	6	
	10/16/2003	6:00	30	52	5	
	10/23/2003	6:00	30	50	3	
	10/30/2003	6:00	30	65	13	
	11/6/2003	9:00	30	64	7	
	11/26/2003	7:00	30	70	3	
	12/1/2003	9:30	NM	NM	NM	
	12/4/2003	9:30	30	70	2	
	12/11/2003	8:30	30	69	6	
	12/18/2003	8:00	30	65	6	
	12/23/2003	6:00	30	68	32	
	1/5/2004	9:00	NM	NM	NM	
	1/7/2004	8:00	NM	NM	NM	
	1/8/2004	9:00	30	55	2	
	1/15/2004	9:00	30	55	12	
	2/2/2004	9:00	30	50	10	
	2/5/2004	9:00	30	55	8	
	2/12/2004	9:00	30	55	0	
	2/19/2004	9:00	30	55	6	
	2/26/2004	9:30	30	57	5	Well 50% Open
	3/4/2004	7:00	7	25	6	Well 5% Open
	3/11/2004	6:30	7	23	0	Well 5% Open
	3/18/2004	8:30	7	17	2	Well 5% Open
	3/25/2004	6:00	7	22	3	Well 5% Open

TABLE III - WELLFIELD DATA

Site Name: BRC Former C-6 Facility
Location: Los Angeles, California
System: Building 1/36 Interim Action SVE System

WELL ID	DATE	TIME	FLOW RATE (1) (scfm)	VACUUM (inches of H ₂ O)	WELLHEAD FID (2) (ppmv)	COMMENTS
1-VIEW-13B	3/6/2002	13:40	NA	2.9	NA	Well Closed
	3/29/2002	8:15	NA	2.2	NA	"
	5/18/2002	NA	1.84	18.5	63	Well Opened
	5/18/2002	NA	8.3	33	220	"
	5/18/2002	NA	18.6	60.5	200	"
	6/3/2002	10:00	26	45	60	"
	6/7/02 through 3/11/03		SVE shut down for retrofit			
	3/12/2003		Begin start-up procedures			
	3/24/2003		52	55	130	Well Opened**
	4/1/2003		15.5	48	220	
	4/16/2003		30	50	160	
	4/29/2003	8:30	21	48	59	
	5/5/2003	8:00	20	51	152	
	5/8/2003	15:30	NM	NM	NM	
	5/12/2003	8:00	21	45	99	
	5/19/2003	15:00	52	45	102	
	6/27/2003	16:00	28	81	132	
	6/30/2003	10:00	30	80	115	
	7/1/2003	8:00	30	78	197	
	7/2/2003	13:30	30	82	165	
	7/3/2003	8:00	30	80	163	
	7/7/2003	9:00	30	80	179	
	7/18/2003	8:42	30	80	30	
	7/24/2003	9:00	30	63	133	
	7/31/2003	8:00	30	65	39	
	8/7/2003	9:30	30	63	75	
	8/14/2003	8:00	30	61	81	
	8/14/2003	8:00	NM	NM	NM	
	8/21/2003	8:30	30	65	101	
	8/21/2003	15:30	NM	NM	NM	
	8/28/2003	6:45	30	59	86	
	9/4/2003	6:50	30	60	63	
	9/4/2003	13:45	NM	NM	NM	
	9/5/2003	11:30	NM	NM	NM	
	9/11/2003	6:30	30	60	54	
	9/11/2003	13:30	NM	NM	NM	
	9/18/2003	7:00	30	60	66	
	9/25/2003	7:00	25	58	57	
	10/2/2003	6:30	30	45	37	
	10/9/2003	9:00	30	54	37	
	10/16/2003	6:00	30	52	37	
	10/23/2003	6:00	30	50	32	
	10/30/2003	6:00	30	65	39	
	11/6/2003	9:00	30	65	48	
	11/26/2003	7:00	30	71	40	
	12/1/2003	9:30	NM	NM	NM	
	12/4/2003	9:30	30	70	45	
	12/11/2003	8:30	30	71	47	
	12/18/2003	8:00	30	69	37	
	12/23/2003	6:00	30	71	91	
	1/5/2004	9:00	NM	NM	NM	
	1/7/2004	8:00	NM	NM	NM	
	1/8/2004	9:00	21	25	42	
	1/15/2004	9:00	21	25	49	
	2/2/2004	9:00	21	24	52	
	2/5/2004	9:00	21	25	59	Well 100% Open
	2/12/2004	9:00	21	28	42	Well 100% Open
	2/19/2004	9:00	21	28	48	Well 100% Open
	2/26/2004	9:30	21	40	22	Well 100% Open
	3/4/2004	7:00	21	40	27	Well 100% Open
	3/11/2004	6:30	21	43	8	Well 100% Open
	3/18/2004	8:30	21	40	8	Well 100% Open
	3/25/2004	6:00	21	40	9	Well 100% Open

TABLE III - WELLFIELD DATA

Site Name: BRC Former C-6 Facility
Location: Los Angeles, California
System: Building 1/36 Interim Action SVE System

WELL ID	DATE	TIME	FLOW RATE (1) (scfm)	VACUUM (inches of H ₂ O)	WELLHEAD FID (2) (ppmv)	COMMENTS
1-VIEW-14A	3/6/2002	13:40	NA	0.4	NA	Well Closed
	3/29/2002	8:15	NA	0.4	NA	"
	5/15/2002	18:48	5.3	24	27	Well Opened
	5/15/2002	19:11	15	30	27	"
	5/15/2002	19:37	27	>100	40	"
	6/3/2002	10:00	22	64	14	Well Closed
	6/7/02 through 3/11/03		SVE shut down for retrofit			
	3/12/2003		Begin start-up procedures			
	3/24/2003		43	50	11	Well Opened**
	4/1/2003		16	50	2.1	
	4/16/2003		26	43	3.8	
	4/29/2003	8:30	29	43	3	
	5/5/2003	8:00	35	60	22	
	5/8/2003	15:30	NM	NM	NM	
	5/12/2003	8:00	43	40	4	Well at 50%
	5/19/2003	15:00	67	41	6	"
	6/27/2003	16:00	19	75	13	
	6/30/2003	10:00	30	78	8	
	7/1/2003	8:00	30	75	31	
	7/2/2003	13:30	30	75	20	
	7/3/2003	8:00	30	72	20	
	7/7/2003	9:00	30	75	9	
	7/18/2003	8:42	30	70	6	
	7/24/2003	9:00	30	45	10	
	7/31/2003	8:00	30	49	8	
	8/7/2003	9:30	30	46	10	
	8/14/2003	8:00	30	45	12	
	8/14/2003	8:00	NM	NM	NM	
	8/21/2003	8:30	30	48	15	
	8/21/2003	15:30	NM	NM	NM	
	8/28/2003	6:45	30	45	26	
	9/4/2003	6:50	30	45	17	
	9/4/2003	13:45	NM	NM	NM	
	9/5/2003	11:30	NM	NM	NM	
	9/11/2003	6:30	30	45	7	
	9/11/2003	13:30	NM	NM	NM	
	9/18/2003	7:00	30	45	16	
	9/25/2003	7:00	30	43	9	
	10/2/2003	6:30	30	43	3	
	10/9/2003	9:00	30	42	3	
	10/16/2003	6:00	30	40	3	
	10/23/2003	6:00	30	39	1	
	10/30/2003	6:00	30	50	6	
	11/6/2003	9:00	30	49	2	
	11/26/2003	7:00	30	54	0	
	12/1/2003	9:30	NM	NM	NM	
	12/4/2003	9:30	30	94	0	
	12/11/2003	8:30	30	54	2	
	12/18/2003	8:00	30	50	4	
	12/23/2003	6:00	30	54	29	
	1/5/2004	9:00	NM	NM	NM	
	1/7/2004	8:00	NM	NM	NM	
	1/8/2004	9:00	30	69	10	
	1/15/2004	9:00	30	62	10	
	2/2/2004	9:00	30	68	9	
	2/5/2004	9:00	30	65	7	
	2/12/2004	9:00	30	60	0	
	2/19/2004	9:00	30	60	2	
	2/26/2004	9:30	30	71	3	Well 75% Open
	3/4/2004	7:00	15	30	9	Well 20% Open
	3/11/2004	6:30	15	18	0	Well 20% Open
	3/18/2004	8:30	15	19	2	Well 20% Open
	3/25/2004	6:00	15	19	2	Well 20% Open

TABLE III - WELLFIELD DATA

Site Name: BRC Former C-6 Facility
Location: Los Angeles, California
System: Building 1/36 Interim Action SVE System

WELL ID	DATE	TIME	FLOW RATE (1) (scfm)	VACUUM (inches of H ₂ O)	WELLHEAD FID (2) (ppmv)	COMMENTS
1-VIEW-14B	3/6/2002	13:40	NA	1.8	NA	Well Closed
	3/29/2002	8:15	NA	1.8	NA	"
	5/18/2002	NA	7.1	15.5	65	Well Opened
	5/18/2002	NA	34.2	33.5	95	"
	5/18/2002	NA	65	61	85	"
	6/3/2002	10:00	38	40	35	"
	6/7/02 through 3/11/03		SVE shut down for retrofit			
	3/12/2003		Begin start-up procedures			
	3/24/2003		41	35	140	Well Opened**
	4/1/2003		40	35	105	
	4/16/2003		32	35	58	
	4/29/2003	8:30	38	35	61	
	5/5/2003	8:00	36	65	22	
	5/8/2003	15:30	NM	NM	NM	
	5/12/2003	8:00	39	32	68	Well at 85%
	5/19/2003	15:00	27	34	83	Well at 50%
	6/27/2003	16:00	30	28	97	
	6/30/2003	10:00	30	28	68	
	7/1/2003	8:00	30	30	89	
	7/2/2003	13:30	30	20	88	
	7/3/2003	8:00	30	22	89	
	7/7/2003	9:00	30	25	81	
	7/18/2003	8:42	30	29	36	
	7/24/2003	9:00	30	31	65	
	7/31/2003	8:00	30	40	59	
	8/7/2003	9:30	30	33	65	
	8/14/2003	8:00	30	32	72	
	8/14/2003	8:00	NM	NM	NM	
	8/21/2003	8:30	30	34	92	
	8/21/2003	15:30	NM	NM	NM	
	8/28/2003	6:45	30	45	79	
	9/4/2003	6:50	30	32	59	
	9/4/2003	13:45	NM	NM	NM	
	9/5/2003	11:30	NM	NM	NM	
	9/11/2003	6:30	30	31	54	
	9/11/2003	13:30	NM	NM	NM	
	9/18/2003	7:00	30	30	64	
	9/25/2003	7:00	30	30	53	
	10/2/2003	6:30	30	30	32	
	10/9/2003	9:00	30	29	30	
	10/16/2003	6:00	30	28	30	
	10/23/2003	6:00	30	27	23	
	10/30/2003	6:00	30	32	34	
	11/6/2003	9:00	30	33	42	
	11/26/2003	7:00	30	36	42	
	12/1/2003	9:30	NM	NM	NM	
	12/4/2003	9:30	30	35	34	
	12/11/2003	8:30	30	38	49	
	12/18/2003	8:00	30	35	37	
	12/23/2003	6:00	30	38	70	
	1/5/2004	9:00	NM	NM	NM	
	1/7/2004	8:00	NM	NM	NM	
	1/8/2004	9:00	30	32	32	
	1/15/2004	9:00	30	66	47	
	2/2/2004	9:00	30	31	38	
	2/5/2004	9:00	30	35	58	
	2/12/2004	9:00	30	33	42	
	2/19/2004	9:00	30	33	38	
	2/26/2004	9:30	30	39	34	Well 50% Open
	3/4/2004	7:00	30	38	40	Well 50% Open
	3/11/2004	6:30	30	78	18	Well 50% Open
	3/18/2004	8:30	30	79	17	Well 50% Open
	3/25/2004	6:00	30	79	20	Well 50% Open

TABLE III - WELLFIELD DATA

Site Name: BRC Former C-6 Facility
Location: Los Angeles, California
System: Building 1/36 Interim Action SVE System

WELL ID	DATE	TIME	FLOW RATE (1) (scfm)	VACUUM (inches of H ₂ O)	WELLHEAD FID (2) (ppmv)	COMMENTS
1-VIEW-15A	3/6/2002	13:40	NA	0.0	NA	Well Closed
	3/29/2002	8:15	NA	0.0	NA	"
	5/22/2002	12:14	16.4	6.5	13.5	Well Opened
	5/22/2002	13:51	74	35	23	"
	5/22/2002	16:00	138	80	19.5	"
	6/3/2002	10:00	84	61	NA	Well Closed
	6/7/02 through 3/11/03		SVE shut down for retrofit			
	3/12/2003		Begin start-up procedures			
	3/24/2003		50	60	9	Well Opened**
	4/1/2003		61	60	2.3	
	4/16/2003		65	50	32	
	4/29/2003	8:30	70	50	30	
	5/5/2003	8:00	84	52	9	
	5/8/2003	15:30	NM	NM	NM	
	5/12/2003	8:00	68	48	6	
	5/19/2003	15:00	113	46	8	
	6/27/2003	16:00	40	77	13	
	6/30/2003	10:00	40	27	3	
	7/1/2003	8:00	40	20	7	
	7/2/2003	13:30	40	30	5	
	7/3/2003	8:00	40	32	11	
	7/7/2003	9:00	40	30	4	
	7/18/2003	8:42	40	32	2	
	7/24/2003	9:00	40	38	2	
	7/31/2003	8:00	40	38	3	
	8/7/2003	9:30	40	35	3	
	8/14/2003	8:00	40	40	5	
	8/14/2003	8:00	NM	NM	NM	
	8/21/2003	8:30	40	39	11	
	8/21/2003	15:30	NM	NM	NM	
	8/28/2003	6:45	40	37	4	
	9/4/2003	6:50	40	35	3	
	9/4/2003	13:45	NM	NM	NM	
	9/5/2003	11:30	NM	NM	NM	
	9/11/2003	6:30	40	36	1	
	9/11/2003	13:30	NM	NM	NM	
	9/18/2003	7:00	40	35	5	
	9/25/2003	7:00	40	35	3	
	10/2/2003	6:30	40	36	2	
	10/9/2003	9:00	40	36	1	
	10/16/2003	6:00	40	35	0	
	10/23/2003	6:00	40	35	0	Well Closed
	10/30/2003	6:00	NM	NM	NM	Well Closed
	11/6/2003	9:00	NM	NM	NM	Well Closed
	11/26/2003	7:00	NM	NM	NM	Well Closed
	12/1/2003	9:30	NM	NM	NM	Well Closed
	12/4/2003	9:30	NM	NM	NM	Well Closed
	12/11/2003	8:30	NM	NM	NM	Well Closed
	12/18/2003	8:00	NM	NM	NM	Well Closed
	12/23/2003	6:00	NM	NM	NM	Well Closed
	1/5/2004	9:00	NM	NM	NM	
	1/7/2004	8:00	NM	NM	NM	
	1/8/2004	9:00	NM	NM	NM	Well Closed
	1/15/2004	9:00	NM	NM	NM	Well Closed
	2/2/2004	9:00	NM	NM	NM	Well Closed
	2/5/2004	9:00	5	20	0	
	2/12/2004	9:00	5	20	0	
	2/19/2004	9:00	5	20	2	
	2/26/2004	9:30	5	25	1	Well 10% Open
	3/4/2004	7:00	5	25	0	Well 10% Open
	3/11/2004	6:30	5	25	0	Well 10% Open
	3/18/2004	8:30	5	16	1	Well 10% Open
	3/25/2004	6:00	5	16	0	Well 10% Open

TABLE III - WELLFIELD DATA

Site Name: BRC Former C-6 Facility
Location: Los Angeles, California
System: Building 1/36 Interim Action SVE System

WELL ID	DATE	TIME	FLOW RATE (1) (scfm)	VACUUM (inches of H ₂ O)	WELLHEAD FID (2) (ppmv)	COMMENTS
1-VIEW-15B	3/6/2002	13:40	NA	0.0	NA	Well Closed
	3/29/2002	8:15	NA	0.0	NA	"
	5/17/2002	NA	12	4	12	Well Opened
	5/17/2002	NA	60.5	27	45	"
	5/17/2002	NA	117	72	40	"
	6/3/2002	10:00	74	34	NA	Well Closed
	6/7/02 through 3/11/03		SVE shut down for retrofit			
	3/12/2003		Begin start-up procedures			
	3/24/2003		45	55	104	Well Opened**
	4/1/2003		30	55	52	
	4/16/2003		32	50	55	
	4/29/2003	8:30	29	45	13	
	5/5/2003	8:00	44	49	51	
	5/8/2003	15:30	NM	NM	NM	
	5/12/2003	8:00	35	45	37	
	5/19/2003	15:00	53	41	36	
	6/27/2003	16:00	40	76	73	
	6/30/2003	10:00	40	38	14	
	7/1/2003	8:00	40	10	37	
	7/2/2003	13:30	40	22	43	
	7/3/2003	8:00	40	20	44	
	7/7/2003	9:00	40	25	36	
	7/18/2003	8:42	40	25	31	
	7/24/2003	9:00	40	32	23	
	7/31/2003	8:00	40	30	98	
	8/7/2003	9:30	40	31	16	
	8/14/2003	8:00	40	35	22	
	8/14/2003	8:00	NM	NM	NM	
	8/21/2003	8:30	40	34	27	
	8/21/2003	15:30	NM	NM	NM	
	8/28/2003	6:45	40	31	18	
	9/4/2003	6:50	40	30	13	
	9/4/2003	13:45	NM	NM	NM	
	9/5/2003	11:30	NM	NM	NM	
	9/11/2003	6:30	40	30	12	
	9/11/2003	13:30	NM	NM	NM	
	9/18/2003	7:00	40	30	15	
	9/25/2003	7:00	40	30	13	
	10/2/2003	6:30	40	32	9	
	10/9/2003	9:00	40	30	8	
	10/16/2003	6:00	40	30	7	
	10/23/2003	6:00	40	29	6	
	10/30/2003	6:00	40	20	6	
	11/6/2003	9:00	40	20	5	
	11/26/2003	7:00	40	24	3	
	12/1/2003	9:30	NM	NM	NM	
	12/4/2003	9:30	40	25	0	
	12/11/2003	8:30	40	25	3	
	12/18/2003	8:00	40	22	154	
	12/23/2003	6:00	40	25	16	
	1/5/2004	9:00	NM	NM	NM	
	1/7/2004	8:00	NM	NM	NM	
	1/8/2004	9:00	40	17	5	
	1/15/2004	9:00	40	15	4	
	2/2/2004	9:00	40	20	7	
	2/5/2004	9:00	40	15	4	
	2/12/2004	9:00	40	15	0	
	2/19/2004	9:00	40	15	5	
	2/26/2004	9:30	40	25	4	Well 10% Open
	3/4/2004	7:00	5	12	3	Well 5% Open
	3/11/2004	6:30	5	12	1	Well 5% Open
	3/18/2004	8:30	5	14	3	Well 5% Open
	3/25/2004	6:00	5	14	3	Well 5% Open

TABLE III - WELLFIELD DATA

Site Name: BRC Former C-6 Facility
Location: Los Angeles, California
System: Building 1/36 Interim Action SVE System

WELL ID	DATE	TIME	FLOW RATE (1) (scfm)	VACUUM (inches of H2O)	WELLHEAD FID (2) (ppmv)	COMMENTS
1-VIEW-16A	3/6/2002	13:40	NA	0.0	NA	Well Closed
	3/29/2002	8:15	NA	0.2	NA	"
	5/22/2002	11:43	3.72	11	85	Well Opened
	5/22/2002	14:17	23.9	72	68	"
	5/22/2002	15:41	25.1	82	75	"
	6/3/2002	10:00	18	70	17	"
	6/7/02 through 3/11/03		SVE shut down for retrofit			
	3/12/2003		Begin start-up procedures			
	3/24/2003		32	37	88	Well Opened**
	4/1/2003		16.4	40	16	
	4/16/2003		18	30	24.5	
	4/29/2003	8:30	13	27	6	
	5/5/2003	8:00	22	35	22	
	5/8/2003	15:30	NM	NM	NM	
	5/12/2003	8:00	20	30	7	
	5/19/2003	15:00	27	35	14	Well at 90%
	6/27/2003	16:00	20	7	12	
	6/30/2003	10:00	20	15	17	
	7/1/2003	8:00	20	15	11	
	7/2/2003	13:30	20	15	17	
	7/3/2003	8:00	20	15	14	
	7/7/2003	9:00	20	18	18	
	7/18/2003	8:42	20	17	7	
	7/24/2003	9:00	20	35	6	
	7/31/2003	8:00	20	35	12	
	8/7/2003	9:30	20	34	11	
	8/14/2003	8:00	20	30	15	
	8/14/2003	8:00	NM	NM	NM	
	8/21/2003	8:30	20	37	19	
	8/21/2003	15:30	NM	NM	NM	
	8/28/2003	6:45	20	10	34	
	9/4/2003	6:50	20	33	7	
	9/4/2003	13:45	NM	NM	NM	
	9/5/2003	11:30	NM	NM	NM	
	9/11/2003	6:30	20	34	7	
	9/11/2003	13:30	NM	NM	NM	
	9/18/2003	7:00	20	34	9	
	9/25/2003	7:00	20	33	8	
	10/2/2003	6:30	20	31	2	
	10/9/2003	9:00	20	30	4	
	10/16/2003	6:00	20	31	3	
	10/23/2003	6:00	20	29	3	
	10/30/2003	6:00	20	63	3	
	11/6/2003	9:00	20	34	2	
	11/26/2003	7:00	20	41	2	
	12/1/2003	9:30	NM	NM	NM	
	12/4/2003	9:30	20	40	0	
	12/11/2003	8:30	20	43	1	
	12/18/2003	8:00	20	41	7	
	12/23/2003	6:00	20	43	15	
	1/5/2004	9:00	NM	NM	NM	
	1/7/2004	8:00	NM	NM	NM	
	1/8/2004	9:00	20	50	4	
	1/15/2004	9:00	20	45	3	
	2/2/2004	9:00	20	50	3	
	2/5/2004	9:00	20	50	18	
	2/12/2004	9:00	20	45	0	
	2/19/2004	9:00	20	30	2	
	2/26/2004	9:30	20	38	2	Well 35% Open
	3/4/2004	7:00	5	5	1	Well 10% Open
	3/11/2004	6:30	5	10	0	Well 10% Open
	3/18/2004	8:30	5	10	1	Well 10% Open
	3/25/2004	6:00	5	10	1	Well 10% Open

TABLE III - WELLFIELD DATA

Site Name: BRC Former C-6 Facility
Location: Los Angeles, California
System: Building 1/36 Interim Action SVE System

WELL ID	DATE	TIME	FLOW RATE (1) (scfm)	VACUUM (inches of H ₂ O)	WELLHEAD FID (2) (ppmv)	COMMENTS
1-VIEW-16B	3/6/2002	13:40	NA	0.0	NA	Well Closed
	3/29/2002	8:15	NA	0.5	NA	"
	5/17/2002	NA	3.6	11	510	Well Opened
	5/17/2002	NA	16.1	25	650	"
	5/17/2002	NA	39.3	74	610	"
	6/3/2002	10:00	22	65	80	"
	6/7/02 through 3/11/03		SVE shut down for retrofit			
	3/12/2003		Begin start-up procedures			
	3/24/2003		37	50	1,400	Well Opened**
	4/1/2003		21	50	630	
	4/16/2003		27	40	475	
	4/29/2003	8:30	23	35	240	
	5/5/2003	8:00	20	40	643	
	5/8/2003	15:30	NM	NM	NM	
	5/12/2003	8:00	19	38	433	
	5/19/2003	15:00	26	42	352	
	6/27/2003	16:00	20	52	465	
	6/30/2003	10:00	20	37	341	
	7/1/2003	8:00	20	38	310	
	7/2/2003	13:30	20	40	423	
	7/3/2003	8:00	20	36	394	
	7/7/2003	9:00	20	45	353	
	7/18/2003	8:42	20	43	170	
	7/24/2003	9:00	20	48	238	
	7/31/2003	8:00	20	52	132	
	8/7/2003	9:30	20	50	194	
	8/14/2003	8:00	20	50	21	
	8/14/2003	8:00	NM	NM	NM	
	8/21/2003	8:30	20	52	246	
	8/21/2003	15:30	NM	NM	NM	
	8/28/2003	6:45	20	48	185	
	9/4/2003	6:50	20	58	139	
	9/4/2003	13:45	NM	NM	NM	
	9/5/2003	11:30	NM	NM	NM	
	9/11/2003	6:30	20	59	166	
	9/11/2003	13:30	NM	NM	NM	
	9/18/2003	7:00	20	59	146	
	9/25/2003	7:00	20	61	146	
	10/2/2003	6:30	20	57	107	
	10/9/2003	9:00	20	56	93	
	10/16/2003	6:00	20	54	99	
	10/23/2003	6:00	20	53	85	
	10/30/2003	6:00	20	67	88	
	11/6/2003	9:00	20	65	74	
	11/26/2003	7:00	20	70	122	
	12/1/2003	9:30	NM	NM	NM	
	12/4/2003	9:30	20	70	123	
	12/11/2003	8:30	20	70	155	
	12/18/2003	8:00	20	60	252	
	12/23/2003	6:00	20	65	125	
	1/5/2004	9:00	NM	NM	NM	
	1/7/2004	8:00	NM	NM	NM	
	1/8/2004	9:00	20	43	116	
	1/15/2004	9:00	20	43	88	
	2/2/2004	9:00	20	40	106	
	2/5/2004	9:00	20	40	116	
	2/12/2004	9:00	20	41	105	
	2/19/2004	9:00	20	40	93	
	2/26/2004	9:30	20	49	92	Well 35% Open
	3/4/2004	7:00	20	48	86	Well 35% Open
	3/11/2004	6:30	20	55	82	Well 35% Open
	3/18/2004	8:30	20	50	43	Well 35% Open
	3/25/2004	6:00	20	50	47	Well 35% Open

TABLE III - WELLFIELD DATA

Site Name: BRC Former C-6 Facility
Location: Los Angeles, California
System: Building 1/36 Interim Action SVE System

WELL ID	DATE	TIME	FLOW RATE (1) (scfm)	VACUUM (inches of H ₂ O)	WELLHEAD FID (2) (ppmv)	COMMENTS
1-VIEW-17A	3/6/2002	13:40	NA	0.0	NA	Well Closed
	3/29/2002	8:15	NA	0.1	NA	"
	5/22/2002	12:00	6.55	7	24	Well Opened
	5/22/2002	13:57	29.2	35	9.5	"
	5/22/2002	15:54	58.5	80	5.6	"
	6/3/2002	10:00	NA	NA	NA	Well Closed
6/7/02 through 3/11/03		SVE shut down for retrofit Begin start-up procedures				
	3/12/2003		37	50	5	Well Opened**
	4/1/2003		38	50	1.4	
	4/16/2003		74	45	24	
	4/29/2003	8:30	95	44	13	
	5/5/2003	8:00	83	45	3	
	5/8/2003	15:30	NM	NM	NM	
	5/12/2003	8:00	89	42	3	
	5/19/2003	15:00	94	39	3	
	6/27/2003	16:00	40	8	9	
	6/30/2003	10:00	40	6	2	
	7/1/2003	8:00	40	10	5	
	7/2/2003	13:30	40	7	5	
	7/3/2003	8:00	40	5	10	
	7/7/2003	9:00	40	10	5	
	7/18/2003	8:42	40	11	2	
	7/24/2003	9:00	40	20	1	
	7/31/2003	8:00	40	20	4	
	8/7/2003	9:30	40	18	3	
	8/14/2003	8:00	40	16	5	
	8/14/2003	8:00	NM	NM	NM	
	8/21/2003	8:30	40	11	10	
	8/21/2003	15:30	NM	NM	NM	
	8/28/2003	6:45	40	10	5	
	9/4/2003	6:50	40	10	3	
	9/4/2003	13:45	NM	NM	NM	
	9/5/2003	11:30	NM	NM	NM	
	9/11/2003	6:30	40	9	2	
	9/11/2003	13:30	NM	NM	NM	
	9/18/2003	7:00	40	9	5	
	9/25/2003	7:00	40	8	3	
	10/2/2003	6:30	40	9	3	
	10/9/2003	9:00	40	9	1	
	10/16/2003	6:00	40	8	0	
	10/23/2003	6:00	40	7	0	Well Closed
	10/30/2003	6:00	NM	NM	NM	Well Closed
	11/6/2003	9:00	NM	NM	NM	Well Closed
	11/26/2003	7:00	NM	NM	NM	Well Closed
	12/1/2003	9:30	NM	NM	NM	Well Closed
	12/4/2003	9:30	NM	NM	NM	Well Closed
	12/11/2003	8:30	NM	NM	NM	Well Closed
	12/18/2003	8:00	NM	NM	NM	Well Closed
	12/23/2003	6:00	NM	NM	NM	Well Closed
	1/5/2004	9:00	NM	NM	NM	
	1/7/2004	8:00	NM	NM	NM	
	1/8/2004	9:00	NM	NM	NM	Well Closed
	1/15/2004	9:00	NM	NM	NM	Well Closed
	2/2/2004	9:00	NM	NM	NM	Well Closed
	2/5/2004	9:00	5	5	0	
	2/12/2004	9:00	5	5	0	
	2/19/2004	9:00	5	5	2	
	2/26/2004	9:30	5	10	1	Well 10% Open
	3/4/2004	7:00	5	7	0	Well 10% Open
	3/11/2004	6:30	5	7	0	Well 10% Open
	3/18/2004	8:30	5	5	1	Well 10% Open
	3/25/2004	6:00	5	5	1	Well 10% Open

TABLE III - WELLFIELD DATA

Site Name: BRC Former C-6 Facility
Location: Los Angeles, California
System: Building 1/36 Interim Action SVE System

WELL ID	DATE	TIME	FLOW RATE (1) (scfm)	VACUUM (inches of H ₂ O)	WELLHEAD FID (2) (ppmv)	COMMENTS
1-VIEW-17B	3/6/2002	13:40	NA	0.0	NA	Well Closed
	3/29/2002	8:15	NA	0.2	NA	"
	5/17/2002	NA	4.5	6	110	Well Opened
	5/17/2002	NA	24.2	36	110	"
	5/17/2002	NA	41.5	72	110	"
	6/3/2002	10:00	40	58	6	"
	6/7/02 through 3/11/03		SVE shut down for retrofit			
	3/12/2003		Begin start-up procedures			
	3/24/2003		30	55	21	Well Opened**
	4/1/2003		25	55	21.5	
	4/16/2003		24	45	31	
	4/29/2003	8:30	32	43	8	
	5/5/2003	8:00	34	50	21	
	5/8/2003	15:30	NM	NM	NM	
	5/12/2003	8:00	26	45	12	
	5/19/2003	15:00	41	46	9	
	6/27/2003	16:00	40	70	27	
	6/30/2003	10:00	40	51	9	
	7/1/2003	8:00	40	58	39	
	7/2/2003	13:30	40	48	13	
	7/3/2003	8:00	40	40	16	
	7/7/2003	9:00	40	48	9	
	7/18/2003	8:42	40	48	5	
	7/24/2003	9:00	40	52	4	
	7/31/2003	8:00	40	52	7	
	8/7/2003	9:30	40	50	4	
	8/14/2003	8:00	40	50	7	
	8/14/2003	8:00	NM	NM	NM	
	8/21/2003	8:30	40	53	12	
	8/21/2003	15:30	NM	NM	NM	
	8/28/2003	6:45	40	49	6	
	9/4/2003	6:50	40	50	4	
	9/4/2003	13:45	NM	NM	NM	
	9/5/2003	11:30	NM	NM	NM	
	9/11/2003	6:30	40	49	2	
	9/11/2003	13:30	NM	NM	NM	
	9/18/2003	7:00	40	50	6	
	9/25/2003	7:00	40	48	4	
	10/2/2003	6:30	40	54	3	
	10/9/2003	9:00	40	54	2	
	10/16/2003	6:00	40	53	1	
	10/23/2003	6:00	40	50	0	Well Closed
	10/30/2003	6:00	NM	NM	NM	Well Closed
	11/6/2003	9:00	NM	NM	NM	Well Closed
	11/26/2003	7:00	NM	NM	NM	Well Closed
	12/1/2003	9:30	NM	NM	NM	Well Closed
	12/4/2003	9:30	NM	NM	NM	Well Closed
	12/11/2003	8:30	NM	NM	NM	Well Closed
	12/18/2003	8:00	NM	NM	NM	Well Closed
	12/23/2003	6:00	NM	NM	NM	Well Closed
	1/5/2004	9:00	NM	NM	NM	
	1/7/2004	8:00	NM	NM	NM	
	1/8/2004	9:00	NM	NM	NM	Well Closed
	1/15/2004	9:00	NM	NM	NM	Well Closed
	2/2/2004	9:00	NM	NM	NM	Well Closed
	2/5/2004	9:00	5	5	0	
	2/12/2004	9:00	5	6	0	
	2/19/2004	9:00	5	6	2	
	2/26/2004	9:30	5	11	1	Well 10% Open
	3/4/2004	7:00	5	10	0	Well 10% Open
	3/11/2004	6:30	5	10	0	Well 10% Open
	3/18/2004	8:30	5	7	2	Well 10% Open
	3/25/2004	6:00	5	7	1	Well 10% Open

TABLE III - WELLFIELD DATA

Site Name: BRC Former C-6 Facility
Location: Los Angeles, California
System: Building 1/36 Interim Action SVE System

WELL ID	DATE	TIME	FLOW RATE (1) (scfm)	VACUUM (inches of H ₂ O)	WELLHEAD FID (2) (ppmv)	COMMENTS
1-VIEW-18A	3/6/2002	13:40	NA	0.0	NA	Well Closed
	3/29/2002	8:15	NA	0.3	NA	"
	5/22/2002	12:18	2.8	33.5	12.2	Well Opened
	5/22/2002	13:45	9.25	72	10.5	"
	5/22/2002	16:08	19.4	80	9.5	"
	6/3/2002	10:00	NA	NA	NA	Well Closed
	6/7/02 through 3/11/03		SVE shut down for retrofit			
	3/12/2003		Begin start-up procedures			
	3/24/2003		40	50	8	Well Opened**
	4/1/2003		33	50	1.2	
	4/16/2003		30	40	355	
	4/29/2003	8:30	31	40	7	
	5/5/2003	8:00	45	45	4	
	5/8/2003	15:30	NM	NM	NM	
	5/12/2003	8:00	30	41	3	
	5/19/2003	15:00	30	41	4	
	6/27/2003	16:00	20	77	6	
	6/30/2003	10:00	30	14	2	
	7/1/2003	8:00	30	20	8	
	7/2/2003	13:30	30	23	9	
	7/3/2003	8:00	30	30	16	
	7/7/2003	9:00	30	22	5	
	7/18/2003	8:42	30	23	2	
	7/24/2003	9:00	30	36	1	
	7/31/2003	8:00	30	35	4	
	8/7/2003	9:30	30	38	3	
	8/14/2003	8:00	30	29	6	
	8/14/2003	8:00	NM	NM	NM	
	8/21/2003	8:30	30	63	12	
	8/21/2003	15:30	NM	NM	NM	
	8/28/2003	6:45	30	58	5	
	9/4/2003	6:50	30	55	2	
	9/4/2003	13:45	NM	NM	NM	
	9/5/2003	11:30	NM	NM	NM	
	9/11/2003	6:30	30	58	1	
	9/11/2003	13:30	NM	NM	NM	
	9/18/2003	7:00	30	57	6	
	9/25/2003	7:00	30	56	4	
	10/2/2003	6:30	30	45	2	
	10/9/2003	9:00	30	43	1	
	10/16/2003	6:00	30	43	0	
	10/23/2003	6:00	30	40	1	Well Closed
	10/30/2003	6:00	NM	NM	NM	Well Closed
	11/6/2003	9:00	NM	NM	NM	Well Closed
	11/26/2003	7:00	NM	NM	NM	Well Closed
	12/1/2003	9:30	NM	NM	NM	Well Closed
	12/4/2003	9:30	NM	NM	NM	Well Closed
	12/11/2003	8:30	NM	NM	NM	Well Closed
	12/18/2003	8:00	NM	NM	NM	Well Closed
	12/23/2003	6:00	NM	NM	NM	Well Closed
	1/5/2004	9:00	NM	NM	NM	
	1/7/2004	8:00	NM	NM	NM	
	1/8/2004	9:00	NM	NM	NM	Well Closed
	1/15/2004	9:00	NM	NM	NM	Well Closed
	2/2/2004	9:00	NM	NM	NM	Well Closed
	2/5/2004	9:00	5	9	2	
	2/12/2004	9:00	5	5	0	
	2/19/2004	9:00	5	5	2	
	2/26/2004	9:30	5	8	1	Well 10% Open
	3/4/2004	7:00	5	7	0	Well 10% Open
	3/11/2004	6:30	5	7	0	Well 10% Open
	3/18/2004	8:30	5	5	1	Well 10% Open
	3/25/2004	6:00	5	5	0	Well 10% Open

TABLE III - WELLFIELD DATA

Site Name: BRC Former C-6 Facility
Location: Los Angeles, California
System: Building 1/36 Interim Action SVE System

WELL ID	DATE	TIME	FLOW RATE (1) (scfm)	VACUUM (inches of H ₂ O)	WELLHEAD FID (2) (ppmv)	COMMENTS
1-VIEW-18B	3/6/2002	13:40	NA	0.2	NA	Well Closed
	3/29/2002	8:15	NA	0.4	NA	"
	5/17/2002	NA	3	2	7.9	Well Opened
	5/17/2002	NA	12.75	16	73	"
	5/17/2002	NA	32.5	72	85	"
	6/3/2002	10:00	32	86	22	"
	6/7/02 through 3/11/03		SVE shut down for retrofit			
	3/12/2003		Begin start-up procedures			
	3/24/2003		48	52	79	Well Opened**
	4/1/2003		26.1	50	8.7	
	4/16/2003		34	45	45	
	4/29/2003	8:30	33	43	11	
	5/5/2003	8:00	73	50	10	
	5/8/2003	15:30	NM	NM	NM	
	5/12/2003	8:00	30	42	7	
	5/19/2003	15:00	45	40	6	
	6/27/2003	16:00	19	79	10	
	6/30/2003	10:00	30	38	4	
	7/1/2003	8:00	30	42	8	
	7/2/2003	13:30	30	46	10	
	7/3/2003	8:00	30	42	15	
	7/7/2003	9:00	30	20	6	
	7/18/2003	8:42	30	37	3	
	7/24/2003	9:00	30	57	2	
	7/31/2003	8:00	30	52	3	
	8/7/2003	9:30	30	48	3	
	8/14/2003	8:00	30	47	5	
	8/14/2003	8:00	NM	NM	NM	
	8/21/2003	8:30	30	50	12	
	8/21/2003	15:30	NM	NM	NM	
	8/28/2003	6:45	30	47	5	
	9/4/2003	6:50	30	45	3	
	9/4/2003	13:45	NM	NM	NM	
	9/5/2003	11:30	NM	NM	NM	
	9/11/2003	6:30	30	47	1.5	
	9/11/2003	13:30	NM	NM	NM	
	9/18/2003	7:00	30	46	6	
	9/25/2003	7:00	30	46	3	
	10/2/2003	6:30	30	43	3	
	10/9/2003	9:00	30	43	1	
	10/16/2003	6:00	30	43	0	
	10/23/2003	6:00	30	40	0	Well Closed
	10/30/2003	6:00	NM	NM	NM	Well Closed
	11/6/2003	9:00	NM	NM	NM	Well Closed
	11/26/2003	7:00	NM	NM	NM	Well Closed
	12/1/2003	9:30	NM	NM	NM	Well Closed
	12/4/2003	9:30	NM	NM	NM	Well Closed
	12/11/2003	8:30	NM	NM	NM	Well Closed
	12/18/2003	8:00	NM	NM	NM	Well Closed
	12/23/2003	6:00	NM	NM	NM	Well Closed
	1/5/2004	9:00	NM	NM	NM	
	1/7/2004	8:00	NM	NM	NM	
	1/8/2004	9:00	NM	NM	NM	Well Closed
	1/15/2004	9:00	NM	NM	NM	Well Closed
	2/2/2004	9:00	NM	NM	NM	Well Closed
	2/5/2004	9:00	5	12	0	
	2/12/2004	9:00	5	10	0	
	2/19/2004	9:00	5	10	2	
	2/26/2004	9:30	5	14	3	Well 15% Open
	3/4/2004	7:00	5	13	0	Well 15% Open
	3/11/2004	6:30	5	13	0	Well 15% Open
	3/18/2004	8:30	5	17	1	Well 15% Open
	3/25/2004	6:00	5	12	1	Well 15% Open

TABLE III - WELLFIELD DATA

Site Name: BRC Former C-6 Facility
Location: Los Angeles, California
System: Building 1/36 Interim Action SVE System

WELL ID	DATE	TIME	FLOW RATE (1) (scfm)	VACUUM (inches of H ₂ O)	WELLHEAD FID (2) (ppmv)	COMMENTS
1-VIEW-19A	3/6/2002	13:40	NA	0.0	NA	Well Closed
	3/29/2002	8:15	NA	0.0	NA	"
	5/22/2002	11:49	6.55	9.5	25.1	Well Opened
	5/22/2002	14:12	35.2	40	13	"
	5/22/2002	15:48	64.5	82	11.7	"
	6/3/2002	10:00	NA	15	NA	Well Closed
	6/7/02 through 3/11/03		SVE shut down for retrofit			
	3/12/2003		Begin start-up procedures			
	3/24/2003		37	55	12	Well Opened**
	4/1/2003		42	55	2.1	
	4/16/2003		29	50	14.5	
	4/29/2003	8:30	32	45	4	
	5/5/2003	8:00	41	45	6	
	5/8/2003	15:30	NM	NM	NM	
	5/12/2003	8:00	44	40	3	
	5/19/2003	15:00	52	45	4	
	6/27/2003	16:00	30	32	6	
	6/30/2003	10:00	30	31	8	
	7/1/2003	8:00	30	33	8	
	7/2/2003	13:30	30	25	14	
	7/3/2003	8:00	30	25	12	
	7/7/2003	9:00	30	25	34	
	7/18/2003	8:42	30	24	3	
	7/24/2003	9:00	30	30	3	
	7/31/2003	8:00	30	25	7	
	8/7/2003	9:30	30	24	5	
	8/14/2003	8:00	30	20	9	
	8/14/2003	8:00	NM	NM	NM	
	8/21/2003	8:30	30	18	13	
	8/21/2003	15:30	NM	NM	NM	
	8/28/2003	6:45	30	18	6	
	9/4/2003	6:50	30	18	5	
	9/4/2003	13:45	NM	NM	NM	
	9/5/2003	11:30	NM	NM	NM	
	9/11/2003	6:30	30	16	4.9	
	9/11/2003	13:30	NM	NM	NM	
	9/18/2003	7:00	30	16	8	
	9/25/2003	7:00	30	16	7	
	10/2/2003	6:30	30	14	3	
	10/9/2003	9:00	30	14	3	
	10/16/2003	6:00	30	14	1	
	10/23/2003	6:00	30	13	1	
	10/30/2003	6:00	30	15	3	
	11/6/2003	9:00	30	23	2	
	11/26/2003	7:00	30	30	3	
	12/1/2003	9:30	NM	NM	NM	
	12/4/2003	9:30	30	30	0	
	12/11/2003	8:30	30	30	1	
	12/18/2003	8:00	30	30	62	
	12/23/2003	6:00	30	30	19	
	1/5/2004	9:00	NM	NM	NM	
	1/7/2004	8:00	NM	NM	NM	
	1/8/2004	9:00	30	30	4	
	1/15/2004	9:00	30	30	4	
	2/2/2004	9:00	30	30	5	
	2/5/2004	9:00	30	30	3	
	2/12/2004	9:00	30	30	0	
	2/19/2004	9:00	30	30	2	
	2/26/2004	9:30	30	39	2	Well 35% Open
	3/4/2004	7:00	5	20	0	Well 5% Open
	3/11/2004	6:30	5	15	0	Well 5% Open
	3/18/2004	8:30	5	15	3	Well 5% Open
	3/25/2004	6:00	5	15	2	Well 5% Open

TABLE III - WELLFIELD DATA

Site Name: BRC Former C-6 Facility
Location: Los Angeles, California
System: Building 1/36 Interim Action SVE System

WELL ID	DATE	TIME	FLOW RATE (1) (scfm)	VACUUM (inches of H2O)	WELLHEAD FID (2) (ppmv)	COMMENTS
1-VIEW-19B	3/6/2002	13:40	NA	0.6	NA	Well Closed
	3/29/2002	8:15	NA	0.6	NA	"
	5/17/2002	NA	3.5	14	59	Well Opened
	5/17/2002	NA	15.8	34	65	"
	5/17/2002	NA	43.1	74	60	"
	6/3/2002	10:00	16	87	5	"
	6/7/02 through 3/11/03		SVE shut down for retrofit			
	3/12/2003		Begin start-up procedures			
	3/24/2003		35	40	55	Well Opened**
	4/1/2003		17	45	37	
	4/16/2003		30	40	56	
	4/29/2003	8:30	16	32	8	
	5/5/2003	8:00	42	40	15	
	5/8/2003	15:30	NM	NM	NM	
	5/12/2003	8:00	32	35	8	
	5/19/2003	15:00	47	40	9	
	6/27/2003	16:00	20	25	12	
	6/30/2003	10:00	20	22	8	
	7/1/2003	8:00	20	24	9	
	7/2/2003	13:30	20	12	15	
	7/3/2003	8:00	20	10	12	
	7/7/2003	9:00	20	18	16	
	7/18/2003	8:42	20	17	3	
	7/24/2003	9:00	20	52	2	
	7/31/2003	8:00	20	20	4	
	8/7/2003	9:30	20	55	4	
	8/14/2003	8:00	20	40	7	
	8/14/2003	8:00	NM	NM	NM	
	8/21/2003	8:30	20	41	12	
	8/21/2003	15:30	NM	NM	NM	
	8/28/2003	6:45	20	38	6	
	9/4/2003	6:50	20	50	5	
	9/4/2003	13:45	NM	NM	NM	
	9/5/2003	11:30	NM	NM	NM	
	9/11/2003	6:30	20	52	5	
	9/11/2003	13:30	NM	NM	NM	
	9/18/2003	7:00	20	52	8	
	9/25/2003	7:00	20	54	6	
	10/2/2003	6:30	20	50	3	
	10/9/2003	9:00	20	49	32	
	10/16/2003	6:00	20	50	2	
	10/23/2003	6:00	20	48	1	
	10/30/2003	6:00	20	57	3	
	11/6/2003	9:00	20	55	1	
	11/26/2003	7:00	20	60	2	
	12/1/2003	9:30	NM	NM	NM	
	12/4/2003	9:30	20	59	0	
	12/11/2003	8:30	20	60	0	
	12/18/2003	8:00	20	60	69	
	12/23/2003	6:00	20	60	23	
	1/5/2004	9:00	NM	NM	NM	
	1/7/2004	8:00	NM	NM	NM	
	1/8/2004	9:00	20	57	3	
	1/15/2004	9:00	20	55	3	
	2/2/2004	9:00	20	55	4	
	2/5/2004	9:00	20	55	2	
	2/12/2004	9:00	20	50	0	
	2/19/2004	9:00	20	50	2	
	2/26/2004	9:30	20	60	2	Well 35% Open
	3/4/2004	7:00	5	10	0	Well 5% Open
	3/11/2004	6:30	7	12	0	Well 5% Open
	3/18/2004	8:30	7	10	1	Well 5% Open
	3/25/2004	6:00	7	10	1	Well 5% Open

TABLE III - WELLFIELD DATA

Site Name: BRC Former C-6 Facility
Location: Los Angeles, California
System: Building 1/36 Interim Action SVE System

WELL ID	DATE	TIME	FLOW RATE (1) (scfm)	VACUUM (inches of H ₂ O)	WELLHEAD FID (2) (ppmv)	COMMENTS
1-VIEW-20A	3/6/2002	13:40	NA	1.3	NA	Well Closed
	3/29/2002	8:15	NA	0.9	NA	"
	5/22/2002	12:23	2.87	9	11	Well Opened
	5/22/2002	13:39	14.1	31.5	11.8	"
	5/22/2002	16:12	33.1	80	4.2	"
	6/3/2002	10:00	NA	10	NA	Well Closed
	6/7/02 through 3/11/03		SVE shut down for retrofit			
	3/12/2003		Begin start-up procedures			
	4/16/2003		0.00	45	120	
	4/29/2003	8:30	21	42	1	Well Opened***
	5/5/2003	8:00	88	45	5	
	5/8/2003	15:30	NM	NM	NM	
	5/12/2003	8:00	20	42	3	
	5/19/2003	15:00	85	40	3	
	6/27/2003	16:00	NA	NA	NA	Well Closed
	6/30/2003	10:00	20	5	3	
	7/1/2003	8:00	20	5	22	
	7/2/2003	13:30	20	10	8	
	7/3/2003	8:00	20	10	23	
	7/7/2003	9:00	20	10	5	
	7/18/2003	8:42	20	13	3	
	7/24/2003	9:00	20	12	1	
	7/31/2003	8:00	20	12	9	
	8/7/2003	9:30	20	13	3	
	8/14/2003	8:00	20	13	8	
	8/14/2003	8:00	NM	NM	NM	
	8/21/2003	8:30	20	11	9	
	8/21/2003	15:30	NM	NM	NM	
	8/28/2003	6:45	20	10	7	
	9/4/2003	6:50	20	10	2	
	9/4/2003	13:45	NM	NM	NM	
	9/5/2003	11:30	NM	NM	NM	
	9/11/2003	6:30	20	10	1	
	9/11/2003	13:30	NM	NM	NM	
	9/18/2003	7:00	20	10	5	
	9/25/2003	7:00	20	13	3	
	10/2/2003	6:30	20	12	1	
	10/9/2003	9:00	20	13	1	
	10/16/2003	6:00	20	12	0	
	10/23/2003	6:00	20	12	0	Well Closed
	10/30/2003	6:00	NM	NM	NM	Well Closed
	11/6/2003	9:00	NM	NM	NM	Well Closed
	11/26/2003	7:00	NM	NM	NM	Well Closed
	12/1/2003	9:30	NM	NM	NM	Well Closed
	12/4/2003	9:30	NM	NM	NM	Well Closed
	12/11/2003	8:30	NM	NM	NM	Well Closed
	12/18/2003	8:00	NM	NM	NM	Well Closed
	12/23/2003	6:00	NM	NM	NM	Well Closed
	1/5/2004	9:00	NM	NM	NM	
	1/7/2004	8:00	NM	NM	NM	
	1/8/2004	9:00	NM	NM	NM	
	1/15/2004	9:00	NM	NM	NM	Well Closed
	2/2/2004	9:00	NM	NM	NM	Well Closed
	2/5/2004	9:00	5	7	0	
	2/12/2004	9:00	5	6	0	
	2/19/2004	9:00	5	6	2	
	2/26/2004	9:30	5	12	2	Well 15% Open
	3/4/2004	7:00	5	13	0	Well 15% Open
	3/11/2004	6:30	5	13	0	Well 15% Open
	3/18/2004	8:30	5	10	1	Well 15% Open
	3/25/2004	6:00	5	10	0	Well 15% Open

TABLE III - WELLFIELD DATA

Site Name: BRC Former C-6 Facility
Location: Los Angeles, California
System: Building 1/36 Interim Action SVE System

WELL ID	DATE	TIME	FLOW RATE (1) (scfm)	VACUUM (inches of H ₂ O)	WELLHEAD FID (2) (ppmv)	COMMENTS
1-VIEW-20B	3/6/2002	13:40	NA	1.4	NA	Well Closed
	3/29/2002	8:15	NA	1.0	NA	"
	5/17/2002	10:30	2.32	14	100	Well Opened
	5/17/2002	NA	10.7	22	170	"
	5/17/2002	NA	32.6	72	105	"
	6/3/2002	10:00	33	61	18	"
6/7/02 through 3/11/03		SVE shut down for retrofit				
	3/12/2003		Begin start-up procedures			
	4/16/2003		33	40	125	
	4/29/2003	8:30	27	34	39	Well Opened***
	5/5/2003	8:00	43	17	61	
	5/8/2003	15:30	NM	NM	NM	
	5/12/2003	8:00	19	20	37	
	5/19/2003	15:00	72	16	34	
	6/27/2003	16:00	NA	NA	NA	Well Closed
	6/30/2003	10:00	20	25	21	
	7/1/2003	8:00	20	34	51	
	7/2/2003	13:30	20	32	77	
	7/3/2003	8:00	20	40	58	
	7/7/2003	9:00	20	30	41	
	7/18/2003	8:42	20	27	28	
	7/24/2003	9:00	20	30	19	
	7/31/2003	8:00	20	38	45	
	8/7/2003	9:30	20	32	13	
	8/14/2003	8:00	20	10	14	
	8/14/2003	8:00	NM	NM	NM	
	8/21/2003	8:30	20	40	19	
	8/21/2003	15:30	NM	NM	NM	
	8/28/2003	6:45	20	23	13	
	9/4/2003	6:50	20	23	10	
	9/4/2003	13:45	NM	NM	NM	
	9/5/2003	11:30	NM	NM	NM	
	9/11/2003	6:30	20	23	7.9	
	9/11/2003	13:30	NM	NM	NM	
	9/18/2003	7:00	20	29	12	
	9/25/2003	7:00	20	38	17	
	10/2/2003	6:30	20	15	9	
	10/9/2003	9:00	20	15	7	
	10/16/2003	6:00	20	13	6	
	10/23/2003	6:00	20	10	6	
	10/30/2003	6:00	20	30	12	
	11/6/2003	9:00	20	34	7	
	11/26/2003	7:00	20	31	6	
	12/1/2003	9:30	NM	NM	NM	
	12/4/2003	9:30	20	15	3	
	12/11/2003	8:30	20	15	6	
	12/18/2003	8:00	20	38	18	
	12/23/2003	6:00	20	50	14	
	1/5/2004	9:00	NM	NM	NM	
	1/7/2004	8:00	NM	NM	NM	
	1/8/2004	9:00	20	55	14	
	1/15/2004	9:00	20	50	5	
	2/2/2004	9:00	20	52	12	
	2/5/2004	9:00	20	40	9	
	2/12/2004	9:00	20	38	0	
	2/19/2004	9:00	20	41	5	
	2/26/2004	9:30	20	53	3	Well 15% Open
	3/4/2004	7:00	5	18	3	Well 2% Open
	3/11/2004	6:30	5	15	2	Well 2% Open
	3/18/2004	8:30	5	10	2	Well 2% Open
	3/25/2004	6:00	5	10	1	Well 2% Open

TABLE III - WELLFIELD DATA

Site Name: BRC Former C-6 Facility
Location: Los Angeles, California
System: Building 1/36 Interim Action SVE System

WELL ID	DATE	TIME	FLOW RATE (1) (scfm)	VACUUM (inches of H ₂ O)	WELLHEAD FID (2) (ppmv)	COMMENTS
1-VIEW-21A	3/6/2002	13:40	NA	NA	NA	Well Closed
	3/29/2002	8:15	NA	NA	NA	"
	5/16/2002	NA	3.57	39	3040	Well Opened
	5/16/2002	NA	5.4	48	3200	"
	5/16/2002	NA	37.7	96	2900	"
	6/3/2002	10:00	28	55	NA	"
	6/7/02 through 3/11/03		SVE shut down for retrofit			
	3/12/2003		Begin start-up procedures			
	4/16/2003		36	40	7200	
	4/29/2003	8:30	26	45	3400	Well Opened***
	5/5/2003	8:00	24	55	+10,000	
	5/8/2003	15:30	NM	NM	NM	
	5/12/2003	8:00	25	40	3,050	
	5/19/2003	15:00	33	40	1,630	
	6/27/2003	16:00	NA	NA	NA	Well Closed
	6/30/2003	10:00	NA	NA	NA	Well Closed
	7/1/2003	8:00	NA	NA	NA	Well Closed
	7/2/2003	13:30	NA	NA	NA	Well Closed
	7/3/2003	8:00	NA	NA	NA	Well Closed
	7/7/2003	9:00	NA	NA	NA	Well Closed
	7/18/2003	8:42	NA	NA	NA	Well Closed
	7/24/2003	9:00	NA	NA	NA	Well Closed
	7/31/2003	8:00	NA	NA	NA	Well Closed
	8/7/2003	9:30	NA	NA	NA	Well Closed
	8/14/2003	8:00	NA	NA	NA	Well Closed
	8/14/2003	8:00	NA	NA	NA	Well Closed
	8/21/2003	8:30	NA	NA	NA	Well Closed
	8/21/2003	15:30	NA	NA	NA	Well Closed
	8/28/2003	6:45	NA	NA	NA	Well Closed
	9/4/2003	6:50	NA	NA	NA	Well Closed
	9/4/2003	13:45	10	NM	54	Well Reopened per H&A
	9/5/2003	11:30	NM	NM	NM	
	9/11/2003	6:30	10	33	63	
	9/11/2003	13:30	NM	NM	NM	
	9/18/2003	7:00	10	33	86	
	9/25/2003	7:00	10	32	89	
	10/2/2003	6:30	10	30	66	
	10/9/2003	9:00	10	25	84	
	10/16/2003	6:00	10	22	24	
	10/23/2003	6:00	10	18	44	
	10/30/2003	6:00	10	23	15	
	11/6/2003	9:00	10	19	7	
	11/26/2003	7:00	10	15	0	
	12/1/2003	9:30	NM	NM	NM	
	12/4/2003	9:30	10	15	0	
	12/11/2003	8:30	10	14	0	
	12/18/2003	8:00	10	12	4	
	12/23/2003	6:00	10	12	15	
	1/5/2004	9:00	NM	NM	NM	
	1/7/2004	8:00	NM	NM	NM	
	1/8/2004	9:00	10	10	3	
	1/15/2004	9:00	10	9	5	
	2/2/2004	9:00	10	10	3	
	2/5/2004	9:00	10	10	2	
	2/12/2004	9:00	10	10	0	
	2/19/2004	9:00	10	10	3	
	2/26/2004	9:30	10	20	1	Well 10% Open
	3/4/2004	7:00	5	14	0	Well 5% Open
	3/11/2004	6:30	5	14	0	Well 5% Open
	3/18/2004	8:30	5	10	2	Well 5% Open
	3/25/2004	6:00	5	10	1	Well 5% Open

TABLE III - WELLFIELD DATA

Site Name: BRC Former C-6 Facility
Location: Los Angeles, California
System: Building 1/36 Interim Action SVE System

WELL ID	DATE	TIME	FLOW RATE (1) (scfm)	VACUUM (inches of H ₂ O)	WELLHEAD FID (2) (ppmv)	COMMENTS
1-VIEW-21B	3/6/2002	13:40	NA	NA	NA	Well Closed
	3/29/2002	8:15	NA	NA	NA	"
	5/20/2002	13:22	1.74	15	700	Well Opened
	5/20/2002	15:28	4.5	45	1030	"
	5/20/2002	17:24	36.3	79	1725	"
	5/21/2002	9:55	48.3	92	1200	"
	6/3/2002	10:00	47	90	NA	"
6/7/02 through 3/11/03		SVE shut down for retrofit Begin start-up procedures				
	3/12/2003		35	45	2670	
	4/16/2003	8:30	31	45	4650	Well Opened***
	5/5/2003	8:00	92	50	+10,000	
	5/8/2003	15:30	NM	NM	NM	
	5/12/2003	8:00	11	40	+10,000	
	5/19/2003	15:00	36	40	+10,000	
	6/27/2003	16:00	NA	NA	NA	Well Closed
	6/30/2003	10:00	NA	NA	NA	Well Closed
	7/1/2003	8:00	NA	NA	NA	Well Closed
	7/2/2003	13:30	NA	NA	NA	Well Closed
	7/3/2003	8:00	NA	NA	NA	Well Closed
	7/7/2003	9:00	NA	NA	NA	Well Closed
	7/18/2003	8:42	NA	NA	NA	Well Closed
	7/24/2003	9:00	NA	NA	NA	Well Closed
	7/31/2003	8:00	NA	NA	NA	Well Closed
	8/7/2003	9:30	NA	NA	NA	Well Closed
	8/14/2003	8:00	NA	NA	NA	Well Closed
	8/14/2003	8:00	NA	NA	NA	Well Closed
	8/21/2003	8:30	NA	NA	NA	Well Closed
	8/21/2003	15:30	NA	NA	NA	Well Closed
	8/28/2003	6:45	NA	NA	NA	Well Closed
	9/4/2003	6:50	NA	NA	NA	Well Closed
	9/4/2003	13:45	10	NM	71	Well Reopened per H&A
	9/5/2003	11:30	NM	NM	NM	
	9/11/2003	6:30	10	50	+10000	
	9/11/2003	13:30	NM	NM	NM	
	9/18/2003	7:00	10	50	+10000	
	9/25/2003	7:00	10	38	+10000	
	10/2/2003	6:30	10	35	4,835	
	10/9/2003	9:00	30	35	4,454	Well 100% Open
	10/16/2003	6:00	14	53	4,798	
	10/23/2003	6:00	15	50	4,380	
	10/30/2003	6:00	15	55	3,890	
	11/6/2003	9:00	15	68	6,208	
	11/26/2003	7:00	15	45	+10000	
	12/1/2003	9:30	NM	NM	NM	
	12/4/2003	9:30	15	49	+10000	
	12/11/2003	8:30	15	58	+10000	
	12/18/2003	8:00	15	54	+10000	
	12/23/2003	6:00	15	58	4,801	
	1/5/2004	9:00	NM	NM	NM	
	1/7/2004	8:00	NM	NM	NM	
	1/8/2004	9:00	15	34	4,194	
	1/15/2004	9:00	15	56	+10000	
	2/2/2004	9:00	15	25	3,879	
	2/5/2004	9:00	15	50	+10000	Well 100% Open
	2/12/2004	9:00	15	50	+10000	Well 100% Open
	2/19/2004	9:00	15	50	+10000	Well 100% Open
	2/26/2004	9:30	15	55	+10000	Well 100% Open
	3/4/2004	7:00	15	55	+10000	Well 100% Open
	3/11/2004	6:30	15	60	+10000	Well 100% Open
	3/18/2004	8:30	15	60	+10000	Well 100% Open
	3/25/2004	6:00	15	60	+10000	Well 100% Open

TABLE III - WELLFIELD DATA

Site Name: BRC Former C-6 Facility
Location: Los Angeles, California
System: Building 1/36 Interim Action SVE System

WELL ID	DATE	TIME	FLOW RATE (1) (scfm)	VACUUM (inches of H ₂ O)	WELLHEAD FID (2) (ppmv)	COMMENTS
1-VIEW-22A	3/6/2002	13:40	NA	5.0	NA	Well Closed
	3/29/2002	8:15	NA	3.1	NA	"
	5/16/2002	NA	3.1	28	2200	Well Opened
	5/16/2002	NA	10.6	52	2400	"
	5/16/2002	NA	18.05	92	1600	"
	6/3/2002	10:00	18	74	80	"
	6/7/02 through 3/11/03		SVE shut down for retrofit			
	3/12/2003		Begin start-up procedures			
	4/16/2003		15.5	40	450	
	4/29/2003	8:30	37	41	296	Well Opened***
	5/5/2003	8:00	72	58	445	
	5/8/2003	15:30	NM	NM	NM	
	5/12/2003	8:00	11	40	330	
	5/19/2003	15:00	65	36	368	
	6/27/2003	16:00	NA	NA	NA	Well Closed
	6/30/2003	10:00	30	38	262	
	7/1/2003	8:00	30	61	202	
	7/2/2003	13:30	NA	NA	NA	Well Closed
	7/3/2003	8:00	NA	NA	NA	Well Closed
	7/7/2003	9:00	NA	NA	NA	Well Closed
	7/18/2003	8:42	NA	NA	NA	Well Closed
	7/24/2003	9:00	NA	NA	NA	Well Closed
	7/31/2003	8:00	NA	NA	NA	Well Closed
	8/7/2003	9:30	NA	NA	NA	Well Closed
	8/14/2003	8:00	NA	NA	NA	Well Closed
	8/14/2003	8:00	NA	NA	NA	Well Closed
	8/21/2003	8:30	NA	NA	NA	Well Closed
	8/21/2003	15:30	20	54	310	Well Opened per H&A
	8/28/2003	6:45	30	55	193	Well Open
	9/4/2003	6:50	30	54	621	
	9/4/2003	13:45	NM	NM	NM	
	9/5/2003	11:30	NM	NM	NM	
	9/11/2003	6:30	30	55	3,102	
	9/11/2003	13:30	NM	NM	NM	
	9/18/2003	7:00	30	55	6,300	
	9/25/2003	7:00	22	52	3,683	
	10/2/2003	6:30	25	50	1,229	
	10/9/2003	9:00	25	50	743	
	10/16/2003	6:00	25	46	287	
	10/23/2003	6:00	25	45	136	
	10/30/2003	6:00	25	60	167	
	11/6/2003	9:00	25	60	95	
	11/26/2003	7:00	25	66	261	
	12/1/2003	9:30	NM	NM	NM	
	12/4/2003	9:30	25	65	260	
	12/11/2003	8:30	25	66	159	
	12/18/2003	8:00	25	63	79	
	12/23/2003	6:00	25	66	87	
	1/5/2004	9:00	NM	NM	NM	
	1/7/2004	8:00	NM	NM	NM	
	1/8/2004	9:00	25	65	158	
	1/15/2004	9:00	25	60	81	
	2/2/2004	9:00	25	65	84	
	2/5/2004	9:00	25	65	102	Well 100% Open
	2/12/2004	9:00	25	60	32	Well 100% Open
	2/19/2004	9:00	25	60	77	Well 100% Open
	2/26/2004	9:30	25	70	27	Well 100% Open
	3/4/2004	7:00	25	65	27	Well 100% Open
	3/11/2004	6:30	25	65	1	Well 100% Open
	3/18/2004	8:30	25	78	11	Well 100% Open
	3/25/2004	6:00	25	78	16	Well 100% Open

TABLE III - WELLFIELD DATA

Site Name: BRC Former C-6 Facility
Location: Los Angeles, California
System: Building 1/36 Interim Action SVE System

WELL ID	DATE	TIME	FLOW RATE (1) (scfm)	VACUUM (inches of H ₂ O)	WELLHEAD FID (2) (ppmv)	COMMENTS
1-VIEW-22B	3/6/2002	13:40	NA	5.1	NA	Well Closed
	3/29/2002	8:15	NA	3.1	NA	"
	5/20/2002	13:30	4.12	16	37	Well Opened
	5/20/2002	15:20	21.1	40	72	"
	5/20/2002	17:35	37	77	179	"
	5/21/2002	10:07	43.6	91	230	"
	6/3/2002	10:00	51	88	20	"
6/7/02 through 3/11/03		SVE shut down for retrofit Begin start-up procedures				
	3/12/2003		20	45	16	
	4/16/2003		24	47	24	Well Opened***
	4/29/2003	8:30	70	53	23	
	5/5/2003	8:00	NM	NM	NM	
	5/8/2003	15:30				
	5/12/2003	8:00	30	45	3	
	5/19/2003	15:00	39	43	38	
	6/27/2003	16:00	NA	NA	NA	Well Closed
	6/30/2003	10:00	30	30	9	
	7/1/2003	8:00	30	28	4	
	7/2/2003	13:30	30	30	7	
	7/3/2003	8:00	30	30	13	
	7/7/2003	9:00	30	31	7	
	7/18/2003	8:42	30	33	9	
	7/24/2003	9:00	30	28	10	
	7/31/2003	8:00	30	30	19	
	8/7/2003	9:30	30	30	4	
	8/14/2003	8:00	30	28	7	
	8/14/2003	8:00	NM	NM	NM	
	8/21/2003	8:30	30	35	17	
	8/21/2003	15:30	NM	NM	NM	
	8/28/2003	6:45	30	35	8	
	9/4/2003	6:50	30	48	11	
	9/4/2003	13:45	NM	NM	NM	
	9/5/2003	11:30	NM	NM	NM	
	9/11/2003	6:30	30	45	340	
	9/11/2003	13:30	NM	NM	NM	
	9/18/2003	7:00	30	48	155	
	9/25/2003	7:00	30	47	48	
	10/2/2003	6:30	30	45	56	
	10/9/2003	9:00	30	43	26	
	10/16/2003	6:00	30	38	4	
	10/23/2003	6:00	30	32	16	
	10/30/2003	6:00	30	42	6	
	11/6/2003	9:00	30	32	0	
	11/26/2003	7:00	30	53	0	
	12/1/2003	9:30	NM	NM	NM	
	12/4/2003	9:30	30	52	0	
	12/11/2003	8:30	30	51	0	
	12/18/2003	8:00	30	50	0	
	12/23/2003	6:00	30	52	3	
	1/5/2004	9:00	NM	NM	NM	
	1/7/2004	8:00	NM	NM	NM	
	1/8/2004	9:00	30	55	83	
	1/15/2004	9:00	30	50	32	
	2/2/2004	9:00	30	54	6	
	2/5/2004	9:00	30	50	8	
	2/12/2004	9:00	30	48	0	
	2/19/2004	9:00	30	48	33	
	2/26/2004	9:30	30	56	2	Well 15% Open
	3/4/2004	7:00	5	20	0	Well 5% Open
	3/11/2004	6:30	5	20	16	Well 5% Open
	3/18/2004	8:30	5	15	1	Well 5% Open
	3/25/2004	6:00	5	15	4	Well 5% Open

TABLE III - WELLFIELD DATA

Site Name: BRC Former C-6 Facility
Location: Los Angeles, California
System: Building 1/36 Interim Action SVE System

WELL ID	DATE	TIME	FLOW RATE (1) (scfm)	VACUUM (inches of H ₂ O)	WELLHEAD FID (2) (ppmv)	COMMENTS
1-VIEW-23A	3/6/2002	13:40	NA	NA	NA	Well Closed
	3/29/2002	8:15	NA	NA	NA	"
	5/16/2002	NA	3.25	20	130	Well Opened
	5/16/2002	NA	12.5	49	45	"
	5/16/2002	NA	21.4	20	35	"
	6/3/2002	10:00	14	40	11	Well Closed
6/7/02 through 3/11/03		SVE shut down for retrofit				
	3/12/2003		Begin start-up procedures			
	4/16/2003		0:00	10	18	
	4/29/2003	8:30	4	7	41	Well Opened***
	5/5/2003	8:00	60	40	22	
	5/8/2003	15:30	NM	NM	NM	
	5/12/2003	8:00	6	10	12	Well at 85%
	5/19/2003	15:00	18	6	1,460	Well at 10%
	6/27/2003	16:00	NA	NA	NA	Well Closed
	6/30/2003	10:00	NA	NA	NA	Well Closed
	7/1/2003	8:00	10	33	1,038	
	7/2/2003	13:30	NA	NA	NA	Well Closed
	7/3/2003	8:00	NA	NA	NA	Well Closed
	7/7/2003	9:00	NA	NA	NA	Well Closed
	7/18/2003	8:42	NA	NA	NA	Well Closed
	7/24/2003	9:00	NA	NA	NA	Well Closed
	7/31/2003	8:00	NA	NA	NA	Well Closed
	8/7/2003	9:30	NA	NA	NA	Well Closed
	8/14/2003	8:00	NA	NA	NA	Well Closed
	8/14/2003	8:00	NA	NA	NA	Well Closed
	8/21/2003	8:30	NA	NA	NA	Well Closed
	8/21/2003	15:30	NA	NA	NA	Well Closed
	8/28/2003	6:45	NA	NA	NA	Well Closed
	9/4/2003	6:50	NA	NA	NA	Well Closed
	9/4/2003	13:45	10	NM	16	Well Reopened per H&A
	9/5/2003	14:00	5	5	NM	
	9/11/2003	6:30	NA	NA	NA	Well Closed
	9/11/2003	13:30	NA	NA	NA	Well Closed
	9/18/2003	7:00	NA	NA	NA	Well Closed
	9/25/2003	7:00	20	33	170	Well Opened @ 20 scfm
	10/2/2003	6:30	20	29	14	
	10/9/2003	9:00	20	25	9	
	10/16/2003	6:00	20	18	4	
	10/23/2003	6:00	20	14	2	
	10/30/2003	6:00	20	21	5	
	11/6/2003	9:00	20	11	0	
	11/26/2003	7:00	20	5	0	
	12/1/2003	9:30	NM	NM	NM	
	12/4/2003	9:30	20	5	0	
	12/11/2003	8:30	20	5	0	
	12/18/2003	8:00	20	5	1	
	12/23/2003	6:00	20	5	7	
	1/5/2004	9:00	NM	NM	NM	
	1/7/2004	8:00	NM	NM	NM	
	1/8/2004	9:00	20	25	11	
	1/15/2004	9:00	20	12	4	
	2/2/2004	9:00	20	14	5	
	2/5/2004	9:00	20	14	8	
	2/12/2004	9:00	20	10	0	
	2/19/2004	9:00	20	10	0	
	2/26/2004	9:30	20	63	43	Well 10% Open
	3/4/2004	7:00	12	55	35	Well 10% Open
	3/11/2004	6:30	12	55	657	Well 10% Open
	3/18/2004	8:30	12	25	49	Well 10% Open
	3/25/2004	6:00	12	20	4	Well 10% Open

TABLE III - WELLFIELD DATA

Site Name: BRC Former C-6 Facility
Location: Los Angeles, California
System: Building 1/36 Interim Action SVE System

WELL ID	DATE	TIME	FLOW RATE (1) (scfm)	VACUUM (inches of H ₂ O)	WELLHEAD FID (2) (ppmv)	COMMENTS
1-VIEW-23B	3/6/2002	13:40	NA	NA	NA	Well Closed
	3/29/2002	8:15	NA	NA	NA	"
	5/20/2002	13:16	2.67	15	46	Well Opened
	5/20/2002	15:38	10	23	1700	"
	5/20/2002	17:08	19.5	79	9000	"
	5/21/2002	9:48	46.3	94	8000	"
	6/3/2002	10:00	37	90	600	"
6/7/02 through 3/11/03		SVE shut down for retrofit Begin start-up procedures				
	3/12/2003		23	40	>10000	
	4/16/2003	8:30	33	43	>9999	Well Opened***
	5/5/2003	8:00	75	45	+10,000	
	5/8/2003	15:30	NM	NM	NM	
	5/12/2003	8:00	11	40	+10,000	
	5/19/2003	15:00	24	40	+10,000	
	6/27/2003	16:00	NA	NA	NA	Well Closed
	6/30/2003	10:00	NA	NA	NA	Well Closed
	7/1/2003	8:00	20	35	+10000	
	7/2/2003	13:30	NA	NA	NA	Well Closed
	7/3/2003	8:00	NA	NA	NA	Well Closed
	7/7/2003	9:00	NA	NA	NA	Well Closed
	7/18/2003	8:42	NA	NA	NA	Well Closed
	7/24/2003	9:00	NA	NA	NA	Well Closed
	7/31/2003	8:00	NA	NA	NA	Well Closed
	8/7/2003	9:30	NA	NA	NA	Well Closed
	8/14/2003	8:00	NA	NA	NA	Well Closed
	8/14/2003	8:00	NA	NA	NA	Well Closed
	8/21/2003	8:30	NA	NA	NA	Well Closed
	8/21/2003	15:30	NA	NA	NA	Well Closed
	8/28/2003	6:45	NA	NA	NA	Well Closed
	9/4/2003	6:50	NA	NA	NA	Well Closed
	9/4/2003	13:45	10	NM	+10000	Well Reopened per H&A
	9/5/2003	14:00	5	11	NM	
	9/11/2003	6:30	NA	NA	NA	Well Closed
	9/11/2003	13:30	NA	NA	NA	Well Closed
	9/18/2003	7:00	8	25	+10000	
	9/25/2003	7:00	8	29	+10000	
	10/2/2003	6:30	8	29	+10000	
	10/9/2003	9:00	11	30	+10000	
	10/16/2003	6:00	12	45	+10000	
	10/23/2003	6:00	19	54	+10000	
	10/30/2003	6:00	15	66	+10000	
	11/6/2003	9:00	15	67	+10000	
	11/20/2003	10:00	NA	NA	NA	Well Closed
	11/26/2003	7:00	NA	NA	NA	Well Closed
	12/1/2003	9:30	11	35	+10000	Well Opened
	12/4/2003	9:30	11	35	+10000	
	12/11/2003	8:30	11	33	+10000	
	12/18/2003	8:00	15	30	+10000	
	12/23/2003	6:00	15	48	+10000	
	1/5/2004	9:00	NM	NM	NM	
	1/7/2004	8:00	NM	NM	NM	
	1/8/2004	9:00	15	10	+10000	
	1/15/2004	9:00	14	25	+10000	
	2/2/2004	9:00	14	5	+10000	
	2/5/2004	9:00	14	13	+10000	
	2/12/2004	9:00	14	12	+10000	
	2/19/2004	9:00	14	20	+10000	
	2/26/2004	9:30	14	24	+10000	Well 10% Open
	3/4/2004	7:00	17	25	+10000	Well 5% Open
	3/11/2004	6:30	17	25	+10000	Well 30% Open
	3/18/2004	8:30	17	25	+10000	Well 30% Open
	3/25/2004	6:00	17	28	+10000	Well 100% Open

TABLE III - WELLFIELD DATA

Site Name: BRC Former C-6 Facility
Location: Los Angeles, California
System: Building 1/36 Interim Action SVE System

WELL ID	DATE	TIME	FLOW RATE (1) (scfm)	VACUUM (inches of H ₂ O)	WELLHEAD FID (2) (ppmv)	COMMENTS
1-VIEW-24A	1/18/2002	10:40	NA	88	> 9,999 *	
	1/24/2002	11:00	NA	75	> 9,999 *	"
	1/31/2002	13:45	33	23	> 9,999	"
	2/7/2002	16:50	31	26	> 9,999	"
	2/15/2002	17:51	NA	NA	> 9,999 *	"
	2/21/2002	17:44	46.5	30	> 9,999	"
	2/27/2002	14:17	32	30	> 9,999	"
	3/6/2002	13:40	94	64	> 9,999	"
	3/13/2002	16:20	45	30	> 9,999	"
	3/20/2002	8:30	42	32	> 9,999	"
	3/29/2002	8:15	9	28	4,000	"
	5/16/2002	NA	8.85	24	450	"
	5/16/2002	NA	33.7	42	550	"
	5/16/2002	NA	77.5	90	520	"
	6/3/2002	10:00	43	56	55	"
	6/7/02 through 3/11/03		SVE shut down for retrofit			
	3/12/2003		Begin start-up procedures			
	4/16/2003		35	45	190	
	4/29/2003	8:30	35	45	60	Well Opened***
	5/5/2003	8:00	70.3	53	145	
	5/8/2003	15:30	NM	NM	NM	
	5/12/2003	8:00	42	43	132	
	5/19/2003	15:00	43	42	81	
	6/27/2003	16:00	NA	NA	NA	Well Closed
	6/30/2003	10:00	30	36	4	
	7/1/2003	8:00	30	34	129	
	7/2/2003	13:30	30	27	124	
	7/3/2003	8:00	30	30	324	
	7/7/2003	9:00	30	30	2,181	
	7/18/2003	8:42	30	47	+10000	
	7/24/2003	9:00	30	35	5,084	
	7/31/2003	8:00	30	35	8,641	
	8/7/2003	9:30	30	35	+10000	
	8/14/2003	8:00	30	34	+10000	
	8/14/2003	8:00	NA	NA	NA	Well Closed
	8/21/2003	8:30	NA	NA	NA	Well Closed
	8/21/2003	15:30	30	35	194	Well Opened per H&A
	8/28/2003	6:45	30	39	+10000	Well Opened
	9/4/2003	6:50	30	38	+10000	
	9/4/2003	13:45	10	NM	+10000	Well Rechecked per H&A
	9/5/2003	13:00	5	15	NM	
	9/11/2003	6:30	NA	NA	NA	Well Closed
	9/11/2003	13:30	10	20	117	Well Opened per H&A
	9/18/2003	7:00	10	22	3,221	
	9/25/2003	7:00	10	21	1,197	
	10/2/2003	6:30	10	20	323	
	10/9/2003	9:00	10	20	136	
	10/16/2003	6:00	10	20	14	
	10/23/2003	6:00	10	16	14	
	10/30/2003	6:00	10	20	8	
	11/6/2003	9:00	10	21	0	
	11/26/2003	7:00	10	18	0	
	12/1/2003	9:30	NM	NM	NM	
	12/4/2003	9:30	10	15	0	
	12/11/2003	8:30	10	12	0	
	12/18/2003	8:00	10	10	2	
	12/23/2003	6:00	10	10	22	
	1/5/2004	9:00	NM	NM	NM	
	1/7/2004	8:00	NM	NM	NM	
	1/8/2004	9:00	10	10	24	
	1/15/2004	9:00	10	10	3	
	2/2/2004	9:00	10	9	8	
	2/5/2004	9:00	10	10	10	
	2/12/2004	9:00	10	10	0	
	2/19/2004	9:00	10	10	1	
	2/26/2004	9:30	10	25	1	Well 10% Open
	3/4/2004	7:00	7	20	0	Well 5% Open
	3/11/2004	6:30	7	17	0	Well 5% Open
	3/18/2004	8:30	7	15	1	Well 5% Open
	3/25/2004	6:00	7	15	3	Well 5% Open

TABLE III - WELLFIELD DATA

Site Name: BRC Former C-6 Facility
Location: Los Angeles, California
System: Building 1/36 Interim Action SVE System

WELL ID	DATE	TIME	FLOW RATE (1) (scfm)	VACUUM (inches of H2O)	WELLHEAD FID (2) (ppmv)	COMMENTS
1-VIEW-24B	12/13/2001	15:00	10	54	> 9,999 *	Well opened
	12/20/2001	14:15	5	47	> 800 *	"
	1/3/2002	13:15	32	48	> 320 *	"
	1/10/2002	14:00	30	48	> 700 *	"
	1/18/2002	8:25	25	90	> 760 *	"
	1/18/2002	10:40	NA	90	> 2,500 *	"
	1/24/2002	11:00	93	90	> 9,999 *	"
	1/31/2002	13:45	9	23	> 9,999	"
	2/7/2002	16:50	9	26	> 9,999	"
	2/15/2002	17:51	NA	NA	> 9,999 *	"
	2/21/2002	17:44	11	30	> 9,999	"
	2/27/2002	14:17	8	31	> 9,999	"
	3/6/2002	13:40	13	64	> 9,999	"
	3/13/2002	16:20	10.5	30	> 9,999	"
	3/20/2002	8:30	5.8	32	> 9,999	"
	3/29/2002	8:15	38	28	> 9,999	"
	5/20/2002	13:43	1.08	15	42	"
	5/20/2002	15:10	4.4	41	490	"
	5/20/2002	17:45	28.4	77	1010	"
	5/21/2002	10:16	41.4	91	635	"
	6/3/2002	10:00	30	70	100	"
	6/7/02 through 3/11/03			SVE shut down for retrofit		
	3/12/2003			Begin start-up procedures		
	4/16/2003		32	47	1675	
	4/29/2003	8:30	28	48	733	Well Opened***
	5/5/2003	8:00	69.9	50	4,170	
	5/8/2003	15:30	NM	NM	NM	
	5/12/2003	8:00	21	46	1,705	
	5/19/2003	15:00	46	44	1,942	
	6/27/2003	16:00	NA	NA	NA	Well Closed
	6/30/2003	10:00	20	78	1,610	
	7/1/2003	8:00	20	79	1,960	
	7/2/2003	13:30	NA	NA	NA	Well Closed
	7/3/2003	8:00	NA	NA	NA	Well Closed
	7/7/2003	9:00	NA	NA	NA	Well Closed
	7/18/2003	8:42	NA	NA	NA	Well Closed
	7/24/2003	9:00	NA	NA	NA	Well Closed
	7/31/2003	8:00	NA	NA	NA	Well Closed
	8/7/2003	9:30	NA	NA	NA	Well Closed
	8/14/2003	8:00	NA	NA	NA	Well Closed
	8/14/2003	8:00	NA	NA	NA	Well Closed
	8/21/2003	8:30	NA	NA	NA	Well Closed
	8/21/2003	15:30	NA	NA	NA	Well Closed
	8/28/2003	6:45	NA	NA	NA	Well Closed
	9/4/2003	6:50	NA	NA	NA	Well Closed
	9/4/2003	13:45	10	NM	+10000	Well Reopened per H&A
	9/5/2003	13:00	5	27	NM	
	9/11/2003	6:30	NA	NA	NA	Well Closed
	9/11/2003	13:30	10	30	+10000	Well Opened per H&A
	9/18/2003	7:00	10	63	+10000	
	9/25/2003	7:00	10	60	+10000	
	10/2/2003	6:30	10	58	+10000	
	10/9/2003	9:00	10	56	+10000	Well 100% Open
	10/16/2003	6:00	7	54	6,010	
	10/23/2003	6:00	17	54	2,396	
	10/30/2003	6:00	15	68	2,172	
	11/6/2003	9:00	15	68	813	
	11/26/2003	7:00	15	74	378	
	12/1/2003	9:30	NM	NM	NM	
	12/4/2003	9:30	15	75	249	
	12/11/2003	8:30	15	73	161	
	12/18/2003	8:00	15	70	66	
	12/23/2003	6:00	15	73	93	
	1/5/2004	9:00	NM	NM	NM	
	1/7/2004	8:00	NM	NM	NM	
	1/8/2004	9:00	20	74	200	
	1/15/2004	9:00	20	70	90	
	2/2/2004	9:00	20	75	128	
	2/5/2004	9:00	20	75	200	Well 100% Open
	2/12/2004	9:00	20	68	49	Well 100% Open
	2/19/2004	9:00	20	68	65	Well 100% Open
	2/26/2004	9:30	20	75	19	Well 100% Open
	3/4/2004	7:00	20	83	30	Well 100% Open
	3/11/2004	6:30	20	87	18	Well 100% Open
	3/18/2004	8:30	20	85	12	Well 100% Open
	3/25/2004	6:00	20	85	15	Well 100% Open

TABLE III - WELLFIELD DATA

Site Name: BRC Former C-6 Facility
Location: Los Angeles, California
System: Building 1/36 Interim Action SVE System

WELL ID	DATE	TIME	FLOW RATE (1) (scfm)	VACUUM (inches of H ₂ O)	WELLHEAD FID (2) (ppmv)	COMMENTS
1-VIEW-25A	3/6/2002	13:40	NA	5.5	NA	Well Closed
	3/29/2002	8:15	NA	3.7	NA	"
	5/16/2002	NA	2.68	23	125	Well Opened
	5/16/2002	NA	13.5	44	135	"
	5/16/2002	NA	28	90	120	"
	6/3/2002	10:00	25	46	45	"
	6/7/02 through 3/11/03		SVE shut down for retrofit			
	3/12/2003		Begin start-up procedures			
	3/24/2003		41	32	110	Well Opened**
	4/1/2003		12	30	49	
	4/16/2003		0.00	30	90	
	4/29/2003	8:30	19	30	88	
	5/5/2003	8:00	32	40	52	
	5/8/2003	15:30	NM	NM	NM	
	5/12/2003	8:00	57	38	165	
	5/19/2003	15:00	24	37	178	
	6/27/2003	16:00	20	52	159	
	6/30/2003	10:00	20	25	54	
	7/1/2003	8:00	22	20	177	
	7/2/2003	13:30	20	25	88	
	7/3/2003	8:00	20	26	79	
	7/7/2003	9:00	20	20	47	
	7/18/2003	8:42	20	23	28	
	7/24/2003	9:00	20	20	14	
	7/31/2003	8:00	20	20	34	
	8/7/2003	9:30	20	18	17	
	8/14/2003	8:00	20	15	39	
	8/14/2003	8:00	NM	NM	NM	
	8/21/2003	8:30	20	9	40	
	8/21/2003	15:30	NM	NM	NM	
	8/28/2003	6:45	20	10	49	
	9/4/2003	6:50	20	8	54	
	9/4/2003	13:45	NM	NM	NM	
	9/5/2003	11:30	NM	NM	NM	
	9/11/2003	6:30	20	8	40	
	9/11/2003	13:30	NM	NM	NM	
	9/18/2003	7:00	20	5	61	
	9/25/2003	7:00	20	4	20	
	10/2/2003	6:30	20	5	46	
	10/9/2003	9:00	20	3	10	
	10/16/2003	6:00	20	3	11	
	10/23/2003	6:00	20	3	9	
	10/30/2003	6:00	20	5	2	
	11/6/2003	9:00	20	5	4	
	11/26/2003	7:00	20	5	0	
	12/1/2003	9:30	NM	NM	NM	
	12/4/2003	9:30	20	5	0	
	12/11/2003	8:30	20	5	0	
	12/18/2003	8:00	20	5	3	
	12/23/2003	6:00	20	5	5	
	1/5/2004	9:00	NM	NM	NM	
	1/7/2004	8:00	NM	NM	NM	
	1/8/2004	9:00	20	5	14	
	1/15/2004	9:00	20	5	2	
	2/2/2004	9:00	20	5	4	
	2/5/2004	9:00	20	5	5	
	2/12/2004	9:00	20	5	0	
	2/19/2004	9:00	20	5	1	
	2/26/2004	9:30	20	15	1	Well 10% Open
	3/4/2004	7:00	8	5	0	Well 2% Open
	3/11/2004	6:30	8	5	0	Well 2% Open
	3/18/2004	8:30	8	5	0	Well 2% Open
	3/25/2004	6:00	8	5	3	Well 2% Open

TABLE III - WELLFIELD DATA

Site Name: BRC Former C-6 Facility
Location: Los Angeles, California
System: Building 1/36 Interim Action SVE System

WELL ID	DATE	TIME	FLOW RATE (1) (scfm)	VACUUM (inches of H ₂ O)	WELLHEAD FID (2) (ppmv)	COMMENTS
1-VIEW-25B	3/6/2002	13:40	NA	5.9	NA	Well Closed
	3/29/2002	8:15	NA	3.5	NA	"
	5/18/2002	10:17	1.36	23	280	Well Opened
	5/18/2002	12:30	3.75	35.5	370	"
	5/18/2002	14:23	7.65	61	310	"
	6/3/2002	10:00	19	45	185	"
	6/7/02 through 3/11/03		SVE shut down for retrofit			
	3/12/2003		Begin start-up procedures			
	4/1/2003		7.5	30	620	
	4/16/2003		12	25	8.1	
	4/29/2003	8:30	14	36	12	Well Opened***
	5/5/2003	8:00	42	55	1,350	
	5/8/2003	15:30	NM	NM	NM	
	5/12/2003	8:00	33	42	732	
	5/19/2003	15:00	37	42	740	
	6/27/2003	16:00	17	79	810	
	6/30/2003	10:00	20	50	535	
	7/1/2003	8:00	20	30	712	
	7/2/2003	13:30	20	35	689	
	7/3/2003	8:00	20	32	762	
	7/7/2003	9:00	20	42	680	
	7/18/2003	8:42	20	41	346	
	7/24/2003	9:00	20	37	451	
	7/31/2003	8:00	20	40	398	
	8/7/2003	9:30	20	36	350	
	8/14/2003	8:00	20	36	441	
	8/14/2003	8:00	NM	NM	NM	
	8/21/2003	8:30	20	37	502	
	8/21/2003	15:30	NM	NM	NM	
	8/28/2003	6:45	20	57	437	
	9/4/2003	6:50	20	58	350	
	9/4/2003	13:45	NM	NM	NM	
	9/5/2003	11:30	NM	NM	NM	
	9/11/2003	6:30	20	60	295	
	9/11/2003	13:30	NM	NM	NM	
	9/18/2003	7:00	20	59	344	
	9/25/2003	7:00	15	57	289	
	10/2/2003	6:30	15	55	242	
	10/9/2003	9:00	20	53	190	
	10/16/2003	6:00	20	50	212	
	10/23/2003	6:00	20	49	165	
	10/30/2003	6:00	20	65	166	
	11/6/2003	9:00	20	65	193	
	11/26/2003	7:00	20	70	180	
	12/1/2003	9:30	NM	NM	NM	
	12/4/2003	9:30	20	70	184	
	12/11/2003	8:30	20	71	204	
	12/18/2003	8:00	20	68	167	
	12/23/2003	6:00	20	70	220	
	1/5/2004	9:00	NM	NM	NM	
	1/7/2004	8:00	NM	NM	NM	
	1/8/2004	9:00	20	72	173	
	1/15/2004	9:00	20	65	152	
	2/2/2004	9:00	20	65	143	
	2/5/2004	9:00	20	65	194	Well 100% Open
	2/12/2004	9:00	20	65	126	Well 100% Open
	2/19/2004	9:00	20	18	126	Well 100% Open
	2/26/2004	9:30	20	18	108	Well 100% Open
	3/4/2004	7:00	20	18	127	Well 100% Open
	3/11/2004	6:30	20	18	81	Well 100% Open
	3/18/2004	8:30	20	16	59	Well 100% Open
	3/25/2004	6:00	20	16	65	Well 100% Open

TABLE III - WELLFIELD DATA

Site Name: BRC Former C-6 Facility
Location: Los Angeles, California
System: Building 1/36 Interim Action SVE System

WELL ID	DATE	TIME	FLOW RATE (1) (scfm)	VACUUM (inches of H ₂ O)	WELLHEAD FID (2) (ppmv)	COMMENTS
1-VIEW-26A	3/6/2002	13:40	NA	3.7	NA	Well Closed
	3/29/2002	8:15	NA	2.7	NA	"
	5/16/2002	10:50	5.45	37	95	Well Opened
	5/16/2002	NA	24.5	90	190	"
	5/16/2002	NA	33.5	>100	95	"
	6/3/2002	10:00	55	85	105	"
	6/7/02 through 3/11/03		SVE shut down for retrofit			
	3/12/2003		Begin start-up procedures			Well Opened
	4/1/2003		16	50	145	
	4/16/2003		34	45	91	
	4/29/2003	8:30	20	43	68	Well Opened***
	5/5/2003	8:00	27	45	60	
	5/8/2003	15:30	NM	NM	NM	
	5/12/2003	8:00	15	40	168	
	5/19/2003	15:00	33	40	176	
	6/27/2003	16:00	15	76	154	
	6/30/2003	10:00	21	75	109	
	7/1/2003	8:00	23	75	209	
	7/2/2003	13:30	30	79	146	
	7/3/2003	8:00	30	75	163	
	7/7/2003	9:00	30	80	171	
	7/18/2003	8:42	30	78	42	
	7/24/2003	9:00	30	62	107	
	7/31/2003	8:00	30	65	43	
	8/7/2003	9:30	30	65	96	
	8/14/2003	8:00	30	60	108	
	8/14/2003	8:00	NM	NM	NM	
	8/21/2003	8:30	30	62	122	
	8/21/2003	15:30	NM	NM	NM	
	8/28/2003	6:45	30	58	132	
	9/4/2003	6:50	30	56	95	
	9/4/2003	13:45	NM	NM	NM	
	9/5/2003	11:30	NM	NM	NM	
	9/11/2003	6:30	30	58	86	
	9/11/2003	13:30	NM	NM	NM	
	9/18/2003	7:00	30	58	104	
	9/25/2003	7:00	30	55	74	
	10/2/2003	6:30	30	52	67	
	10/9/2003	9:00	30	52	49	
	10/16/2003	6:00	30	50	49	
	10/23/2003	6:00	30	48	44	
	10/30/2003	6:00	30	0	46	
	11/6/2003	9:00	30	0	50	
	11/26/2003	7:00	30	67	42	
	12/1/2003	9:30	NM	NM	NM	
	12/4/2003	9:30	30	66	44	
	12/11/2003	8:30	30	65	50	
	12/18/2003	8:00	30	66	38	
	12/23/2003	6:00	30	65	103	
	1/5/2004	9:00	NM	NM	NM	
	1/7/2004	8:00	NM	NM	NM	
	1/8/2004	9:00	23	70	93	
	1/15/2004	9:00	23	65	57	
	2/2/2004	9:00	23	68	51	
	2/5/2004	9:00	23	65	62	Well 100% Open
	2/12/2004	9:00	23	60	35	Well 100% Open
	2/19/2004	9:00	23	60	44	Well 100% Open
	2/26/2004	9:30	23	68	25	Well 100% Open
	3/4/2004	7:00	23	68	26	Well 100% Open
	3/11/2004	6:30	23	70	19	Well 100% Open
	3/18/2004	8:30	23	79	16	Well 100% Open
	3/25/2004	6:00	23	79	22	Well 100% Open

TABLE III - WELLFIELD DATA

Site Name: BRC Former C-6 Facility
Location: Los Angeles, California
System: Building 1/36 Interim Action SVE System

WELL ID	DATE	TIME	FLOW RATE (1) (scfm)	VACUUM (inches of H ₂ O)	WELLHEAD FID (2) (ppmv)	COMMENTS
1-VIEW-26B	3/6/2002	13:40	NA	3.8	NA	Well Closed
	3/29/2002	8:15	NA	2.8	NA	"
	5/18/2002	NA	5.15	19.5	260	Well Opened
	5/18/2002	NA	23	35	280	"
	5/18/2002	NA	43.6	61	240	"
	6/3/2002	10:00	24	36	60	"
	6/7/02 through 3/11/03		SVE shut down for retrofit			
	3/12/2003		Begin start-up procedures			
	4/1/2003		27.5	65	322	
	4/16/2003		19	35	220	
	4/29/2003	8:30	22	34	193	Well Opened***
	5/5/2003	8:00	39	60	50	
	5/8/2003	15:30	NM	NM	NM	
	5/12/2003	8:00	30	36	258	Well at 50%
	5/19/2003	15:00	33	35	270	"
	6/27/2003	16:00	30	38	380	
	6/30/2003	10:00	30	40	253	
	7/1/2003	8:00	30	42	369	
	7/2/2003	13:30	30	40	352	
	7/3/2003	8:00	30	40	353	
	7/7/2003	9:00	30	45	311	
	7/18/2003	8:42	30	44	143	
	7/24/2003	9:00	30	36	281	
	7/31/2003	8:00	30	40	177	
	8/7/2003	9:30	30	38	245	
	8/14/2003	8:00	30	36	279	
	8/14/2003	8:00	NM	NM	NM	
	8/21/2003	8:30	30	37	331	
	8/21/2003	15:30	NM	NM	NM	
	8/28/2003	6:45	30	35	280	
	9/4/2003	6:50	30	35	199	
	9/4/2003	13:45	NM	NM	NM	
	9/5/2003	11:30	NM	NM	NM	
	9/11/2003	6:30	30	35	200	
	9/11/2003	13:30	NM	NM	NM	
	9/18/2003	7:00	30	35	216	
	9/25/2003	7:00	30	40	179	
	10/2/2003	6:30	30	39	132	
	10/9/2003	9:00	30	39	109	
	10/16/2003	6:00	30	38	110	
	10/23/2003	6:00	30	35	86	
	10/30/2003	6:00	30	43	115	
	11/6/2003	9:00	30	43	131	
	11/26/2003	7:00	30	49	104	
	12/1/2003	9:30	NM	NM	NM	
	12/4/2003	9:30	30	46	110	
	12/11/2003	8:30	30	50	119	
	12/18/2003	8:00	30	48	93	
	12/23/2003	6:00	30	50	175	
	1/5/2004	9:00	NM	NM	NM	
	1/7/2004	8:00	NM	NM	NM	
	1/8/2004	9:00	30	46	150	
	1/15/2004	9:00	30	46	95	
	2/2/2004	9:00	30	45	129	
	2/5/2004	9:00	30	43	133	
	2/12/2004	9:00	30	45	92	
	2/19/2004	9:00	30	45	109	
	2/26/2004	9:30	30	55	64	Well 100% Open
	3/4/2004	7:00	30	52	68	Well 50% Open
	3/11/2004	6:30	30	52	58	Well 50% Open
	3/18/2004	8:30	30	56	47	Well 50% Open
	3/25/2004	6:00	30	56	60	Well 50% Open

Notes:

ppmv: parts per million by volume

scfm: standard cubic foot per minute (acf m corrected for vacuum and temperature)

NA: data was not recorded or available

* Well head readings not taken. Estimates based on diluted inlet concentrations

(1) Direct flow readings taken by hand-held TSI Veloci-calc Plus

(2) Measurements taken with a Foxboro OVA FID calibrated to 100 ppmv Hexane, results as Hexane

** Well opened between 3/12/03 and 3/24/03 as part of start-up procedures. Data provided was collected on 3/24/03

*** Well opened between 3/25/03 and 4/15/03 during re-start procedures. Data provided was collected on 4/29/03

TABLE IV - MEK ANALYTICAL RESULTS

Site Name: BRC Former C-6 Facility
Location: Los Angeles, California
System: Building 1/36 SVE System

WELL ID	MEK CONCENTRATIONS (ppmV)		
	Static (Pre-Start) 18-Dec-2002	Prior to Retrofit Start-up March/April 2003	26-Feb-2004
1-VEW-1	N/S	ND	N/S
1-VEW-2	N/S	ND	N/S
1-VEW-3	N/S	ND	N/S
1-VEW-4	N/S	ND	N/S
1-VEW-5	N/S	ND	N/S
1-VEW-6	52	ND	N/S
1-VEW-7	ND	ND	N/S
1-VEW-8A	ND	ND	N/S
1-VEW-8B	ND	ND	N/S
1-VEW-9	13	15	16
1-VEW-10A	22	0.0026 J	ND
1-VEW-10B	0.44	4.8 J	74
1-VEW-11A	0.29	ND	0.19
1-VEW-11B	ND	ND	0.38
1-VEW-12	ND	ND	ND
1-VEW-13A	N/S	ND	N/S
1-VEW-13B	N/S	ND	N/S
1-VEW-14A	N/S	ND	N/S
1-VEW-14B	N/S	ND	N/S
1-VEW-15A	N/S	ND	N/S
1-VEW-15B	N/S	ND	N/S
1-VEW-16A	N/S	ND	N/S
1-VEW-16B	N/S	ND	N/S
1-VEW-17A	N/S	ND	N/S
1-VEW-17B	N/S	ND	N/S
1-VEW-18A	0.46	0.0044 J	N/S
1-VEW-18B	0.35	ND	N/S
1-VEW-19A	25	ND	1.2
1-VEW-19B	65	ND	0.85
1-VEW-20A	0.03	ND	0.45
1-VEW-20B	ND	ND	0.38
1-VEW-21A	620	550	0.05
1-VEW-21B	160	110	950
1-VEW-22A	0.15	ND	N/S
1-VEW-22B	0.12	ND	N/S
1-VEW-23A	14	0.012 J	0.35
1-VEW-23B	29	320	2200
1-VEW-24A	ND	ND	ND
1-VEW-24B	ND	5.0 J	0.3
1-VEW-25A	ND	ND	N/S
1-VEW-25B	0.1	ND	N/S
1-VEW-26A	N/S	ND	N/S
1-VEW-26B	N/S	ND	N/S

Notes:


ppmV: Parts per million by volume

J: Estimated


ND: Not Detected

N/S: Not Sampled


GRAPH 1
MONTHLY PERCENT OPERATION



GRAPH 2
SVE SYSTEM TOTAL DILUTED VOC INFLUENT CONCENTRATION
(LABORATORY DATA)



GRAPH 3
CUMULATIVE VOLATILE ORGANIC COMPOUND MASS REMOVED



MAINTENANCE LOG

Site Name: BRC Former C-6 Facility
Location: Los Angeles, California
System: Building 1/36 Interim Action SVE System

DATE	MAINTENANCE ACTIVITY
7/2/2001	Pilot system started
8/17/2001	One GAC vessel was changed out (8,000 lbs), system shut down contingent to potential move to C-1
9/11/2001	System restarted
10/1/2001	System shutdown and wells abandoned for site grading
11/29/2001	New well installed and re-piped to system
12/13/2001	System restarted
12/20/2001	System shutdown, GAC breakthrough
12/28/2001	One GAC vessel was changed out (8,000 lbs), system restarted
1/31/2002	System shutdown, GAC breakthrough
2/6/2002	One GAC vessel was changed out (8,000 lbs), system restarted
2/21/2002	System shutdown, GAC breakthrough
2/27/2002	One GAC vessel was changed out (8,000 lbs), system restarted
3/8/2002	System shutdown, GAC breakthrough, one GAC vessel was changed out (8,000 lbs), system restarted
3/29/2002	Pilot system shutdown and removed, GAC breakthrough, install 1,000 scfm unit
4/17/2002	One GAC vessel (8,000 lbs) changed out in preparation for 1000 scfm unit
5/15/2002	1000 scfm unit installed and started, South vessel as primary carbon
5/18/2002	System shutdown, west vessel switched into primary position, system restarted
5/21/2002	South GAC vessel was changed out (8,000 lbs), system restarted, south vessel as primary carbon
5/27/2002	System shut down, GAC breakthrough
5/29/2002	South and West GAC vessel were changed out (16,000 lbs), system restarted, west vessel as primary carbon
6/3/2002	North vessel as primary and south vessel as secondary carbon, system modifications installed
6/7/2002	System shutdown due to apparent vandalism
6/12/2002	GAC overheating discovered. Quenched with water
6/13/2002	Additional GAC quenching. GAC removed from all three vessels
8/1/2002 - 9/30/2002	Bidding and procurement for retrofit
10/30/2002	Notice to proceed for retrofit contractor
11/13/2002	Complete water line installation
12/3/2002	Deliver GAC vessels with retrofits
12/10/2002	Equipment and electrical installation
12/23/2002 - 1/2/2003	Holiday shutdown period
1/3/2003	System modification and pre-startup testing
3/12/2003	Begin start-up procedures: System operating during working hours while extraction wells are brought on-line
3/14/2003	Continuing start-up procedures: SVE is left to run continuously. More wells are brought on line.
3/24/2003	One GAC vessel was changed out (8,000 lbs), system restarted
3/31/2003	System shut down while waiting for carbon regeneration, GAC breakthrough during start-up procedures.
4/1/2003	Carbon in vessels V-2 and V-3 was replaced (approx 16,000 lbs) and the system restarted.
4/3/2003	Vessel V-4 made the primary and vessel V-3 the secondary.
4/7/2003	Start turning on category 1 wells (wells with expected MEK concentrations)
4/11/2003	Removed 30 gallons of water that accumulated in wellfield piping.
4/15/2003	Water placed in on-site water storage tank.
4/16/2003	Breakthrough from primary vessel (V-4). Vessel V-3 made the primary and Vessel 2 the secondary
4/21/2003	Finished opening wells for re-start up procedures: all wells open. Carbon in vessel V-4 replaced (8,000 lbs).
4/25/2003	Breakthrough from primary vessel V-3. Vessel V-2 made the primary and vessel V-4 the secondary.
4/29/2003	Carbon in vessel V-3 replaced (8,000 lbs.).
5/5/2003	Breakthrough from vessel V-2. Vessel V-4 made the primary and vessel V-3 the secondary.
5/6/2003	Carbon stored on-site while carbon is re-profiled as all wells are now on-line
5/8/2003	Carbon in vessel V-2 replaced (approx 6,500 lbs.).
5/12/2003	Operation and Maintenance of SVE system turned over to Wayne Perry. Breakthrough of primary vessel (V3).
5/14/2003	Change carbon in primary (V3) and secondary (V2) vessels.
5/19/2003	Meeting with Value Engineering to obtain access to PLC program. Check system.
5/21/2003	O&M of system by WPI, breakthrough on primary vessel (V2). Changed primary vessel to V4 and secondary to V3.
5/22/2003	Carbon change vessel (V2).
6/27/2003	O&M by WPI, breakthrough of primary vessel (V4), changed primary to V3 and secondary to V2.
7/1/2003	Carbon change vessel (V4).
7/2/2003	System shut down due to AQMD permit compliance issues. System remains shut down.
7/31/2003	Reviewed start-up check list.
8/7/2003	Raised exhaust stack from 12.5 to 14 feet.
8/14/2003	Blower motor was unstuck.
8/21/2003	Drained water from carbon canisters prior to start up.
8/28/2003	System shut down pending carbon change out.
9/4/2003	Carbon in V-2 and V-3 was replaced. V-4 was changed to primary and V-3 was changed to secondary.
9/4/2003	Breakthrough from primary vessel (V-4). Vessel V-3 made the primary and Vessel 2 the secondary.
9/4/2003	Carbon in V-4 was replaced. Greased motor and blower. Checked blower oil.
9/4/2003	Breakthrough from primary vessel (V-3). Vessel V-2 was changed to primary and V-4 the secondary.
9/4/2003	Carbon in V-3 replaced with 7 sacks of carbon. Secondary vessel changed from V-4 to V-3
9/4/2003	Per H&A Squire, WPI closed VEW24A at 08:00. Carbon in V-2 replaced with 7 sacks of carbon.
9/4/2003	Per H&A Squire, WPI opened Wells VEW22A and VEW24A. WPI also rechecked the following wells at H&A's direction: VEW9, VEW10B, VEW11B, VEW22A and VEW24A. VOC readings were taken after wells were opened.
9/4/2003	Carbon in V-3 replaced with 7 sacks of carbon. Primary vessel changed from V-3 to V-2. Water pump making noise may need to be replaced.
9/4/2003	Computer screen not working and was unable to get temperatures on carbon tanks.
9/4/2003	Pump that removes water from carbon tanks still not working.
9/4/2003	Changed flows on VEW9, VEW11B and VEW24A. Opened and set flow at 10 for wells VEW21A, VEW21B, VEW23A, VEW23B and VEW24B per H&A.
9/5/2003	H&A is working on resolving computer issue which is still not working so there are no temperature readings.

Site Name: BRC Former C-6 Facility
Location: Los Angeles, California
System: Building 1/36 Interim Action SVE System

DATE	MAINTENANCE ACTIVITY
9/5/2003	Adjusted wells per H&A: VEW9, VEW11B, VEW23A, VEW23B, VEW24A and VEW24B lowered flow to 5. Opened VEW24A, VEW24B to 10 scfm eff at 325 scfm. Opened VEW23B to 10 scfm eff at 1250 scfm. Closed VEW23B, VEW24A and VEW24B and left system running.
9/11/2003	Primary vessel changed from V-2 to V-4. Carbon in V-2 was replaced with 7 sacks of carbon. Opened VEW24A and VEW24B and set at 10 scfm per H&A.
9/18/2003	Primary vessel changed from V-4 to V-3. Carbon in V-4 was replaced with 7 sacks of carbon per H&A. Opened VEW23B. WPI reduced scfm to 8.25 that lowered undiluted influent to 845.
9/25/2003	Primary vessel changed from V-3 to V-2. Opened VEW23A at 20 scfm. Changed scfm on VEW9, VEW10B and VEW 11B from 10 to 20 scfm.
10/9/2003	Per Haley & Aldrich, WPI opened Wells VEW-9, 10B, 21B and 24B to 100% to raise influent concentrations to 860 ppmv and opened VEW-23B to 11 scfm. No carbon change occurred. Primary vessel changed from V-2 to V-4 and secondary vessel from V-4 to V-3.
10/16/2003	No changes at wells. Added 7 sacks of carbon to V-2 and changed primary vessel from V-4 to V-3 and secondary vessel from V-3 to V-2.
10/23/2003	Per Haley & Aldrich, WPI closed Wells VEW 5, 6, 15A, 17A & 18 A&B and 20A. The system was shutdown for 45 minutes to change blower oil and lube bearings. Carbon in V-4 was replaced with 7 sacks of carbon.
10/30/2003	Arrived on site and the system was found not running. Blower was shutdown and alarm was flashing. Checked blower and motor. Re-started system.
11/3/2003	Arrived on site to verify system was in operation per Haley & Aldrich, took system readings at carbon system. Carbon 1 and exhaust exceeded limits, shut down system for carbon change. Changed carbon in V-3 and V-2, placing 7 sacks of carbon in each. Primary vessel was switched from V-3 to V-2 and then to V-4.
11/10/2003	Temperature of carbon tanks was checked.
11/13/2003	Unit had shut down on November 10, 2003 at approximately 3PM. System flooded carbon tanks V-3 and V-2. Berm was found full of water as is storage tanks. Unit will remain down until all water is removed.
11/20/2003	Unit is running on dilution air only. Well field was closed off and then VOC readings were measured at exhaust and after Carbon #1. Later, well field was opened. Per Haley & Aldrich, well VEW-23B was closed. Primary vessel switched from V-4 to V-3.
11/26/2003	Upon departure from site, WPI opened dilution valve to 100% and closed valve to well field per Haley & Aldrich.
12/1/2003	Upon arrival, WPI opened well field valve and closed manual dilution valve. Per Haley & Aldrich, WPI opened 23B to raise influent level to 949, carbon breakthrough was 11.7 and exhaust was 2.8. Water storage tank has 19' of water. SVE system must be pulling water into the knock-out pot and pumping it into the tank. Unauthorized trucks and bikes have been driving around the well field and leaving tracks.
12/4/2003	Primary vessel switched from V-3 to V-2; secondary vessel switched from V-2 to V-4.
12/11/2003	Primary vessel switched from V-2 to V-4; secondary vessel switched from V-4 to V-3. Carbon in V-3 was replaced with 7 sacks of carbon.
12/18/2003	Primary vessel switched from V-4 to V-3; secondary vessel switched from V-3 to V-2. Carbon in V-2 was replaced with 7 sacks of carbon. Per Haley & Aldrich, WPI opened 23B from 11 scfm to 15 scfm to raise influent concentration to the unit.
12/23/2003	Storage tank was pumped out by Boeing. Shut down system and quenched V-3 and V-2. At Boeing's request, WPI shut off main water and power to unit over the holiday period. Carbon in V-4 was replaced with 7 sacks of carbon.
1/5/2004	System re-started after holiday break. Greased blower, pumped water from V-3 and V-2 and compound into storage tank due to rain.
1/7/2004	Completed annual system checklist with Haley & Aldrich.
1/8/2004	Per Haley & Aldrich, WPI set flow on 23B to 12 scfm and on departure from the site, the undiluted inlet was 740 ppmv and Carbon 1 was 12.8 ppmv.
1/12/2004	System called in an alarm, WPI went to check on system and found system to be operating normally. Notified Haley & Aldrich.
1/15/2004	Per Haley & Aldrich, WPI opened VEW23B to raise undiluted influent concentration up to 920 ppmv at departure from site. Changed primary vessel from V-3 to V-2 and secondary vessel from V-2 to V-4.
1/19/2004	WPI was on site for carbon change when it was cancelled by Haley & Aldrich due to construction activities on site.
1/22/2004	WPI arrived on site and found dilution valve was opened on 1/21/04 by Haley & Aldrich due to construction activities during which the water line was broken. Well field is closed. WPI installed a 2 inch water valve per Haley & Aldrich drawing.
1/29/2004	WPI arrived on site to check well field and collect samples. System is currently running on dilution air only. Opened well field to collect lab samples and then returned system to full dilution air only.
2/2/2004	WPI arrived on site to open well field back on line after closing dilution valve. Turned on 2" water line and flushed line. Took apart back flow preventer and cleaned it. Upon departure, influent was at 534 ppmv and Carbon #1 was 9.2 ppmv per Haley & Aldrich.
2/3/2004	WPI arrived on site to verify system was operating correctly. Pumped 50 gallons of water from compound and equipment was operating.
2/5/2004	WPI opened Wells VEW5, VEW6, VEW15A, VEW17A, VEW17B, VEW18A, VEW18B and VEW20A per Haley & Aldrich. WPI also set influent at 851 per Haley & Aldrich and at departure, breakthrough was 7.4 and exhaust was 0.9. Primary vessel was switched from V-2 to V-4; secondary vessel was switched from V-4 to V-3. Carbon was replaced in V-2 and V-3 with 7 sacks of carbon in each vessel.
2/12/2004	WPI changed primary vessel from V-4 to V-3 and secondary vessel from V-3 to V-2.
2/19/2004	Per Haley & Aldrich, WPI set the undiluted influent to 982 and the carbon 1 was 11.5 at departure. Carbon in V-4 was replaced with 7 sacks of carbon.
2/26/2004	Primary vessel was switched from V-3 to V-2 and secondary vessel was switched from V-2 to V-4.
3/4/2004	Primary vessel was switched from V-2 to V-4 and secondary vessel was switched from V-4 to V-3. Carbon was replaced in V-3 with 7 sacks of carbon. Per Haley & Aldrich, WPI reduced the flow from wells VEW10A, VEW11A, VEW12, VEW13A, VEW15B, VEW16A, VEW19A, VEW19B, VEW20B, VEW21A, VEW22B, VEW24A and VEW25A to increase flow from VEW23B.
3/11/2004	Primary vessel was switched from V-4 to V-3 and secondary vessel was switched from V-3 to V-2. Upon departure, WPI measured undiluted influent at 981 ppmv. Carbon was changed in V-2 with 7 sacks of carbon.
3/18/2004	On departure, influent was at 615 and 1-VEW-23B was at 100% open. Carbon 1 was at 6.8 ppmv. WPI called Haley & Aldrich and reviewed all readings and left system running at current settings. 7 sacks of carbon was replaced in V-4.
3/25/2004	On departure, influent was at 958 ppmv and Carbon 1 was 3.9 ppmv. Collected monthly samples. Primary vessel was switched from V-3 to V-2 and secondary vessel was switched from V-2 to V-4.
3/29/2004	System called in an alarm to WPI. Arrived on site and found blower was off and vessels did not quench. WPI tested all fuses which were in working order. Computer was indicating that blower was shut down and dilution valve was fully open. WPI restarted system. System was running upon departure.